

Charges

Item	Description	Unit Cost	Tax	Quantity	Line Total
Electrical		\$5,950.00	X	1	\$\$5,950.00

- Maine Inclusions:

- Upgrade existing 100amp service to 200amps.
- Provide metering and grounding to code.
- Provide (1) new 200amp rated meter enclosure with external disconnect and 8 exterior circuits.
- Provide new rigid riser and weatherhead.
- Provide new SER cable from meter disconnect to panel.
- Provide (1) new 40 space 200amp rated main lug panel.
- Provide whole home surge suppression.
- Provide breakers to match existing.
- Provide (1) new GFCI protected service receptacle at panel.
- Provide water pipe bonding to meter disconnect.
- Provide all coordination with KBLP and AHJ.

Additional Basement Area Work:

Disconnect or make safe electrical wiring within basement including;

receptacles, junction box to exterior pole light, hanging unsecured

wiring, open splice and open dead ends.

Remove un-used wiring.