"When you want it done right"

Accurate Plumbing

ESTIMATE	#32239
ESTIMATE DATE	Sep 24, 2026
SERVICE DATE	Sep 24, 2026
EXPIRATION DATE	Oct 23, 2026
TOTAL	$17,408.00

Meredith Cooper
1010 Elmer St
Chico, CA 95928

(314) 791-9166
meredithjcooper@gmail.com

CONTACT US

3125 Southgate Ln
Chico, CA 95928

(530) 894-1800
info@accurateplumbingservices.net

Service completed by: Cody Daniels

ESTIMATE

Option #1

Service completed by: Cody Daniels

Services	qty	unit price	amount
Sewer line connection/ job details This quote includes all parts and labor This quote is to abandon failed septic system and reroute sewer line around the left side of the home and connect it to the existing city sewer tap connection that is underground provided by the city. We would use a mini excavator and hand digging to dig from the existing cleanout behind the home. We would use 4 inch ABS pipe and fittings as your new drain line all the way to the city connection. By the Home, we would install a new two-way clean out for future service ability Once new drain pipe is laid and connected the trench will be backfilled, and the new pipe will be covered. We are not responsible for any landscaping, irrigation lines, drip lines, etc.. Customer will be responsible for any reconnection's and repairs if we are to dig through the area and run into any irrigation or sprinkler lines Customer is responsible for clearing yard waste and other yard debris from the area before work begins as we will need to have space for the dirt we are excavating and will use it again to backfill To gain access we will need to disconnect the existing picket fence to be able to get the excavator as well as have space for the concrete truck for the second half of the job. On the second day after the initial drain work is complete. We will have a septic pump truck come out and make sure the septic tank is completely empty prior to abandonment, which is a requirement of the county. Once tank is empty on the same day, our concrete truck will come and completely backfill the septic tank with slurry to make it safe and secure. At this time all permit prices are subject to change, depending upon the city requirements, and if there is any price update from them. We will inform you of any updates if we need to make any price changes.	1.0	$0.00	$0.00
P4234-Replace Plastic 4" Sewer Line - Up to5', 5' Deep Description: Replace 4" sewer main up to 5' deep, first 5'. Incudes double sweeping cleanout.	1.0	$1,050.00	$1,050.00
P4234-A4234 Additional 5' increments 4' ABS sewer main Description-4" Sewer main replacement. Each additional 5' increments up to 5' deep in 4" ABS	15.0	$289.00	$4,335.00
Mini Excavator Daily charge for Mini Excavator E-20 per day	1.0	$458.00	$458.00

Tamper Tamper Rental per day	1.0	$163.00	$163.00
On-Site Building Permit Includes one building permit for designated job Cost of permit is subject to change per city/county requirements.	1.0	$525.00	$525.00
Septic abandonment permit This price is subject to change depending on county requirements	1.0	$525.00	$525.00
Encroachment Permit - City of Chico Includes one encroachment permit for designated job Cost of permit is subject to change per city/county requirements.	1.0	$1,500.00	$1,500.00
Slurry delivery This slurry mix is to be installed and pumped into the existing tank. This tank must be empty prior to abandonment. This is county requirements	1.0	$2,450.00	$2,450.00
Septic pump This is the price to pump the tank down prior to slurry	1.0	$1,541.00	$1,541.00
Sewer connection fee This fee is paid by the homeowner to the city of Chico to authorize the company to connect their sewer line from their home to the city sewer line in front of their home. If quote is approved, then customer will pay this fee ahead of time prior to Work beginning. This notice is to let the customer know that it needs to be paid and as soon as customer pays it, this line item will be removed from the quote	1.0	$2,500.00	$2,500.00
P2347-ASSISTANT TO JOB FEE Assistant to job fee per hour 2 helpers for 1 full day	16.0	$146.00	$2,336.00
Fuel Charge Fuel Charge	1.0	$25.00	$25.00

Services subtotal: $17,408.00

Subtotal	$17,408.00
Total	**$17,408.00**

THANK YOU

We appreciate your business and referrals! We strive to provide a five-star experience. If we did not meet your expectations, please contact our office so we can address your concerns.

WORK AUTHORIZATION & PAYMENT

By authorizing the work described on this invoice, the customer agrees to the work performed and the terms stated herein. Customer understands that aged, deteriorated, corroded, or otherwise compromised plumbing fixtures, piping, and components may be damaged or may fail during conventional repair efforts due to their existing condition. Customer agrees that Accurate Plumbing is not responsible for damage or failure resulting from the pre-existing condition of such items. Payment for all authorized work, materials, and services is due upon completion unless otherwise agreed in writing.

WARRANTY

Accurate Plumbing warrants services performed for one (1) year from the date of service, except drain cleaning services, which are warranted for ninety (90) days. Warranty coverage does not apply to damage caused by rodents, pre-existing conditions, or continued deterioration or failure of plumbing components not included in the authorized repair. Repairs to pre-existing conditions are not warranted where the underlying condition remains

unresolved. All warranties are void if payment is not made when due.

NON-COVERED SERVICES

Accurate Plumbing does not perform drywall, stucco, flooring, trim, painting, landscaping, or other restoration work unless specifically stated on the invoice or authorized in writing.