



Walker County Subdivision Regulations

EFFECTIVE: 6/16/2025

Resolution & Order # 2025-77

THE STATE OF TEXAS §
 § KNOW ALL MEN BY THESE PRESENTS:
COUNTY OF WALKER §

THAT ON THIS, **16th Day of June 2025**, the Commissioners Court of Walker County, Texas, met in duly called and convened lawful Session at the County Courthouse in Huntsville, Texas, with the following members present:

Colt Christian	County Judge
Danny Kuykendall	Commissioner, Precinct One
Ronnie White	Commissioner, Precinct Two
Bill Daugette	Commissioner, Precinct Three
Brandon Decker	Commissioner, Precinct Four

And at said meeting, among other business, came up for consideration and adoption the following Resolution and Order:


WHEREAS, the Commissioners Court of Walker County, Texas, has, after proper notice, held a public hearing concerning a proposed revision of the Walker County Subdivision Regulation; and

WHEREAS, after soliciting the public's comments, the Commissioners Court finds that the adoption of revised Regulations will be in the public interest;

NOW THEREFORE BE IT RESOLVED, that the Walker County Commissioners Court hereby adopts the attached document as the revised Walker County Subdivision Regulations and *orders* that they be in full force and effect on **June 16, 2025**; and

FURTHER RESOLVED, that County Judge Colt Christian be, and is hereby authorized to sign this Resolution and Order as the act and deed of the Walker County Commissioners Court.


The foregoing Resolution and order was lawfully moved by Commissioner White, duly seconded by Commissioner Daugette, and duly adopted by the Commissioners Court on a vote of four (4) members for the motion and one (1) member(s) opposed, with no commissioner(s) being absent from the dais.


Colt Christian
County Judge, Walker County, Texas

DATE: June 16, 2025


Danny Kuykendall
Commissioner, Precinct One, Walker County, Texas


Ronnie White
Commissioner, Precinct Two, Walker County, Texas


Bill Daugette
Commissioner, Precinct Three, Walker County, Texas



Brandon Decker
Commissioner, Precinct Four, Walker County, Texas

Table of Contents

Resolution & Order # 2025-77	2
Table of Contents	3
Walker County Subdivision Regulations	5
Section 1 - Purpose	5
Section 2 - Definition of Terms	6
Section 3 - Application Review and Approval Procedures	11
Section 4 - Plat Requirements	20
Section 5 - Amending Plats, Re-plats, or Vacating a Plat	25
Section 6 - Financial Responsibilities and Guarantees	26
Section 7 - Maintenance	28
Section 8 - Private Subdivisions	30
Section 9 - Variances	31
Section 10 - Penalties	32
Section 11 - Minimum Lot Frontage	33
Appendix A - Platting Guidelines	34
A1 - Plat Required	34
A2 - Exceptions by Law	35
A3 - Additional Exceptions	36
Appendix B - Engineering Guidelines	38
B1 - Graphic Requirements	38
B2 - Lot, Utility Easement, and Setback Requirements	41
B3 - Road Alignments	43
B4 - Minimum Road Design Requirements	44
B5 - Construction – General	49
B6 - Subgrade	50
B7 - Intentionally Left Blank	51
B8 - Intentionally Left Blank	52
B9 - Concrete Pavement	53
B10 - Concrete – General	54
B11 - Road Names, Signs, and Markers	55
B12 - Drainage	56
B13 - Testing and Reporting	62
Appendix C - Plat Notes	63
C1 - Owner's Dedication	63

C2 - Roadway Construction	63
C3 - Owner's Responsibilities	64
C4 - Commissioners Court Approval	64
C5 - County Clerk's Certification	65
C6 - On-site Sewage Facility Review	66
C7 - Mailboxes	66
C8 - Floodplain Regulations Certification	66
C9 - Development Notes	66
C10 - Plat Notes Addressing Area Drainage	67
C11 - Plat Notes Addressing Utilities	68
C12 - Water Supply Note:	68
C13 - Certification of Surveyor	68
Appendix D - Plat Application Checklists	69
Appendix E - Construction Documents	71
Appendix F - Roadway Cross-Sections & Details	74
Appendix G - Curb Details	80
Appendix H - Concrete Pavement Details	82
Appendix I - Storm Bedding and Backfill Details	84

Walker County Subdivision Regulations

On July 21, 1986, acting pursuant to the Texas Local Government Code, Walker County adopted regulations governing platting and the subdivision of land. They were further revised on March 18, 1991, February 7, 1994, December 11, 1995, October 15, 1996, November 23, 1998, July 24, 2000, April 25, 2005, February 26, 2018, April 23, 2018, September 23, 2019, June 1, 2022, March 27, 2023, April 24, 2023, September 1, 2023, November 18, 2024, May 5, 2025, and are hereby further revised as follows. These Regulations shall be known as the Walker County Subdivision Regulations.

These revised Regulations, as well as required review fees, shall apply to all new Applications received on or after the date that these revised Regulations were adopted by the Walker County Commissioners Court. Any subdivision applications that were originally submitted prior to that date shall be subject to the Regulations and any applicable fees that were in effect at the time of the original submission, unless, at the applicant's option, the applicant elects to proceed under the new regulations or requirements. Compliance with these Regulations shall be a prerequisite to the approval of any subdivision by Walker County, except insofar as they may conflict with any applicable State statute.

Section 1 - Purpose

1.1 These Regulations have been prepared in general to aid in the orderly development of Walker County, Texas, and provide guidelines, which will lead to a desirable environment. Specifically, they have been prepared for the following purposes:

- To furnish the Owner with guidance and assistance in the expedient preparation and approval of his or her plat.
- To protect the citizens of Walker County by providing subdivision and development guidelines for residential, commercial, and industrial subdivisions.
- To provide for the welfare of the public by providing guidelines for the location, design, and construction of roadways, roadway intersections, drainage improvements, and other features that provide for the safety of the general public.
- To provide for the proper arrangement and construction of roads, and to ensure the proper relationship of roads to existing or planned roads.
- To ensure adequate access for emergency response vehicles.
- To ensure that Walker County will not be burdened with substandard roads in the future.

Section 2 - Definition of Terms

2.1 **100-year Floodplain**

Any land that would be inundated by a flood having a one percent chance of occurring in any given year, including but not limited to any land shown on the current version of the FEMA National Flood Insurance Program Flood Maps.

2.2 **100-year Storm**

A storm having a one percent probability of occurrence in any given year.

2.3 **Application**

A submittal that includes a completed Application form along with all required attachments which may be required as part of that submittal and the appropriate review fee. These attachments may include but are not limited to forms, agency approvals, specifications, drawings, drainage or geotechnical reports, and electronic data files. (See Appendix D). The DPD is authorized to make additions or changes to the Application forms without any additional approval by Commissioners Court.

2.4 **Base Flood Elevation (BFE)**

The water surface elevation resulting from the flood that has a one percent chance of equaling or exceeding that level in any given year (also called the Base Flood).

2.5 **Block**

A tract of land bounded by actual or platted roads, waterways, or other definite boundaries, or a combination thereof.

2.6 **Commissioners Court**

All references in these Regulations to the Commissioners Court shall mean the Commissioners Court of Walker County or the person(s) designated by the Commissioners Court of Walker County.

2.7 **Condominium Development**

A form of real property with portions of the real property designated for separate Ownership or occupancy, and the remainder of the real property designated for common Ownership or occupancy solely by the Owners of those portions. For the purposes of these Regulations, Condominiums shall include, but not be limited to, all developments created under Chapter 82 of the Texas Property Code, also known as the Uniform Condominium Act.

2.8 **County**

All references in these Regulations to the "County" shall mean Walker County.

2.9 **County Engineer**

All references in these Regulations to the "County Engineer" shall be construed to refer to the Professional Engineer employed by or contracted by Walker County for the review of plat applications, plans, permits, or general engineering review related to any application, or his/her authorized representative.

2.10 **Cul-de-sac**

A road having one terminus open for vehicular and the other terminated by a vehicular turnaround.

2.11 **Daughter Tract/Daughter Parcel**

Any of the tracts created by the division of a parent tract, including the remainder of the parent tract itself.

2.12 **DPD**

All references in these regulations to the "DPD" shall be construed to refer to the current Director of Planning and Development for Walker County, Texas, or his/her authorized representative.

2.13 **Dwelling Unit**

A dwelling unit is defined as a single unit of residence for a family of one or more persons.

2.14 **Easement**

A grant by the property Owner for the use of a strip or parcel of land by the public or utilities, or for any private purpose.

2.15 **ETJ (Extraterritorial Jurisdiction)**

The unincorporated area that is contiguous to the corporate boundaries of a city, as defined by that city, and within various distances of the municipality depending on the number of inhabitants of a municipality. Within an ETJ, cities have statutory authority to adopt rules governing plats and subdivisions.

2.16 **FEMA**

The Federal Emergency Management Agency, a federal agency of the Department of Homeland Security.

2.17 **Frontage**

Frontage is the measurement of distance along the right of way adjacent to and abutting a lot boundary as measured at the edge of the right of way of:

- 1) an existing city, county, or state-maintained road; or
- 2) a public road that has been platted in accordance with these regulations and either submitted an approved surety or accepted as substantially complete-

2.18 **Guidelines**

The Engineering Guidelines contained in Appendix B as part of the Walker County Subdivision Regulations, as amended.

2.19 **Improvements**

Any or all road pavements, curbs and gutters, sidewalks, utilities, drainage facilities, topsoil, trees, grading, signs, and crosswalks, and may also include walkways, streetlights, or any other manmade changes to improved or unimproved real estate.

2.20 **LOG**

Lip of Gutter; the front edge of the curb. The point where the curb meets the roadway pavement. (Also referred to as the "face of curb").

2.21 **Loop Street**

A type of local street where each end terminates at an intersection with the same street.

2.22 **Lot**

For the purpose of these Regulations, a parcel or part of a tract of land created by a division of a parent tract regardless of whether it is made using a metes and bounds description in a deed of conveyance or a contract for deed, by using a contract of sale or executory contract to convey, or by using any other method, exclusive of any adjoining road or road right-of-way. Lots shall meet the minimum dimensions, area, and setback requirements of these Regulations.

2.23 **Major Thoroughfare**

Major thoroughfare shall mean an arterial road as defined herein.

2.24 **Minimum Requirements**

Requirements when defined as a minimum shall be the least restrictive standards as allowed by applicable local, state, and federal regulations.

2.25 **Minor Subdivision / Minor Plat**

Minor Subdivision/ Minor Plat shall mean an application for plat that meets the following:

- a) does not include or require the construction of any road or drainage improvements under this policy, excluding detention;
- b) subdivides an existing compliant tract into 4 or fewer parts, tracts, or lots;
- c) and is not located within a platted subdivision.

2.26 **Owner**

The person(s) possessing title and/or applicable lienholders to the property to be subdivided. This can also refer to the Owner's surveyor, engineer, lawyer, planner, or other agent(s) who has been given authority to represent the Owner.

2.27 **Parent Tract/Parent Parcel**

The original tract/parcel owned by the Owner prior to any division.

2.28 **Plans**

Construction drawings, specifications, reports, calculations, detailed quantity take-offs, bidding forms, or other documents required for construction, construction review, or construction-related approvals.

2.29 **Plat**

The Plat is the plat required for filing in the records of the County Clerk and is a map or drawing of a proposed subdivision (1) prepared in conformance with the approved engineering plans application and (2) meeting the requirements of these regulations.

2.30 **Precinct Commissioner**

The Walker County Commissioner in whose precinct the subdivision is located.

2.31 **RV Park:**

Also known as a Recreational Vehicle Park, is a planned facility or location created for the temporary lodging of individuals in Recreational Vehicles, Motor Homes, 5th wheel trailers, and similar vehicles, but not including mobile homes, manufactured homes, or structures not certified and licensed for roadway operation by a state. RV Parks offer short-term lodging not to exceed five months per year. For the purposes of this policy, an RV Park would include any property that offers two or more recreational vehicles or recreational vehicle spaces or sites for rent, lease, or financial gain on a single property.

2.32 **Registered Professional Engineer**

A person licensed, as of the date of the plan being presented, to practice engineering in Texas.

2.33 **Registered Professional Land Surveyor**

A person licensed, as of the date of the plan being presented, to practice land surveying in Texas.

2.34 **Regulations**

The Walker County Subdivision Regulations (this document), as amended, including all appendices.

2.35 **Residential Rental Community**

A Residential Rental Community is a property subdivided by short-term leases, not to exceed 36 months, into two (2) or more separate dwelling units or spaces. A Residential Rental Community does not include Condominiums, Manufactured Home Rental Communities, or Recreational Vehicle Parks.

2.36 **Road/Street**

The terms "street" or "road" are interchangeable and mean a vehicular way, including culverts and bridges, and are used to describe all vehicular ways regardless of any other designation they may carry. All roads shall be categorized into one of the following functional classifications:

2.36.1 **Arterial Road**

Arterial roads are those that are principally regional in nature, which will serve vehicular traffic beyond the limits of a subdivision; or connect one collector or arterial with one or more collectors or arterials. Arterial roads include any road used for through or high-volume traffic ($\geq 12,000$ average daily trips), or any road included as an arterial on a county or city transportation plan.

2.36.2 **Collector Road**

Collector roads are those that connect one local road with one or more local roads; or any road with $\geq 2,000$ average daily trips that is not an arterial road.

2.36.3 **Local Road**

Local roads are those that principally provide direct access to lots within a subdivision and have less than 2,000 average daily trips.

All roads Arterial, Collector, and Local roads shall also be classified as follows:

2.36.4 **Urban Road**

For the purposes of this order, an urban road is any road situated such that any of the lot frontages are less than 125 feet. Any road with a curb and gutter design will be considered an urban road.

2.36.5 **Rural Road**

For the purposes of this order, a rural road is any road situated such that any of the lot frontages are 125 feet or more.

2.36.6 **Major Thoroughfare**

Major thoroughfare includes arterial roads, as defined herein, and all roads included either now or in the future in the Walker County Long Range Transportation Plan.

2.37 **Subdivision**

The division of a tract of land into two or more parts to layout (1) a subdivision of the tract, including an addition; (2) lots; or (3) streets, alleys, squares, parks, or (4) other parts of the tract intended by the owner of the tract to be dedicated to public use (Sec 232.001, Texas Local Government Code, as

amended. The Walker County Commissioners Court has adopted guidelines, incorporated in these Regulations as Appendix A, stating when Owners are required to file a plat for a subdivision). A division of a tract includes a division regardless of whether it is made using a metes and bounds description in a deed of conveyance or a contract for deed, by using a contract of sale or executory contract to convey, or by using any other method.

For the purpose of these Regulations, subdivisions shall be classified as either urban or rural, as follows:

2.37.1 Urban Subdivision

Urban subdivisions are any subdivision such that any of the lot frontages are less than 125 feet or are less than 1 acre in size.

2.37.2 Rural Subdivision

Rural subdivisions are any subdivision such that all of the lot frontages are 125 feet or more, and all lots are greater or equal to 1 acre in size.

2.38 Travel Way

The portion of a road or roadway intended for vehicular travel. Where concrete curb is installed, the travel way shall be measured LOG to LOG. In cases where a rollover curb (i.e., 4"x12" curb) is installed, the travel way shall be measured from the inside edge to the inside edge of the rollover curb (i.e., the rollover curb is not included as part of the travel way). The travel way also does not include gravel or paved shoulders.

2.39 TxMUTCD

The latest edition of the Texas Manual on Uniform Traffic Control Devices.

2.40 Utility

All persons, firms, corporations, partnerships, municipality, or other private authorities providing gas, electric, water, sewer, drainage facilities, telecommunications, cable television, or other services of a similar nature.

Section 3 - Application Review and Approval Procedures

General Requirements

- 3.1 Every Owner of any tract of land situated outside the corporate limits of any city in Walker County, Texas, must apply for approval and have a plat of the subdivision prepared in compliance with these regulations as authorized by Chapter 232 of the Texas Local Government Code and under the platting and applicability guidelines included in Appendix A. No plat shall be approved for filing in the unincorporated areas of Walker County, Texas, without meeting the requirements of these regulations unless specifically exempted (See Platting Guidelines included as Appendix A). Any tract that has not had its boundary changed since February 1, 2000, may be sold in its entirety without being platted unless otherwise required by State law; this would include but is not limited to the replatting and amending plat requirements.
- 3.2 If the property to be platted lies entirely within the limits of a city, the Owner shall consult directly with that city pertaining to all platting procedures and requirements.
- 3.3 If the property to be platted lies entirely outside of the limits of a city and all ETJs, platting procedures and requirements shall be in accordance with these Regulations.
- 3.4 If the property to be platted lies fully or partially within the ETJ of a city, the platting procedure shall be accomplished in accordance with the most current applicable agreement between the County and that city.
- 3.5 In those ETJ's where the agreement provides for a joint review by both the city and the County (reference is made to Appendix E), an Application shall be filed with the entity or office required by the agreement.
- 3.6 It is the obligation of the Owner to submit all information necessary to permit proper review by the County. If this is not done, the submission will be rejected and a new application must be filed.
- 3.7 All subdivisions of land must either be approved for an exception under State or Local exceptions (See Appendix A), or complete all required applications and approvals required herein. All applications for an exception must be approved by the DPD and/or the County Engineer and have an affidavit of exception on the current form filed in the records of the County Clerk.
- 3.8 All applications shall be marked as to the category of application: Exception, Variance, Plat, or Replat / Amending Plat. Additionally, applications shall include any request for consideration as a plat seeking consideration under the requirements of a Minor Subdivision. A separate application governed by independent timelines and processes will need to be submitted for each category of application requested and/or necessary for the completion of a project.
- 3.9 All applications must include all submittals as required herein or shown on the "Walker County Subdivision Regulations Application Checklist" attached as Appendix D. Appendix D is provided as a guide to assist the applicant in the application process and does not provide complete details of each individual requirement, the detailed requirements are provided in the text and appendices of these regulations.
- 3.10 Once an application and application fee are submitted, no refund of any fees will be given unless required by statute or approved by Commissioners Court. There will be no refund due to an application being submitted incomplete or the withdrawal or cancellation of an application or project. It is the Owner's responsibility to review these regulations and associated guidance and submit the

application only after due diligence has been given to the completeness and suitability of the application.

- 3.11 All subdivisions of land not otherwise excepted by these regulations must submit a plat application for approval prior to filing a plat or subdividing any property within the unincorporated areas of Walker County. For certain platting such as amending plats, lot combination in existing subdivisions, and minor subdivisions with prior approval from the DPD and/or County Engineer a minor plat complying with the County's standards may be submitted. The names of the proposed subdivision and any of the physical features (such as streets, parks, etc.) must not be so similar in spelling or pronunciation to the names of similar features in Walker County, as to cause confusion. All streets and roads must be named on the plat, a list of road names must be submitted by the Owner to the Department of Planning and Development, and approval of the names received, prior to the submittal of the plat application for review and approval.
- 3.12 The Owner must submit five fully signed and executed copies of the plat on 18"x24" media (three paper copies and two mylar copies). In addition to the plat, the Owner must submit 3 paper copies of all submittals along with the following digital files of any plans, plats, exhibits, studies, or other documents required by these regulations for all applications:
- a) A copy of all items in an Adobe .pdf format;
 - b) A copy of all plans, plats, maps, or spatially displayed or related documents and data in .dwg format or pre-approved alternate format.
 - c) A copy of all features shown on the plat must be provided in ESRI shapefile format, including but not limited to roads, rights of way, easements, lot lines, property lines, section and block outlines, etc.

All entities or objects within the AutoCAD drawing file shall be at zero elevation. The coordinate system of the electronic drawing and shapefile shall be the Texas State Plane Coordinate System, Central Zone, U.S. Survey feet, grid coordinates. Right-of-way centerlines, real property boundary lines (lots, blocks, external subdivision boundary, rights-of-way, etc.), and text shall each reside on independent or separate layers. All documents required to be submitted by a registered professional land surveyor or professional engineer must be sealed and signed. *An exemption from the requirement to submit a digital map may be granted if the Owner of the tract submits with the plat application an acknowledged statement indicating that the digital mapping technology necessary to submit a map that complies with this subsection was not reasonably accessible, including justification as to why the technology is not reasonably accessible.*

- 3.13 To protect the public interest, the Commissioners Court of Walker County hereby decrees under the provisions of Chapter 232, Texas Local Government Code, that the Owner of any tract of land that desires to obtain the approval necessary for recording a subdivision plat in the County Clerk's Records of Walker County shall construct all roads and drainage facilities, including stormwater detention, along with any items required by other governmental agencies in said subdivision to the standards and specifications set forth in the Engineering Guidelines incorporated as Appendix B of these Regulations before offering said plat for approval unless financial surety is approved and provided in accordance with Section 6, construction plans are approved by the Commissioners Court, and all necessary permits have been issued.
- 3.14 If an Owner wishes to construct improvements prior to filing a plat, then the owner must submit a variance request, requesting a revised process for submittal and approval of infrastructure.
- 3.15 All road and drainage improvements shall be designed and certified by a Professional Engineer

licensed to practice in Texas. All plans and specifications shall conform to the requirements of these regulations.

- 3.16 The Owner shall submit construction plans, sealed by a Professional Engineer, for roads, drainage, traffic signage, and/or utility improvements within the proposed subdivision or within any existing County right of way to the Planning and Development Department and obtain plan approval from the Commissioners Court prior to beginning construction. These plans shall show the location of water, sanitary sewer, and storm sewer utilities, and shall show proposed easements for privately owned utilities (electric, cable television, gas, telephone, etc.). Utilities will be reviewed based on their impact on the right of way, public infrastructure, and the floodplain. These plans shall be sealed by a professional engineer and include the design requirements as described in Appendix B, Engineering Guidelines.

Pre-Application Meeting

- 3.17 It is strongly recommended that the Owner request and attend a pre-application meeting with the Walker County Department of Planning and Development prior to all Plat Applications.
- 3.18 The Owner must submit a request for this meeting and is encouraged to bring to the meeting any of the application documents listed in Appendix D.
- 3.19 A Pre-Application Meeting will generally be scheduled within 10 business days of the receipt of a completed request and the Owner will be notified of the time and date of the meeting. The time, date, duration, and location of the meeting will be at the complete discretion of the County.
- 3.20 The Pre-Application Meeting will allow the Staff to provide some information on the plat application processes and allow Owner to ask questions related to policy in relation to a potential application.
- 3.21 A Pre-Application meeting does not constitute a Plat Application.

Plat Application

- 3.22 A Plat Application must be submitted and approved prior to any plat being filed for all subdivisions of land subject to these regulations. (See Appendix A for additional guidance on applicability)
- 3.23 Applications and any revised applications or responses to conditional approvals or disapprovals must be submitted during a scheduled submittal meeting with DPD or assigned staff. The Owner or the Owner's designated representative must attend the meeting. This meeting may be scheduled in conjunction with a pre-development meeting if so desired by the applicant.
- 3.24 The Application must include the documents and other information required by these regulations.
- 3.25 All Plat Applications shall include the fee as required by the currently adopted Schedule of fees.
- 3.26 All Plat Applications must include a completed and executed Application Form in its most current version. The application form will be available from the Department of Planning and Development, and the DPD has the authority to update or change this form without the need for any additional action by Commissioners Court.
- 3.27 All Plat Applications shall include copies of the current filed deed for the parent tract.
- 3.28 All Plat Applications shall include a copy of a valid Title Abstract or Title Report completed to current

ownership for the parent tract from a title company or attorney. The surveyor's certification shall state the plat was completed with the benefit of a current Title Abstract or Title Report and includes all encumbrances noted on the current Title Abstract or Title Report.

- 3.29 All Plat Applications shall include a copy of a Final Plat in compliance with these Regulations and including all final signatures and certifications.
- 3.30 All Plat Applications shall include such documents as necessary to identify the Owner or Owner's agent authorized to sign documents in relation to the plat. This may include but is not limited to powers of attorney, articles of incorporation, and title documents.
- 3.31 All Plat Applications not specifically exempted from the requirement to submit a detention/drainage study or flood study under these regulations, and all Subdivision Applications that include the construction of any improvements required or regulated under these regulations must include completed plans, sealed by a Registered Professional Engineer authorized to practice in Texas, for all improvements. The plans must comply with these regulations including but not limited to Appendix B. In addition, all plans must be satisfactory to the Commissioners Court.
- 3.32 All Plat Applications proposing new streets and roads must include copies of written approval from the governmental authority having jurisdiction over 911 addressing that all road names and spellings included in the plat have been authorized for use.
- 3.33 All Plat Applications that do not indicate plans for the connection to or installation of a TCEQ approved municipal wastewater system must include an approved OSSF Subdivision Planning Materials Submittal for Subdivision Development from the TCEQ Authorized Agent unless exempted in writing. No lot or tract shall be included within any application for subdivision in violation of state law or local order, including, but not limited to the Texas Administrative Code, Title 30, Chapter 285, and the Walker County Regulations for on-site sewage facilities.
- 3.34 All Plat Applications planning to utilize a TCEQ approved municipal wastewater system must include a letter from the wastewater provider including a reference to the provider's valid Certificate of Convenience and Necessity (CCN) or documentation of an application, indicating that the provider is prepared to provide sewer services to the proposed subdivision.
- 3.35 All Plat Applications shall include letters of serviceability from all water and electric providers, including the name, phone number, and e-mail address of the utility company contact. The letter must include a reference to the subdivision and the number of lots to be served.
- 3.36 If a person submits a plat for the subdivision of a tract of land for which the source of the water supply intended for the subdivision is groundwater under that land, the plat application must include a written statement that:
 - (1) is prepared by an engineer licensed to practice in this state or a geoscientist licensed to practice in this state; and
 - (2) certifies that adequate groundwater is available for the subdivision.
 - (3) The certificate shall be submitted with a TCEQ-approved form.
 - (4) The report shall include a satisfactory letter of receipt and comment from the Bluebonnet Groundwater Conservation District.

A variance for this item cannot be granted unless credible evidence of groundwater availability in the vicinity of the proposed subdivision is provided, and it complies with Local Government Code §232.0032.

- 3.37 All Plat Applications that require or include the construction of improvements must include an approved permit issued under the Walker County Regulations for Flood Plain Management. All plats and plans shall conform to the Walker County Floodplain Regulations regardless of the permitting requirements.
- 3.38 All Plat Applications that require a variance to be granted must submit a copy of all approved variances with the application.
- 3.39 All Plat Applications requiring the construction of improvements must include a detailed and itemized report including a list of improvements, in a bid schedule format, with associated unit quantities that are necessary to complete the road and drainage improvements per the required construction plans and is sufficient for the Commissioners Court to set the bond amount, sealed by a registered professional engineer authorized to practice in Texas. The report must be acceptable to the County Engineer and the Commissioners Court in format and content. Lump sum units shall not be used for quantifiable items such as pavement, stabilization, earthwork, etc.
- 3.40 All Plat Applications requiring the construction of improvements must include a maintenance plan in the form of a document signed by the Owner specifying the mechanism and/or entity that will be responsible for maintenance of the public improvements within the subdivision until such time, if any, the roads, drainage, and associated appurtenances are adopted for public maintenance by Walker County. The plat must include a note identifying the entity referenced in the maintenance plan that shall be responsible for the on-going maintenance of the roads, rights-of-way, signage, drainage, and other improvements within the subdivision, until such time, if any, said infrastructure is adopted into public maintenance.
- 3.41 All Plat Application shall include any necessary approvals from other governmental agencies such as Texas Department of Transportation, Groundwater Districts, Army Corps of Engineers, etc. Any plat proposed within 2000 feet of the Trinity River or Lake Livingston shall include a letter of "no objection" from the Trinity River Authority. Any plat proposed within 2000 feet of Lake Conroe shall include a letter of "no objection" from the San Jacinto River Authority. Any plat proposing to connect to or provide access from a road under the maintenance or control of the Texas Department of Transportation shall provide written approval of said access or connection. It is the sole responsibility of the Owner and/or the Owner's Representative to properly research any approvals that are required from other agencies. Acceptance of an application by Walker County does not waive any responsibility or requirement for compliance with any outside agency.

Review Process

- 3.42 All plat applications shall be submitted complete and made as a single submittal. It is the Owner's responsibility to review these regulations and associated guidance and submit the application only after due diligence has been given to the completeness and suitability of the application. An application checklist is attached as Appendix D, as an aid to compliance. Acceptance of the application for review is not an indication of the completeness of an application. No review for completeness will take place prior to submittal of an application by the Owner and payment of the associated fee. It should be recognized by the Owner that the submittal of a complete application is a requirement of the Owner and that the submittal of incomplete applications affects program costs and expenses and may result in increases in the application fee.
- 3.43 Once an application and application submittal fee are submitted no refund of any fees will be given

unless required by statute or approved by the direct action of Commissioners Court. There will be no refund due to an application being submitted incomplete or the withdrawal or cancellation of an application or project.

- 3.44 An application is considered submitted for review on the date application, revised application, or resubmittal is received by the Walker County Department of Planning and Development at:

**1313 University Avenue, Suite A
Huntsville, TX 77320**

- 3.45 Delivery of the application must take place in accordance with the administrative criteria set by the Walker County Department of Planning and Development. The Walker County Department of Planning and Development does not receive any applications on non-business days. Unless an alternative submittal process has been agreed to in advance and in writing by the DPD, all submittals must take place at a submittal meeting scheduled in advance by the Owner.
- 3.46 The DPD is authorized to set any necessary administrative criteria related to the submittal of applications under this policy, including but not limited to, setting the times and/or dates at which applications will be received, requiring appointments for submittal of the applications, making changes as necessary to the administrative forms related to applications, specifying the method and type of payment, and specifying the form of submittal.
- 3.47 The County shall have 10 business days from the date the application is received to notify the Applicant of any documents or other required information missing from the application. The application will not be considered complete until all documents or other required information are submitted. This initial review of the submittal is an administrative review to determine if required documents or other information are missing from the application and should not be construed as a qualitative review to determine approval, completeness, appropriateness, or compliance of the documentation or other submittals with these regulations.
- 3.48 In such cases where the application is missing any document or other required information, the County will notify the Owner of the missing documents or other required information. The missing documents or other required information must be submitted to the County as a single submittal along with payment for any increase in the fee, and a receipt will be provided to Owner for the revised submittal. Each time a submittal is made of missing documents or other required information the 10-business day administrative review period described in Sections 3.42 - 3.48 will begin again. This process will continue until all documents and other required information are submitted, or until the Application expires (See Section 3.68).
- 3.49 If an incomplete application is submitted for review, but the application fee and completed application form are submitted, the Owner may request a "Guidance Review" from the County on the incomplete application prior to submitting the missing documents or other required information in the revised application. The guidance review is a voluntary process designed to improve the Owner's Application without being subject to the strict timelines, revision processes, and rejection processes surrounding completed applications. The DPD and County Engineer are not required to conduct a guidance review of any incomplete applications unless the DPD agrees that the review would have significant benefit to the application and not create a significant negative impact on County resources. The acceptance of an application for "Guidance Review" is at the total discretion of the DPD. A "Guidance Review" may only be requested or granted on withdrawn or incomplete applications. As the Guidance Review is not a required process, it is outside of the application process timeline, and there is no maximum response time for this process to complete; however, the Owner may proceed to re-

application at any point without waiting for the Guidance Review to be completed if the Owner so desires.

- 3.50 Once an application is considered complete and regulatory review has begun no additional documents or other information may be submitted for review, with the exception of a response to a conditional approval or disapproval by the Commissioners Court or its authorized representative. If an application is withdrawn then a revised application may be submitted under the conditions allowed of this policy.
- 3.51 Following the receipt of a complete Application, the DPD and/or the County Engineer will review the Application for compliance with these regulations and forward the application and the review comments to the Commissioners Court for action.
- 3.52 The DPD and/or County Engineer will submit a copy of the application review(s) to the Commissioners Court, the person authorized by the Commissioners Court, or, in the case of a joint review where the county is not acting as the authorized office, to the specified authorized office.
- 3.53 Unless an Owner successfully withdraws an application, the DPD and/or County Engineer will refer the original application along with comments and recommendations to the Commissioners Court or person designated by the Commissioners Court for action.
- 3.54 The Commissioners Court or its designee will consider the plat application for approval within 30 days of the date of the receipt of a complete application, unless a valid extension is allowed for under law or has been applied for and granted by the Owner.
- 3.55 If an application is approved without conditions, the application will be considered complete and the plat may then be approved for filing by the Commissioners Court. Approval for the plat for filing is a separate action from the approval of the plat application and is not included in the 30-day or 15-day timelines for the approval of the application.
- 3.56 If an application is disapproved or approved with conditions, the Commissioners Court or its authorized representative shall provide a written list of conditions for approval to the Owner. The Owner may withdraw the application or submit a written response that satisfies each reason for disapproval provided or satisfies each condition. If the Owner wishes to submit a response, the response should be submitted as a single submittal addressing each condition or reason.
- 3.57 If the applicant chooses to submit a written response that satisfies each reason for disapproval provided, or satisfies each condition for conditional approval, the applicant must submit the written response in the same format(s) and quantities as required under the original application. The response shall be accompanied by all required forms, and any increases in the application fee or outstanding fee balances shall be paid when submitting the response.
- 3.58 Following the submittal of a response to a conditional approval or disapproval, the Commissioners Court and/or its designee shall review the response and take additional action to approve, approve with conditions, or disapprove the application within 15 calendar days.
- 3.59 The process described in Sections 3.56 through 3.58 shall continue until the application is approved by the Commissioners Court, is approved by the Commissioners Court's designee, expires, or is withdrawn.
- 3.60 At any time following the submittal and acceptance of a completed application, the DPD or County Engineer may recommend the application for action by the Commissioners Court or a person herein designated by the Commissioners Court.

- 3.61 At any time following the submittal and acceptance of a completed application, the Commissioners Court may take action on an application without allowing for a withdrawal, revision, or extension.
- 3.62 Following approval of a plat for filing by the Walker County Commissioners Court, the Owner shall submit the final plat to the County Clerk for recording in accordance with the requirements of the County Clerk's Office.
- 3.63 If a final plat is not recorded within five years of the approval of the plat for filing by the Commissioners Court, the approval of the final plat expires. A single six-month extension may be granted by the Commissioners Court. The extension must be requested in writing by the Owner at least 30 days prior to the expiration.

Withdrawal of an Application

- 3.64 If the Owner wishes to withdraw the application, the Owner must submit a request for an administrative withdrawal of the original application on the current County form. Withdrawal of an application is voluntary and must be requested by the Owner on an approved form. An application that has been withdrawn can only be submitted as a new application. However, it may be submitted within 90 days of the withdrawal under the same application number and pay only the increase in fee that would be charged for a revised application under the schedule of fees. If an application is withdrawn and not resubmitted within 90 days, then the application must be submitted as a new application in accordance with these regulations, and a new application fee must be paid.
- 3.65 An application submitted following a withdrawal will be processed under a new timeline starting with a review for completeness under these regulations. No replacement applications will be accepted once an application has been accepted as complete without the original application being withdrawn.
- 3.66 The Owner may voluntarily submit a withdrawal of application and replacement application only if approved by an authorized representative of the Commissioners Court.
- 3.67 The DPD and/or the County Engineer are hereby authorized to approve or deny any requests for extension or application withdrawal and/or replacement.

Expiration of an Application

- 3.68 Applications shall automatically expire in 120 days under the conditions laid out in 245.002(e) of the Texas Local Government Code. All applications shall expire as a dormant application under 245.005 5 years from the original date of submittal.

Minor Subdivisions

- 3.69 Minor subdivisions are subdivisions with four or fewer total lots, that are not located within an existing platted subdivision, and that do not require the construction of any road or drainage improvement under these regulations aside from detention. (See definitions section)
- 3.70 Minor Subdivision Applications (while not exempt from meeting the detention requirements of these regulations, State, or Federal law) are not required by these regulations to submit engineering plans or a drainage study for review by the County as long as the plat includes the Minor Plat drainage

certifications under C10. Minor Subdivisions are also not required to submit a Title Report but shall include all encumbrances noted on the current Title Report.

- 3.71 Minor Subdivisions are not required to submit 911 name approvals, engineer's itemized list of improvements, bonding, maintenance plans, letters of serviceability, or engineering drawings required for Plats because, by definition, these plats do not include or require the construction of said improvements.
- 3.72 Instead of the submittal requirements listed in Section 3.12, Minor Subdivision Applications may submit the plat on 8.5" by 14"/11" paper, three original copies of the plat must be submitted. The plat must include all of the requirements described in Section 4 of these regulations, with the exception of the applicable plat notes and signature blocks from Appendix C. The applicable Appendix C notes and signature blocks will be included on the Minor Plat document created by Walker County. The submitted plat will be attached to the Minor Plat document as an exhibit. Once fully executed and approved the plat will be filed in the Official Public Records of Walker County, Texas.
- 3.73 If any portion of the original parent tract being subdivided as a Minor Subdivision is further subdivided so that the total number of daughter tracts created from the original parent tract exceeds 4, then all new lots created must be addressed by the re-plat application's engineering plans, including detention for all new lots created by the replat. A note to this effect shall be placed on the face of the plat.
- 3.74 The DPD and/or the County Engineer are hereby authorized to approve, disapprove, or approve with conditions all plat applications involving Minor Subdivisions.
- 3.75 If any portion of the original parent tract was subdivided within the previous five years utilizing an exception other than those exceptions listed under Section A2 or A3.3 of Appendix A, then all daughter tracts from the parent tract subject to the exception shall also be included in the total lot count to determine eligibility for Minor Subdivision plats.

Amending Plats and Re-plats Process

- 3.76 Re-plat and Amending Plat applications shall not be subject to the same review timelines and procedures that relate to the approval of plat applications.
- 3.77 Re-plats or Amending Plats otherwise meeting the requirements of a Minor Subdivision will be allowed to utilize the submittal requirements for Minor Subdivision Applications; all other Amending Plats or Re-plats shall meet the same submittal requirements as listed for Plat Applications within these regulations.
- 3.78 As re-plats and amending plats are subject to different procedures and timelines as outlined in Chapter 232 of the Texas Local government code, these applications will be processed in accordance with those requirements (see Section 5).

Section 4 - Plat Requirements

Every plat shall include all of the following:

- 4.1 Date, north arrow, scale, and a title block with the name of the proposed subdivision, legal description, number of blocks/lots/reserves, and acreage. The scale of the plat, excluding the vicinity map and key map overall, shall not be greater than 200 feet per inch and shall be to a standard engineering scale.
- 4.2 All portions of the plat must be legible without magnification. The minimum text size shall be 0.06 inches.
- 4.3 The plat shall be prepared by a Registered Professional Land Surveyor.
- 4.4 A vicinity map drawn at a scale appropriate to show all nearby major roadways and sufficient in detail to identify the location of the proposed plat. A graphic or stated scale is not required on a vicinity map.
- 4.5 The plat shall be certified as to accuracy by the surveyor preparing the plat and show in reasonable detail the location of and width of existing and proposed streets, roads, alleys, lots, parks, easements, and other related features within the subdivision.
- 4.6 The plat shall be drawn on tracing cloth or other permanent type of material consisting of one or more sheets measuring eighteen inches wide and twenty-four inches long. If separate sheets are used a key map showing the entire tract with match lines shall be drawn on the first sheet.
- 4.7 Bearings and distances, calling for the lines of established surveys, landmarks, and other data furnished, sufficient to locate the property on the ground, must be shown on the plat.
- 4.8 Lots and block numbers are to be arranged in a systematic order as shown on the plat in distinct and legible figures.
- 4.9 The plat (including the entire parent tract if only a portion of that tract is to be subdivided) shall be shown on a single sheet, regardless of its acreage. The plat may also be separately shown on multiple sheets if necessary to show all details and information as required by this section. Multiple sheet plats shall have the subdivision name and sheet number located in the lower right-hand corner of each sheet.
- 4.10 Name, address, and telephone number of the professional individual(s) or firm(s) responsible for the preparation or certification of the plat.
- 4.11 Name of the property Owner(s) of record.
- 4.12 All adjacent property Owner's names, deed record, or subdivision name, block, and lot number.
- 4.13 County boundaries, city limits, ETJ boundaries, and subdivision section and/or phase boundaries.
- 4.14 Size, in acres, of all daughter tracts, including the remaining portion of the original tract.
- 4.15 Centerline tangent lengths and curve data for all proposed roads.
- 4.16 Road names and road designation (whether the road will be public or private), and right-of-way width for all proposed roads within and all existing roads abutting the plat. All rights-of-way and easements shall comply with Appendix B and Appendix F.

- 4.17 Survey ties across all existing right-of-way located adjacent to the boundary of the subdivision. Each tie shall show the bearing and distance from a proposed property pin to an existing property pin or fence if a pin cannot be found. Based upon this tie, a right-of-way width shall be shown. The intent of this requirement is to assist in determining if an additional right-of-way is needed.
- 4.18 Any existing County-maintained road right-of-way that joins the tract being subdivided shall have the same right-of-way widths and setbacks required herein. The additional right-of-way, as might be required, shall be furnished by the Owner and measured from an acceptable centerline alignment. The dedication of additional rights-of-way and setbacks along existing County-maintained roads is not required to exceed the boundaries of the parent tract(s). For rights-of-way and easements within amending plats and replats, see Section 5.
- 4.19 A dimension from the centerline of any existing roadway's pavement or causeway to the edge of the existing or proposed right-of-way.
- 4.20 Any area dedicated for road right of way shall be shown with bearings and distances, and be included on the plat drawing or in the plat notes the acreage of the dedicated road right of way.
- 4.21 All existing property lines and proposed lot lines with bearings and dimensions. For required lot frontages and other lot requirements, refer to Appendix B.
- 4.22 Building setback lines for each proposed lot. For building setback requirements, refer to Appendix B. Building setback lines can be included by a note on the plat at the owner's discretion.
- 4.23 All lot lines shall stop at the right-of-way lines; under no circumstances shall they extend past or into the right-of-way.
- 4.24 Proposed easements for detention basins, if needed, based on the requirements outlined in Appendix B.
- 4.25 Location of all existing and proposed easements including, but not limited to those outlined in Appendix B.
- 4.26 The location, zone classification, and panel effective date of the 100-year floodplain as identified on the most current Walker County Flood Insurance Rate Map (FIRM), published by the Federal Emergency Management Agency (FEMA).
- 4.27 The location of easements, lots, or reserves necessary for the proposed cluster mailboxes, if required.
- 4.28 If the proposed plat is to be a private subdivision (containing private roads), the title of the plat shall contain the phrase, "A Private Subdivision". Refer to Section 8 for additional requirements.
- 4.29 All existing and proposed plat boundary lines, phase/section lines, and lot lines with bearings and distances. Bearings shall be based on the Texas State Plane Coordinate System, Central Zone. Distances shall be expressed in U.S. Survey feet, and state whether distances are "Grid" or "Surface". A Combined Scale Factor shall be specified on the face of the plat to eight decimal places (example: 0.12345678) to facilitate the conversion of surface distances to grid distances. At least two external boundary corners of each block within the subdivision shall have grid coordinates depicted on the plat to the nearest one-hundredth of a foot (0.01 feet).

- 4.30 Owners are responsible for having surveys conducted and survey monuments installed in accordance with all the requirements and procedures established by Walker County and the Professional and Technical Standards of the Texas Board of Professional Engineers and Land Surveyors. All property boundary corners, angle points, and points of curvature or tangency must be monumented or referenced by corner accessory monumentation carried out by a registered professional land surveyor. All monuments must:
- a) Be set of sufficient depth to retain stable and distinctive location;
 - b) Be of a size and material, that in the surveyor's judgment, will best ensure that the monument will withstand the deteriorating forces of nature;
 - c) Include a cap or marker identifying the responsible registrant, firm, or associated employer;
 - d) Include a notation on the applicable plan or plat that the corner was either found or set and a description of its physical characteristics; and
 - e) Be exposed for inspection if requested by County.
- 4.31 All plats shall make accommodation for any necessary easements, rights-of-way, or lot design necessary to accommodate the improvements related to the subdivision as required by these regulations.
- 4.32 Any vertical elevations depicted on the plat shall be expressed in U.S. Survey feet and shall indicate the specific vertical datum used. Describe and locate at least one vertical reference mark used to verify or establish said datum, and indicate the vertical elevation used at each vertical reference mark.
- 4.33 Road rights of way shall be dedicated to the public except when a variance is granted in accordance with Section 8. All public roadways and easements shall be dedicated free of liens. All rights-of-way and easements shall be in compliance with Appendix B and Appendix F. All dedications of a right-of-way shall be by easement and in conformance with these regulations. The dedication shall be accompanied by a plat note as found in Appendix C1. The Owner's and any lien holder's dedication, and restrictions if any, duly acknowledged in the manner required for acknowledgment of deeds, shall also be provided.
- 4.34 If public roadways are to be built as part of the plat, the plat note regarding the responsibility for the construction of roadways is found in Appendix C2.
- 4.35 The plat note regarding Owner's responsibilities, as found in Appendix C3, must be included if not contained in the Owner's dedication.
- 4.36 All proposed easements and existing easements of record that have a designated route shall be shown on the plat with bearings and dimensions. The Owner shall be responsible for coordinating with all utility providers the location of all utility easements that are shown on the final plat.
- 4.37 For Major Plats: If there are any areas within the plat that include a FEMA-mapped floodplain with any Zone A classification, or if any water-course whose upstream drainage basin is larger than 640 acres exists within or adjacent to the plat boundary, the plat shall also show the extent of the 100-year floodplain as determined by an engineering study under the seal of a Registered Professional Engineer. This study shall be sufficient in scope to determine and establish a base flood elevation (BFE) for all points within the plat in accordance with FEMA-approved methodologies and standard engineering practices.

- 4.38 For plats where a FEMA-mapped floodplain with a Zone AE classification exists within the subdivision, the BFE established by the associated FEMA-published flood study may be substituted for the engineering study.
- 4.39 A minimum lowest finished floor elevation (FFE) for buildings shall be established for each lot adjacent to the floodplain. This minimum FFE shall be established in accordance with the most current edition of the Walker County Floodplain Regulations. FFE shall utilize the same vertical datum as used with the BFE determination and shall include information as to the elevation of the FFE above the BFE.
- 4.40 The plat note found in Appendix C4 for Commissioners Court approval, including authorization for the County Clerk to file the plat for record, and the County Clerk's certification as found in Appendix C5 must be included on all plats. These signatures shall be obtained after approval by the Walker County Commissioners Court.
- 4.41 All variances granted shall be listed in the notes section of the plat.
- 4.42 All parcels within the boundary of the subdivision shall have a block and lot number shown on the plat drawing.
- 4.43 If any lot within the plat will be served by an on-site sewage facility, a signature block as found in Appendix C6 shall be placed on the plat. This block shall show that a properly licensed individual has examined the plat and that it complies with the Walker County On-Site Sewage Facility Regulations, Construction Standards for On-Site Sewage Facility Regulations as published by the Texas Commission on Environmental Quality (TCEQ as amended). The Registered Sanitarian or Engineer that prepared the OSSF planning materials for the developer must sign this signature block.
- 4.44 If rural route mailboxes are proposed, see Appendix C7 for the placement of such mailboxes.
- 4.45 Plats shall reference the applicable FEMA FIRM Panel and note the flood zone. Major plats or plats for tracts within the ETJ of a city shall include the signature block as found in Appendix C8 relating to floodplain regulation.
- 4.46 If any areas of the plat are located outside of incorporated areas, include the plat note as found in Appendix C9 regarding the requirement to obtain a unique Development Permit from the Walker County Floodplain Administrator prior to any manmade change to improved or unimproved real estate, including but not limited to the placement of a structure or surface improvement.
- 4.47 All plats shall include the appropriate drainage notes/certifications as found in Appendix C10.
- 4.48 All plats shall include the appropriate note addressing utilities as found in Appendix C11.
- 4.49 All plats shall include the appropriate note addressing water supply as found in Appendix C12.
- 4.50 All plats shall include a Certification of Surveyor as found in Appendix C13.
- 4.51 If a variance is obtained from Commissioners Court for the roads within the subdivision to be private, include the appropriate note(s) per the requirements of Section 8.

- 4.52 It is the responsibility of the Owner to assure that the proposed name of the subdivision is not duplicated. Subdivisions with different sections are considered unique. The Owner shall check with the County Clerk's records for verification.
- 4.53 A culvert schedule shall be calculated by a licensed professional engineer and included on the plat in table form for all proposed driveway culverts. The table shall include the adjoining street name, lot and block number, and diameter of each culvert. The design requirements are outlined in Appendix B and in the *Regulations for Walker County Driveway Permits, Design, and Materials*.
- 4.54 The Owner shall provide a letter of serviceability from an entity or entities providing water service. If water service to the subdivision will be by individual private wells, include a note on the plat that says that all lots will be served by private, on-site wells.
- 4.55 All notes on the face of the plat shall be directly related to plan approvals, subdivision regulations, and other federal, state, and local regulations. Specific deed restrictions that are not related to the application or variances granted in relation to the application shall not be listed on the face of the plat.

Section 5 - Amending Plats, Re-plats, or Vacating a Plat

- 5.1 The Owner of a previously recorded lot may create an amended plat to create six or fewer lots in the subdivision or a part of the subdivision covered by the preceding plat if:
- a) The changes do not affect any applicable County regulations, including zoning regulations if the County has authority to adopt zoning regulations; and
 - b) The changes do not attempt to amend or remove any existing covenants or restrictions; and
 - c) All applicable requirements of Section 232.009 of the Texas Local Government Code, as amended, are met.
 - d) The amended plat is prepared in accordance with the final plat requirements of these regulations.
- 5.2 The vacation of an existing plat shall be accomplished in accordance with the applicable provisions outlined in Section 232.008 and/or 232.0083 of the Texas Local Government Code, as amended.
- 5.3 Walker County does hereby adopt, as an alternative to the provisions in Section 232.009 governing the revision of plats, the provisions in Sections 212.013, 212.014, 212.015, and 212.016 governing plat vacations, replatting, and plat amendment. The Commissioners Court may approve a plat vacation, a replat, and an amending plat in the same manner and under the same conditions, including the notice and hearing requirements, as a municipal authority responsible for approving plats under those sections.
- Instead of the purpose described by Section 212.016(a)(10), an amended plat may be approved and issued by the county to make necessary changes to the preceding plat to create six or fewer lots in the subdivision or a part of the subdivision covered by the preceding plat if:
- a) the changes do not affect applicable County regulations, including zoning regulations if the County has authority to adopt zoning regulations; and
 - b) the changes do not attempt to amend or remove any covenants or restrictions.
- 5.4 If an amended plat or a vacated plat is not recorded within two years of the approval by the Commissioners Court, the approval of the amended or vacated plat expires. The Commissioners Court may grant a single six-month extension.
- 5.5 When an amending plat or replat is proposed in order to consolidate lots, the consolidated lots are exempt from the minimum lot frontage requirements.
- 5.6 If permitted by the Commissioner for the Precinct in which the property is located and the existing dedicated right-of-way width is 50 feet or greater, an amending plat or replat of an existing subdivision can utilize the right-of-way width dedicated in the original plat without a variance from the Commissioners Court.

Section 6 - Financial Responsibilities and Guarantees

- 6.1 To protect the public interest, the Commissioners Court of Walker County hereby decrees under the provisions of Chapter 232, Local Government Code, that the Owner of any tract of land that desires to obtain approval of a subdivision plat for recording a plat in the County records shall construct all roads and drainage facilities, including stormwater detention, and any other items required by other governmental agencies, in said subdivision to the standards and specifications set forth in the Engineering Guidelines incorporated as Appendix B of these Regulations before offering said plat for approval, unless the owner meets the requirements of Section 6.4.
- 6.2 When traffic signal and additional turn lanes are required due to anticipated future traffic generated by the subdivision, as determined by the County Engineer or an independent traffic engineer, the future traffic signal shall be included on the Engineer's itemized quantity take-off and be added to the surety provided to the County. Installation of such signals shall be the responsibility of the Owner. Turn lanes and required signals shall be constructed in conjunction with the roadways. If improvements, turn lanes, or traffic signals are required by the Texas Department of Transportation (TXDOT) in relation to the subdivision, then the Owner shall provide written documentation to the County that all necessary TXDOT permits, surety, and construction requirements have been met with the application.
- 6.3 If the subdivision is required to construct off-site stormwater detention, then surety will be required for the construction of the detention facility prior to beginning construction of the subdivision improvements. This surety will be released upon completion of the construction of the detention facility and acceptance of the construction by the County.
- 6.4 If the Owner desires to have the plat approved before the completion of construction of the roads and drainage, then the Owner shall give a good and sufficient security in the form of a bond, cash, or letter of credit acceptable to the Commissioners Court, with the form and content reviewed by the Walker County Criminal District Attorney's Office. The bond or letter of credit must:
- (1) be payable to the County Judge of Walker County and the Judge's successors in office;
 - (2) be in an amount determined by the Commissioners Court to be adequate to ensure proper construction of the roads and streets in and drainage requirements for the subdivision. The security shall contain an amount sufficient for administering the rebidding of the proposed construction should this become necessary. The security amount shall be the full amount of the approved cost of construction. The surety shall be non-cancellable and remain in full force and effect until the obligation is completed.
 - (3) be executed with sureties as may be approved by Commissioners Court;
 - (4) be executed by a company authorized to do business as a surety in this State if the court requires a surety bond executed by a corporate surety; and
 - (5) be conditioned that the roads and streets and the drainage requirements for the subdivision will be constructed:
 - (A) in accordance with the specifications adopted by Commissioners Court; and

(B) within a reasonable time as set by Commissioners Court or based upon a schedule provided by the applicant and accepted by Commissioners Court.

- 6.5 The release of the security shall be conditioned on the completion (in compliance with the Engineering Guidelines and these regulations) of all the roads and drainage facilities shown on the plat.
- 6.6 The Owner may be granted partial reductions of the security requirement upon written approval by the Commissioners Court, and, if applicable, in accordance with the City ordinance when the subdivision lies inside the ETJ of a city.

Section 7 - Maintenance

- 7.1 By accepting a subdivision plat for filing, the Commissioners Court does not thereby accept the roads or improvements in the subdivision for Ownership or maintenance by the County. The Owner of the platted lots and/or the entity identified in the Maintenance Bond will be responsible for maintenance of all roads within the subdivision until such time, if any, as the maintenance of the roads have been accepted by the County.
- 7.2 The entity named in the Maintenance Plan and the Owner shall be responsible for the maintenance of the roads and other associated drainage and improvements in the subdivision.
- 7.3 With the exception of utilities designed and installed in accordance with these regulations, including public water system valves and hydrants, no landscaping, irrigation, sidewalks, illumination, water quality features, or other improvements not related to roads and drainage shall be located within the public rights-of-way, unless the Commissioners Court has granted a specific variance. Any such features proposed shall be included in the maintenance plan submitted with the Plat Application.
- 7.4 Once the construction has been completed and the County Engineer has reviewed the construction, the Owner shall provide the DPD with a paper copy and digital files of the "As-Built" plans showing the original approval signatures and the seal of a Registered Professional Engineer. These plans are to show the improvements as they were actually built. The files shall be in the same format as required in Section 3. After the "As-Built" plans are received and all construction deficiencies have been satisfied, the Owner's Engineer shall submit a dated, sealed, certification that all improvements have been constructed in accordance with the plans and the requirements of these regulations, unless as specific written variance has been granted, the form of this certification is subject to the approval of the DPD and/or County Engineer.
- 7.5 The County will consider accepting a road for maintenance only after dedication to the public of an easement for the roadway and associated drainage, and the minimum standards of these regulations being met. The County may also consider any other factors relating to the public's interest in their decision regarding accepting maintenance of the roads or drainage system.
- 7.6 In addition, written certification from a Registered Professional Engineer and the Owner is required, stating that the improvements were constructed in accordance with the applicable subdivision regulations in effect when the subdivision was recorded along with any written approved variances). If a final plat for the subdivision where the improvements are located was never recorded, the improvements must meet the current applicable subdivision regulations subject to any approved variances.
- 7.7 At the end of construction of the subdivision, but prior to consideration of the release of the construction surety or the acceptance of substantial completion of the roads by the County; the Owner shall provide to the County a bond in the amount of 10% of the total cost of construction of the roads and drainage of the subdivision as determined by Commissioners Court. The security shall be non-cancellable and remain in full force and effect until the obligation is completed. This bond must be payable to the County Judge, or his successors in office, of Walker County, Texas, and must be provided by the owner. Upon receipt of the additional surety and the acceptance of the substantial completion of the improvements by the County Engineer and the Commissioners Court, the County will continue to inspect the infrastructure for failure, defect, or other issues related to

construction or materials for an additional two years. The surety will be released or reduced following the extended inspection periods as described, unless a failure of workmanship or materials, in the sole opinion of the Commissioners Court, has occurred. The Owner will be notified of any deficiencies and given the opportunity to repair such deficiencies. If the Owner does not provide repairs within 30 days, the bond may be used by the County to repair these deficiencies.

- 7.8 Following the extended inspection period detailed above, the Commissioners Court, at its discretion, may conduct a hearing to decide whether or not to accept the roads for public maintenance. The Commissioners Court is not obligated to accept any roads, drainage, or other improvements even when they meet the minimum criteria of these regulations, and may consider other factors related to the public benefit, including but not limited to, the benefits of maintenance and cost of maintenance, the number of dwellings or properties served by the roadways, and the benefits to countywide traffic when making this decision.
- 7.9 The enforcement of deed and plat restrictions are the responsibility of the Owner(s) of the subdivision. However, in the unincorporated areas of Walker County, and the Extraterritorial Jurisdiction, both the city and Walker County, shall have the right and authority to enforce plat restrictions through appropriate legal procedure. This requirement does not create an obligation or requirement on the part of the County or city to enforce any plat restriction unless, in the judgement of the city or County, the enforcement is in public's interest and deemed appropriate or necessary at the time of occurrence.
- 7.10 In the event that the roads and drainage infrastructure are accepted for public maintenance, the County will assume no responsibility for drainage ways or easements in the subdivision outside of the road right-of-way or adjacent easements. Maintenance and liability of improvements not directly related to the roadway and drainage ways, including but not limited to landscaping, illumination, sidewalks, utilities, water quality features, or any other improvements required by other governmental agencies shall not be the responsibility of the County unless specifically approved for maintenance by the Commissioners Court.

Section 8 - Private Subdivisions

All new lots, including lots subject to an exception, must have lot frontages as required by these regulations. If an Owner intends to create a subdivision utilizing private roads, the Owner must receive a direct variance from Section 11 and Appendix B from Commissioners Court, submit a plat application in accordance with these regulations, and, at a minimum, meet the following requirements:

- 8.1 Private roads must meet all County road standards, except where specific variances have been granted by Commissioners Court for adequate cause in each case.
- 8.2 The title of the final plat for private subdivisions shall contain the phrase, "A Private Subdivision".
- 8.3 The subdivision plat and restrictions must contain a statement that Walker County will at no point be under any obligation to accept maintenance of the roads or associated drainage features, as the roads and associated drainage features were developed and approved, by request of the owner, specifically for private maintenance.
- 8.4 The plat must include a note identifying the entity referenced in the maintenance plan that shall be responsible for the on-going maintenance of the roads, rights-of-way, signage, drainage, gates, and other improvements within the subdivision.
- 8.5 The plat must include a note stating that any gates shall be accessible by emergency services personnel and all residents and landowners of the platted subdivision.
- 8.6 The subdivision plat must contain a statement that the entity referenced in the maintenance plan must ensure that the roads, rights-of-way, signage, drainage, gates, and other improvements shall be maintained to a standard that will allow emergency vehicles access for the roadway design speed in perpetuity.
- 8.7 The plat must contain a requirement that every deed contains a notice to the grantee that all roads are private and state the name of the entity that shall be perpetually liable for maintenance, that the County will never accept them for maintenance, and that the quality of the roads must be maintained as to not affect access by public service agencies such as police, fire, and emergency medical services.
- 8.8 All arterial roads must be dedicated to the public. Other roads must be dedicated to the homeowners association or other entity identified within the maintenance plan for the use of the property Owners, their assigns and successors, and emergency response agencies.
- 8.9 A sign must be placed at the entrance of the subdivision clearly stating that the roads in this subdivision are private roads. The location of this sign must be shown in the construction plans.
- 8.10 Any Owner that gates the entrances to the subdivision must provide either a crash gate or a lock box and a letter of approval from all of the affected emergency response agencies stating their approval of full-time access to and from the subdivision.
- 8.11 All road signs and signage in the subdivision shall be marked private and include design requirements as adopted by the County for public and private roads.
- 8.12 The County will not be responsible for providing traffic control enforcement within private subdivisions.

Section 9 - Variances

- 9.1 A variance is a grant of relief to a property owner from strict compliance with these regulations. The intent of a variance is not to simply remove an inconvenience or financial burden that may result from compliance with applicable regulatory requirements. Variances are intended to help alleviate an undue hardship that would be caused by the literal enforcement of the subject ordinance requirements. Variances are intended to provide relief when the requirements of these regulations render construction or placement of improvements impractical or impossible because of some unique or special characteristic of the subject property itself.
- 9.2 The Commissioners Court of Walker County shall have the authority to grant variances to these Regulations when the public interest, improved design functionality, or the requirements of justice demands relaxation of the strict requirements of the rules.
- 9.3 Any person who wishes to receive a variance shall apply with the proper forms and fees to the Department of Planning and Development.
- 9.4 All variances must be applied for separately from and prior to the application to which the variance is applicable and shall include all applicable information necessary for the review of the variance. In cases where an applicant has received a variance a copy of the approved variance must be submitted with any application to which it applies in order for the application to be considered complete.
- 9.5 The decision of the Commissioners Court whether to grant or deny a variance is at its complete discretion and shall be final.
- 9.6 If a plat or variance is approved by the Commissioners Court or is approved with condition(s), documentation of the variance approval will be provided to the applicant following the approval of the Commissioners Court's minutes.
- 9.7 Unless the plat, plans, or construction is completed including any required contingencies, filing, and/or inspections, all variances granted will expire 3 years from the date they are granted unless a specific term is set by the Commissioners Court in its action on the variance or the variance is specifically extended in writing by Commissioners Court.

Section 10 - Penalties

- 10.1 Section 232.005 of the Texas Local Government Code, as amended, provides for the enforcement of the state subdivision laws and of these Regulations.
- 10.2 A person commits an offense if the person knowingly or intentionally violates a requirement of these Regulations, including the Engineering Guidelines and other appendices incorporated herein. Such offense is a Class B Misdemeanor, punishable in July 2011 by (1) a fine not to exceed \$2,000; (2) confinement in jail for a term not to exceed 180 days; or (3) both such fine and confinement. (Texas Penal Code, Title 3, Ch. 12, Sec. 12.03, as amended).
- 10.3 A person may be jointly responsible as a party to an offense if the person (acting with intent to promote or assist the commission of the offense) solicits, encourages, directs, aids, or attempts to aid another person to commit the offense (Texas Penal Code, Title 2, Sec. 7.01, as amended). Thus, a real estate agent or broker, construction contractor, a lender, an attorney, a surveyor, an engineer, a title insurer, or any other person who assists in violating these Regulations may also face criminal penalties.
- 10.4 Besides prosecuting a criminal complaint, the County Attorney or other prosecuting attorney for the County may file a civil action in a court of competent jurisdiction to enjoin any violation or threatened violation of these Regulations and to recover damages.
- 10.5 A tract that has been subdivided without compliance with these Regulations will be ineligible to obtain a permit for the construction or modification of an On-Site Sewage Facility or the issuance of a Development Permit under the Walker County Floodplain Development, until such time as the tract has been brought into compliance.

Section 11 - Minimum Lot Frontage

- 11.1 All lots, including those subject to an exception, must have a minimum frontage length, as described in Appendix B2.1, on an existing County road unless otherwise specifically allowed by these regulations.

Appendix A - Platting Guidelines

As a guide to the public in determining when it is necessary to file a plat and comply with these Regulations (as amended), the Commissioners Court (as an incident of its power to enforce the subdivision laws and regulations under Chapter 232, Texas Local Government Code, as amended) has adopted the following policy guidelines stating when the division of an existing tract shall be considered by the Court to be a subdivision requiring the filing of a plat by law and/or compliance with regulations adopted under Chapter 232 authorizing the regulation of plats and subdivisions of land, and thus requiring compliance with these Regulations:

A1 - Plat Required

A1.1 Unless otherwise specifically exempted in these regulations, the owner of a tract of land located outside the limits of a municipality must have a plat of the subdivision prepared and approved under these regulations if the owner divides the tract into two or more parts to layout:

1. a subdivision of the tract, including an addition;
2. Lots; or
3. streets, alleys, squares, parks, or other parts of the tract intended by the owner of the tract to be dedicated to public use.

A division of a tract includes division regardless of whether it is made by using a metes and bounds description in a deed of conveyance or in a contract for deed, by using a contract of sale or other executory contract to convey, or by any other means.

A1.2 If a plat is required under these guidelines, it is immaterial that the division of daughter tracts is by contract, option, lease, or lease-purchase, rather than by deed, or that the daughter tracts are described by metes and bounds rather than lot and block.

A1.3 If the subdivision is for a Condominium Development, and if two or more structures, portions of structures, areas, or spaces are offered for sale, rent or lease, then the subdivision shall comply in all respects with these Regulations and the Walker County Engineering Guidelines. If compliance is required, an application for plat approval of the proposed Subdivision shall be prepared and submitted to the Commissioners Court in accordance with the terms and procedures set forth in these regulations. The final plat must be filed and recorded with the Walker County Clerk. This section excludes Manufactured Housing Communities separately regulated under the Walker County Manufactured Home Rental Community Regulations.

A1.4 For the purpose of compliance with the Walker County Subdivision Regulations, any proposed RV Park or addition to any existing RV Park must comply with the minimum requirements of the current version of the Walker County Manufactured Home Rental Community Regulations. The requirements of said regulations must be applied to the RV Park in the same manner as they would to a Manufactured Home Rental Community. RV Park submittals must be submitted under the fee schedules and under the application requirements of the Walker County Subdivisions Regulations.

A1.5 Residential Rental Community submittals must be submitted under the fee schedules and under the application requirements of these regulations. For the purpose of compliance with the Walker County Subdivision Regulations, any proposed Residential Rental Community, or addition to any existing Residential Rental Community, must comply with the minimum requirements of the current version of the Walker County Manufactured Home Rental Community Regulations. The requirements of said regulations must be applied to the Residential Rental Community in the same manner as they would to a Manufactured Home Rental Community, except as follows:

1. All rental spaces shall comply with the frontage requirements of the Walker County Subdivision Regulations, in the same manner as if they were lots.
2. All rental spaces shall comply with the minimum and maximum depth to width requirements of the Walker County Subdivision Regulations, in the same manner as if they were lots.
3. All drainage design criteria shall comply with the Walker County Subdivision Regulations.

A2 - Exceptions by Law

A2.1 A property that has frontage on a public street and whose boundary has not changed since February 1, 2000, is considered a legal lot, unless said tract is otherwise required to complete a replat under State law. *[Texas Court of Appeals, Elgin Bank v. Travis County]*

A2.2 In accordance with Section 232.0015, Texas Local Government Code, as amended, the filing of a plat is not required when the Owner does not lay out a part of the tract as described by Texas Local Government Code 232.001 (a)(3), and when the subdivision meets one of the requirements listed below (A2.2.1 – A2.2.8). In compliance with 232 Texas Local Government Code and these regulations and in order to qualify for exception, all daughter tracts must meet the minimum frontage requirements as required by these regulations, not be a part of a previously platted subdivision, and must apply for and file an approved affidavit of exception.

A2.2.1 All daughter tracts are greater than 10 acres. *[LGC § 232.0015(f)]*

A2.2.2 The land is to be used primarily for agricultural use, as defined by Article VIII, Section 1d, Texas Constitution, as amended, or for farm, ranch, wildlife management, or timber production use within the meaning of Art. VIII, Sec. 1-d-1, Texas Constitution, as amended. *[LGC § 232.0015(c)]* If a tract of land ceases to be used primarily for these uses, the Owner shall be required to comply with these Regulations on the same basis as any newly divided tract. *[LGC § 232.0015(d)]*

A2.2.3 A person makes a conveyance of four or fewer tracts, each of which is sold, conveyed, given, or otherwise transferred, to persons who are related to the Owner within the third degree of consanguinity (parent, child, grandparent, grandchild, sister, brother, great-grandparent, great-grandchild, aunt, uncle, niece, nephew) or affinity (the spouse of anyone listed above, or so related to the Owner's spouse) for their personal use. *[LGC § 232.0015(e)]*

A2.2.4 All daughter tracts are to be sold to veterans through the Veteran's Land Board Program. *[LGC § 232.0015(g)]*

A2.2.5 The Owner of the land is the State of Texas, an agency, board or commission of the State of Texas, or a permanent school fund or other dedicated fund of the State, and the Owner does not lay out any part of the tract for roads, parks, or other areas for the common use of two or more tracts or the use of the public. *[LGC § 232.0015(h)]*

A2.2.6 The Owner is a political subdivision of the State of Texas, the land is situated in a floodplain, and all lots are sold to adjoining landowners. *[LGC § 232.0015(i)]*

A2.2.7 The Owner divides the tract into two parts and one new part is retained by the Owner and the balance of the property is transferred to another person who will further subdivide the tract subject to the platting requirements herein. *[LGC § 232.0015(j)]*

A2.2.8 The Owner transfers all parts to persons who owned an undivided interest in the original tract and a plat is filed before any further development of any part of the tract. [LGC § 232.0015(k)]

- A2.3 All exemptions in this subsection must be approved in writing by the County Engineer and/or DPD prior to the division of the property. To claim any exemption, the person or entity who claims to be entitled to any exclusion to platting set out in these Guidelines must provide:
- A2.4 An affidavit claiming the exemption and setting out the detailed basis for exclusion from the platting requirement, subject to penalties of perjury.
- A2.5 A copy of the deeds or other instruments creating the daughter tracts referenced in the affidavit.
- A2.6 The division shall comply with any other applicable State or Local regulations including but not limited to on-site sewage and floodplain regulations.

A3 - Additional Exceptions

The Commissioners Court has adopted the following additional policy guidelines stating the division of an existing tract may be considered exempt from the requirement to file a plat and may instead apply for and file an affidavit of exception. In order to qualify for an exception, all daughter tracts must meet the minimum frontage requirements as required by these regulations, not be part of a previously platted subdivision, and must apply for and file an approved affidavit of exception (A3.1-A3.11). Exception under A3.3 do not require tracts to meet the minimum lot frontage requirements.

- A3.1 Any tract whose boundary has not changed since February 1, 2000, may be sold in its entirety without being platted.
- A3.2 A plat is not required when daughter tracts are created solely for purposes of platting them as individual subdivisions in their own right, providing that each daughter tract has at least 125 feet of frontage on a publicly maintained road. The Owner must submit to the Court the preliminary plat for the project as a whole before claiming this exception.
- A3.3 A plat is not required when two or more adjacent landowners, or a single landowner owning two or more adjacent tracts, adjusts or changes the property lines that separate their (the) respective tracts, so long as there is the same number of tracts in existence before and after the transaction. This exemption applies whether the transaction requires an exchange of land by both Owners, or only a transfer of land from one Owner to the other, and whether the transaction takes the form of a sale or an exchange in kind. Any land added to a tract through such a transaction shall become an integral part of that tract, and may not be separately conveyed, except in compliance with the subdivision laws. Each resulting tract shall be subject to the minimum lot size requirements of these Regulations and other applicable laws. This exception does not apply if the adjustment will change the boundary between two legally platted lots or add or subtract land from a legally platted subdivision.
- A3.4 With the exception of exceptions under Section A2 and A3.3 (Adjacent Landowner) an exemption may not be exercised within five years of exercising another exemption.
- A3.5 A plat is not required when a smaller tract is surveyed out of the parent tract solely for the purposes of obtaining financing for purchase or improvement of that part of the property, provided that

possession and primary beneficial Ownership of the entire parent tract are intended to remain unified.

- A3.6 A plat is not required when a smaller tract is created by the legitimate foreclosure of a valid lien on a part of the parent tract. This provision does not exempt sham transactions or foreclosures staged to avoid the platting requirement.
- A3.7 A plat is not required if the property has been divided by the final decree of a court of record with appropriate jurisdiction.
- A3.8 A plat is not required for non-residential commercial and retail developments divided by lease into 2 or more separate spaces, not to exceed 60 months.
- A3.9 All exemptions in this subsection must be approved in writing by the County Engineer and/or DPD prior to the division of the property. To claim any exemption, the person or entity who claims to be entitled to any exclusion to platting set out in these Guidelines must provide:
- a) An affidavit claiming the exemption and setting out the detailed basis for exclusion from the platting requirement, subject to penalties of perjury.
 - b) A copy of the deed for the parent tract(s).
 - c) A copy of a survey or surveys sealed by a Registered Professional Land Surveyor of the proposed daughter tracts, and their general location in relation to the parent tract.

The division shall comply with any other applicable State or Local regulations, including but not limited to on-site sewage and floodplain regulations.

Appendix B - Engineering Guidelines

B1 - Graphic Requirements

- B1.1. Provide legible construction drawings, to an accurate scale, and provide a north arrow where applicable. Construction drawings shall be accurate, complete, and not conflict with the plat, specifications, or within the sheets. The plans and plat shall clearly present the proposed design for the development without magnification. Incomplete plan sets will be rejected.
- B1.2. The seal, date, and signature of the Professional Engineer responsible for the plans and calculations are required on each sheet developed by the design engineer, which shall be in accordance with the Texas Board of Professional Engineers and Licensed Surveyors Laws and Rules. Reports shall also include the seal, date, and signature of the responsible Professional Engineer.
- B1.3. Provide a cover sheet for projects involving three or more design plans, excluding detail sheets. Plan sheet numbers and titles must be listed on the cover sheet. Include a vicinity map to identify the project location. Show pertinent City Limits and ETJs on the vicinity map. If revisions occur after plan approval, list the revision(s) and associated sheet number(s) on the cover sheet of the plans and resubmit the plans for review and approval. Include the following notes on the cover sheet, when applicable:
- a. The design of this project will not negatively impact this property or adjacent properties/roadways.
 - b. Detention basins shall be constructed prior to placement of impervious cover.
 - c. Utilities and drainage within 2 horizontal feet of roadways shall be fully encased in a minimum of 6 inches of 2-sack cement stabilized sand.
 - d. The geotechnical investigation for this project was conducted per the latest edition of the Walker County Subdivision Regulations. Soils report was prepared by *[Geotechnical Engineering Firm]* Report No. *[No. of Report]*, dated *[Date of Report]*. All construction and materials testing, including but not limited to testing of right-of-way compaction, subgrade, and concrete, shall be performed by an A2LA Certified Independent Testing Laboratory.
 - e. A mandatory Walker County Pre-Construction Conference shall be held at least 72 hours prior to construction. Contact Walker County Planning & Development to schedule the Walker County Pre-Construction Conference.
 - f. The Contractor/Engineer shall request a pre-pave inspection from Walker County Planning & Development 72 hours prior to paving, after the Engineer deems the project is ready for paving. The pre-pave request shall include a certification from the Engineer. Pavement placed without a "no objection" obtained from the County may jeopardize County certification and/or acceptance.
- B1.4. Each set of engineering plans shall contain paving and drainage key drawings, indexing specific plan and profile sheets.
- B1.5. Draw key overall layouts and drainage area maps to a minimum scale of 1" = 200'.
- B1.6. Provide plan and profile sheets with complete, clear stationing. Generally, stationing runs down the centerline of streets and is used for all improvements in and adjacent to the right-of-way. Plan stationing must run from left to right, except for short streets or lines originating from a major intersection, where

the full length can be shown on one sheet. Plan and profile sheets are not required for projects subject to the Walker County Manufactured Home Rental Community Regulations.

B1.7. Standard scales permitted for plans and profiles drawings are as follows:

1" = 20' Horizontal, 1" = 2' Vertical
1" = 40' Horizontal, 1" = 4' Vertical, or
1" = 50' Horizontal, 1" = 5' Vertical

The above scales are minimum; larger scales may be used to show details of construction.

B1.8. Make a statement on the cover sheet referencing assumed control coordinates.

B1.9. Each sheet of the plan and profile shall have a benchmark elevation and description defined. Projects in flood-prone areas shall be tied to the NAVD 1988 datum or the datum used for current FEMA maps. If the property lies below the base flood level, the floodplain must be delineated graphically on all plan sheets.

B1.10. If a roadway exists where plans are being prepared to improve or construct new pavement or a utility, label the existing roadway width, surfacing type, and thickness.

B1.11. Show all street and road alignments on plans.

B1.12. Show and label proposed pavement and ditches, typical cross-sections, details, lines, and grades, existing topography within the street right-of-way, and any existing or proposed easement. At the intersection, the cross-street details shall be shown at a sufficient distance (20-foot minimum distance outside the primary roadway right-of-way) in each direction along the cross-street for designing adequate street crossings.

B1.13. Match lines between plan and profile sheets shall not be placed or shown within cross-street intersections including cross-street right-of-way.

B1.14. A drainage area map shall be submitted and shall include drainage computations with drainage area and storm water flow labeled.

B1.15. Basic plan and profile sheets shall contain the following information:

- a. The profile vertical scale shall be 1/10th the horizontal scale.
- b. The plan view and profile view shall be on the same sheet whenever practical.
- c. All existing and proposed utilities and pavement shall be on the same plan and profile sheet for a given section.
- d. Identify lot lines, property lines, easements, rights-of-way, and outfalls.
- e. Label each plan sheet as to street/easement widths, pavement widths, pavement thickness where applicable, type of roadway materials, curbs, intersection radii, curve data, stationing, existing utilities (type and location), and any other pertinent feature affecting design. The minimum text size shall be 0.08 inches.
- f. Show water, sewer, paving, and drainage design in and adjacent to right-of-way on the same plan and profile sheets. Graphically show and label flow line elevations, slopes, and direction of flow for ditches.
- g. Show and label all ditches, swales, culverts, headwalls, erosion control, detention ponds, and any other drainage structures or facilities.

- h. Show and label floodplains.
 - i. Label proposed top of curb grades except at railroad crossings. Centerline grades are acceptable only for paving without curb and gutters.
 - j. Show in profile curb return elevations for turnouts.
 - k. Show existing and proposed station median noses or the centerline of median openings, including median width.
 - l. The design of both roadways is required on paving sections with a median.
 - m. In plan view, show station PCs, PTs, and radius returns. Show in profile station radius returns and grade change PIs with their respective elevations.
 - n. Show all water and sewer service leads in plan view.
 - o. Specify the rim and all flow line elevations at all inlets and junction boxes. Locate inlets within 5 feet of lot lines.
 - p. In profile view, show all storm sewer and label length, grade, material, and size.
 - q. In profile view, show and label existing ground profiles at both right-of-way lines.
 - r. The location of all existing and proposed water bodies on or immediately adjacent to the subject property.
- B1.16. All plan revisions made after final plan approval, including as-built revisions, shall be signed and sealed by a registered engineer, including a date that reflects the plan revision date. The revisions issued after the plan approval shall be clouded.

B2 - Lot, Utility Easement, and Setback Requirements

B2.1. Lots shall have minimum frontages as follows:

A minimum frontage of 125 feet is required for all open ditch roads unless the lot complies with the applicable standard for flag, knuckle, or cul-de-sac lots.

The minimum frontage for all other lots is 80 feet unless the lot complies with the applicable standard for flag, knuckle, or cul-de-sac lots. Lots shall have a minimum depth of no less than 160 feet.

B2.2. Lots with less than 125 feet of frontage shall have a maximum depth no greater than three times the frontage of the lot, with the exception of cul-de-sacs, knuckles, and flag lots (See B2.3 and B2.4). Lots with 125 feet of frontage or greater shall have a maximum depth no greater than four times the frontage of the lot.

B2.3. Flag lots shall have a minimum staff width of 50 feet, and no portion of the lot shall have a width of less than 50 feet. The depth of the flag shall not exceed three times the average width of the flag. The average width shall be calculated as the average of the frontage and the back lot line widths. No more than two consecutive flag lots can adjoin.

B2.4. Lots with frontage along a cul-de-sac or knuckle shall have a minimum frontage of 50 feet. The depth of the lot shall not exceed three times the average width of the cul-de-sac or knuckle lot. The minimum average width shall be the same as the required frontage. For lots along cul-de-sacs and knuckles, the average width shall be calculated as the average of the frontage and the back lot line widths.

B2.5. For determining the area required for an on-site sewage facility, the minimum lot size shall be in accordance with the current regulations of Walker County, the Texas Commission on Environmental Quality, or the Authorized Agent having jurisdiction, whichever regulation is most stringent.

B2.6. The minimum building setback line on arterial roadways shall be 50 feet from the edge of the right-of-way.

B2.7. The minimum building setback line on all collector and local roads shall be 25 feet from the edge of the right-of-way.

The right-of-way shall be used for the purpose of paving and maintaining streets and installing, containing, and maintaining storm sewers. Any additional utilities will require a separate utility easement outside the street rights-of-way, with the exception of fire hydrants and water valves that are located either 5 feet from the edge of the road or on the high bank of the ditch's backslope, whichever is furthest from the edge of the road. Fire hydrants and water valves shall not be located in such a way as to obstruct the maintenance of public improvements or designed/constructed drainage capacity or flows.

B2.8. Where a subdivision is made on an existing publicly maintained road and there are existing utilities in place, see section B4.13(2).

- B2.9. All roads, public and private, shall have a minimum 20-foot utility easement adjacent and parallel to the road right of way. Public roads shall have a public utility easement. Private roads have the option of using private utility easements. Where a utility easement overlaps a public drainage easement, the utility easement shall extend a minimum of 10 feet outside the drainage easement (excluding "box easements"). The utility provider may require additional width, and utilities shall not be located within the public drainage easement except for perpendicular crossings.
- B2.10. With the exception of "Private Subdivisions," the plat shall provide a public drainage easement, sufficient to contain the designed and constructed roadside ditches parallel and adjacent to the public right of way. Additionally, the plat shall provide for a minimum 30-foot-by 30-foot "box" drainage easement adjacent to the right-of-way, upstream and downstream of each culvert where it crosses a street. All public drainage easements shall be noted on the plat as "D.E.," and the notation shall be included in the legend.
- B2.11. Easements shall be provided, where necessary, for all drainage courses in and across the property to be platted. The location and width shall be shown on the plat and marked "Private Drainage Easement" or "Private Drainage and Underground Utilities Easement". In general, a "Private Drainage Easement" shall be a minimum of 20 feet in width when it is not parallel to a public right of way. All drainage easements shall be located in such a manner as to be locatable on the ground. Owner is responsible for the maintenance of private easements. See B12.12.c for storm sewer easement requirements. All Private Drainage Easements shall be noted on the plat as "P.D.E." and the notation shall be included in the legend. P.D.E.s are also required for lot-to-lot drainage within Urban Subdivisions.
- B2.12. The following roads are designated as arterial roadways. The Commissioners Court may specify additional roadways upon recommendation by the County Engineer:
- All roads maintained under the State or Federal system of Roads including but not limited to roads designated as Farm to Market Roads, State Highways, Interstate Highways, and United States Highways.*
- B2.13. If the building setback lines, as stated above, conflict with the setback requirements adopted by a municipality, the municipal requirements shall prevail if they are in the ETJ of the municipality.

B3 - Road Alignments

- B3.1. New roadways that do not connect to an existing publicly maintained road will not be approved without a specific variance.
- B3.2. An internal road system that minimizes driveways and cross-streets to existing County or other public roadways is required. Lots bordering on an existing arterial road shall have access to an internal, platted road, and the final plat shall contain a restriction requiring driveways to connect only to an internal, platted road.
- B3.3. Road Intersections
 - B3.3.1. Roads shall be designed and constructed to intersect with each other at 90 degrees, plus or minus 10 degrees. The acute angle of the intersection shall have a 30-foot minimum radius for both the right-of-way and paving.
 - B3.3.2. At a "T" intersection, where a street has not been improved to its ultimate width, the pavement shall be stopped at either the right-of-way line or the end of curve return.
 - B3.3.3. The minimum offset between road intersections shall be 200' (centerline to centerline).
- B3.4. Points of Access
 - B3.4.1. Developments that exceed 40 dwelling units shall be provided with two separate and approved access roads. Exception: Where there are 41 to 149 lots or dwelling units, a single access point will be permitted if that access provides a 40-foot wide travel way. A dwelling unit is defined as a single unit of residence for a family of one or more persons.
 - B3.4.2. Where two access roads are required, they shall be placed a distance apart equal to, but not less than, one-half of the length of the maximum overall diagonal dimension of the property or area to be served, measured in a straight line between access points.

B4 - Minimum Road Design Requirements

- B4.1. Unless otherwise stated in these Regulations, all roads shall be designed and constructed in accordance with 2024 TxDOT Standard Specifications.
- B4.2. Subdivisions of thirty (30) lots and less, being out of the parent tract, that utilize frontage or access along existing publicly maintained roads, are not required to improve existing roadways but shall dedicate right-of-way out of the parent tract based on an acceptable alignment. If more than 30 lots in the proposed subdivision have frontage on an existing public right of way, the existing public street shall be improved along the frontage to meet the requirements of these Regulations. Any lot with frontage on an open ditch roadway shall be 1 acre in size and have a minimum frontage of 125 feet, or in the case of cul-de-sac, knuckle, and flag lots, meet the applicable frontage standard detailed in these regulations. See Section 5 for frontage exceptions related to replats and amending plats.
- B4.3. Lots intended to access future roads will not be approved.
- B4.4. For purposes of this Appendix, ADT shall be defined as the anticipated average daily traffic at the time of complete build-out of the subdivision, including any future development that may be served by a given road. For planning purposes, it shall be assumed that single-family residential lots will generate a minimum 9.44 ADT. If an area of future development consists of ½ acre or more, it shall be assumed that such development will produce an ADT of 57 per acre, unless there is a note prohibiting future subdivision and limiting the lot to single-family residential construction.
- B4.5. Areas of future development with residential, commercial, or unspecified land use (including reserves or residuals) must have separate and independent access from that of the streets within the proposed development and may not be connected to street within the development, unless road design and construction within the proposed development meet the applicable standard for the average daily trips for ultimate buildout of the residential, commercial, or unspecified land use.
- B4.6. Roadways shall be classified as Arterial, Collector, or Local Streets and conform to Table B4.1.

Table B4.1 Roadway Design Standards

Street Classification ⁽¹⁾		Projected Volume per Day ⁽²⁾	Min. Number of Travel Lanes (Min. 12' Wide)	Min. Center Lane Width (ft)	Min. Paved Shoulder Width (ft)	Is Curb & Gutter ⁽³⁾ Required	Min. Pavement Width ⁽⁴⁾ (ft)	Min. Right-of-Way Width (ft)	Min. Design Speed (MPH)	Min. Design Storm ⁽⁵⁾ (Yr)
Arterial	Rural	12,000+	2	14	6	No	50	100	45	10
	Urban	12,000+	4	20		Yes	69	100	45	10
Collector	Rural	6,000-11,999	TO BE DETERMINED BY COMMISSIONERS COURT ⁽⁶⁾						40	10
		2,000-5,999	2		2	No	28	80	40	10
	Urban	6,000-11,999	2	14	8 ⁽⁷⁾	Yes	55	80	40	10
		2,000-5,999	2		8 ⁽⁷⁾	Yes	41	60	40	10
Local	Rural	< 2,000	N/A			No	26	70	35	10
	Urban	< 2,000	N/A			Yes	32	50	35	5
Low	Rural	< 190 ⁽⁸⁾	N/A			No	22	60	35	10

Notes:

- (1) Refer to Section 2 for Rural and Urban definitions.
- (2) Roads with a projected volume over 6,000 trips per day shall have striping.
- (3) If curb and gutter is not required, the developer can choose to install curb and gutter in lieu of shoulders. Standard 6" concrete curbs and 4"x12" rollover curbs are permitted. Within urban single-family residential subdivisions where residential lots have frontage, 4"x12" rollover curbs are required. Asphalt will not be permitted on curb and gutter or open ditch roadways. Refer to Appendix G for details.
- (4) For curb and gutter pavement sections, this measurement is from back of curb to back of curb.
- (5) Culverts under streets shall be designed and installed per Appendix B.12.
- (6) The developer shall provide an engineer's recommendation, land plan, TIA, and typical cross-section based on traffic volume. The 80-foot minimum right-of-way width must be justified based on site conditions and roadway width.
- (7) The paved shoulder on Urban Collectors is a parking lane.
- (8) Must be in a rural development consisting of only one street that is less than 1,000 linear feet in total length.

B4.7. Refer to Appendix F for roadway cross-sections, Appendix G for curb and gutter details, and Appendix H for concrete pavement details. The details in the appendix provide the minimum County requirements, and the construction plans shall include a site-specific design prepared by a professional engineer that is equal to or greater than the minimum requirements, including the minimum design life and traffic loading during and after construction. The final details and design shall be signed and sealed by a professional engineer.

B4.8. Residential lots shall not have direct access to arterial roads.

B4.9. If the Collector road is included in a roadway or transportation plan, the right-of-way and pavement cross-section shall be as required in the plan.

B4.10. Local roads shall be designed as follows:


- a. Developer can choose to install curb and gutter in lieu of shoulders on local roads. Standard 6" concrete curbs are permitted. Rollover curbs (4"x12") are permitted in single-family residential subdivisions where residential lots have frontage.
- b. Block length shall not exceed 1,250 feet (centerline to centerline) for urban lots and 2,500 feet for rural lots; the minimum distance shall be 200 feet. Exception: developments with a minimum of 5-acre lots may have up to 5,000-foot block lengths.

B4.11. The following standards apply to all roads:

- a. Pavement striping shall comply with the Texas Manual on Uniform Traffic Control Devices.
- b. Provide steel casing or C900 DR 18 PVC casing on all water and sanitary sewer crossings under proposed arterial and collector streets. Casing shall extend a minimum of 5 feet beyond the edge

of the pavement. Steel casing shall have a minimum wall thickness of 0.375 inches, rolled steel type. Spiral steel will not be allowed. Exemption: service leads are not required to be cased.

- c. All utility installations shall comply with Texas Administrative Code, Title 43, Part 1, Chapter 21, Subchapter C.
- d. All pipeline installations shall be reviewed and approved by Walker County. Where utilities cross pipelines, signage shall be installed where the utility crosses the pipeline's easement line, one foot outside of the easement. The sign shall note the type of utility crossing the pipeline (i.e., water, sewer, storm, gas, etc.).
- e. Roads shall be dedicated to the public except as indicated in Section 8. The Owner may dedicate the right of way or an easement for road, drainage, and utility purposes, at the Owner's option.
- f. Accepted roads must have driveways that meet Walker County standards. The most restrictive criteria shall apply.
- g. Driveways shall comply with the Regulations for Walker County Driveway Permits, Design, and Materials.
- h. Where concrete curb and gutter are constructed, they shall be constructed per 2024 TxDOT Specification Item 529.
- i. Loops, being a single street connecting to the same street on each end, shall not exceed 2,500 feet for urban streets and 5,000 feet for rural streets. Exception: developments with a minimum of 5-acre lots may have up to 10,000 linear-foot loops.
- j. Dead-end streets shall not exceed 1,250 feet for urban streets and 2,500 feet for rural streets unless a future extension is planned. Exception: developments with a minimum of 5-acre lots may have up to 5,000 linear-foot dead-end streets.
- k. Manholes shall not be located in or under the street pavement.
- l. The minimum grade for all roads shall be 0.5% and the maximum grade shall be 7%.
- m. Curb and gutter roads shall have a minimum 1% fall around intersection turnouts for a maximum radius of 35 feet. Grades for larger radii shall be determined on an individual basis.
- n. The minimum street intersection radii shall be 25 feet. The minimum cul-de-sac and knuckle radii requirements are as follows:



- o. All roads shall maintain a height clearance of at least 14 feet.
- p. Provide a vertical curve anywhere the algebraic difference between grades exceeds one percent. Specify the PI station and elevation, and specify the K Value. Design curves in accordance with the TxDOT Roadway Design Manual.
- q. Local Roads may have a minimum centerline radius of 300 feet or more as long as minimum sight distance requirements are met. Local Roads that do not have a minimum centerline radius of 300 feet, Collector Roads, and Artillery Roads shall be designed in accordance with the 2024 TxDOT Roadway Design Manual. The minimum tangent on reverse curves between points of curvature shall be 50 feet.
- r. Provide a cut back a minimum of 15 feet from the point where the street right-of-way lines would intersect to provide a visibility triangle. A 25-foot radius at intersecting right-of-way lines is also acceptable.
- s. A permit, encroachment agreement, or letter of no objection from the pipeline company, is required when paving is placed over transmission pipelines. Whenever possible, roadway crossings of pipelines shall be avoided or minimized by design, and perpendicular crossings are required. All existing utilities crossing proposed streets shall meet the minimum TxDOT utility crossing criteria, including but not limited to the requirements of TAC Chapter 21.
- t. In new subdivisions, the Owner shall install cluster mailboxes at the location(s) approved by the US Postal Service. The placement of individual or cluster mailboxes along arterial and collector roads shall not be permitted in new subdivisions unless specifically approved by the Commissioners Court. Mailboxes shall not encroach on/over sidewalks or other public walks or ways in the County right-of-way. Mailboxes shall be installed in accordance with applicable postal regulations. Individual and cluster mailboxes shall not be installed in such a way as to negatively impact road or drainage capacity, design, or function.
- u. All pavements are to be designed by a Registered Professional Engineer. The design shall be based on a minimum 20-year design life and in conjunction with recommendations based upon a soils report of samples taken along the proposed roadways. Test borings shall be placed at a maximum spacing of 500 feet or other sampling frequency approved by the County Engineer based on recommendations provided by the geotechnical engineer. The soils report and pavement design shall be submitted to the County Engineer for review. The pavement design must be approved by the County Engineer prior to or concurrently with the review and approval of the construction plans. In addition to the basis of the pavement design, the soils report shall contain the results of sampled and tested subgrade for plasticity index, pH, sulfate content, and maximum density.
- v. Provide a Traffic Control Plan in accordance with the Texas Manual on Uniform Traffic Control Devices.

B4.12. The following requirements apply to dead-end roads and cul-de-sacs:

- a. Dead end roads having a throat length longer than 150 feet shall have a cul-de-sac with a minimum right-of-way radius of 50 feet (40 feet minimum pavement radius to face of curb/edge or edge of pavement). A cul-de-sac is not required on dead-end streets that have a throat length of 150 feet or less.
- b. "No Outlet" signs must be placed at the entrance to the dead-end road, even if the road is planned to be extended in the future.
- c. Dead end roads that end at undeveloped property must be extended to the property line. At the terminus, a temporary cul-de-sac shall be provided for all such streets having a throat length more

than 150 feet, constructed in accordance with the requirements of this Appendix. Hammerhead design will not be allowed; however, alternate designs, such as landscape center islands, may be considered by the County Engineer to ensure a sufficient turnaround area is provided.

- d. For all temporary cul-de-sacs, provide a minimum easement radius of 50 feet (40 feet pavement radius to face of curb/edge or edge of pavement). Temporary easements shall be established for the portions of the cul-de-sac that lie outside of the road right-of-way. Such easements that lie within the plat boundary shall be shown on the final plat. Easements that lie outside the boundary of the plat may be in the form of a separate document but must be recorded prior to the construction of any roadway improvements or final plat approval. The plat or easement document shall include a note stating the easement shall automatically terminate upon the date a plat or other appropriate instrument has been recorded that publicly dedicates a road extension.
- e. Standard TxDOT barricades shall be placed at the end of all dead-end roads not terminating in a cul-de-sac.

B4.13. Additional Right of Way for Existing Roads

When a subdivision is adjacent to an existing road, the DPD or County Engineer shall determine the right-of-way width that will be necessary for the maintenance and improvement of the existing road. If the existing road is an Arterial roadway, as defined herein, the Owner shall dedicate to the public up to 100 feet in the overall width of the right-of-way, as determined by Commissioners Court. The Owner shall dedicate an easement for the road, drainage, and utility purposes. No utilities, debris, landscaping, irrigation, sidewalks, illumination, water quality features, or other improvements not related to roads and drainage shall be located within the public rights-of-way, unless the Commissioners Court has granted a specific variance, with the following exception:

- 1) fire hydrants that are located either 5 feet from the edge of the road or on the high bank of the ditch's backslope, whichever is furthest from the edge of the road. Fire hydrants shall not be located in such a way as to obstruct the designed/constructed drainage capacity or flows.
- 2) Where a subdivision is made on an existing publicly maintained road, there is no new construction of road and drainage infrastructure required, and there are existing utilities in place, they do not have to be relocated at the time of the plat. This does not preclude the County or other public agency from requesting the utility to be relocated at a future date where a right exists, nor exclude future action by the County or public agencies related to the relocation or construction of the utilities. No landscaping, irrigation, sidewalks, illumination, water quality features, or other improvements not related to roads and drainage shall be located within the public rights-of-way unless the Commissioners Court has granted a specific variance.
- 3) perpendicular utility crossings.

B4.14. A traffic impact analysis is required if any of the criteria below is met:

- a. Volume per day is 6,000 or greater
- b. All developments located within 500 feet of the intersection of two or more arterial and/or collector streets with an overall footprint in excess of 5 acres
- c. New school construction
- d. Shopping centers with gross square footage in excess of 100,000 square feet
- e. TxDOT requires analysis
- f. There are more than 150 peak hour trips

B5 - Construction – General

- B5.1. A preconstruction meeting must be scheduled and held prior to the start of construction, and a construction schedule shall be included in the request for a preconstruction meeting. The applicant's Engineer, Applicant, Contractor, Subcontractors, DPD, and County Engineer shall attend this meeting.
- B5.2. All roads are to be constructed in accordance with the construction documents associated with the approved plans and in accordance with the specifications found in the Walker County Subdivision Regulations and the 2024 version of the "Texas Department of Transportation Standard Specifications for Construction of Highways, Streets, and Bridges."
- B5.3. It is the responsibility of the applicant's certifying licensed engineer to ensure that work is performed in accordance with the approved plans. Monitoring by the certifying engineer shall be performed throughout the construction project for all operations.
- B5.4. All materials (including but not limited to right-of-way compaction, subgrade, and concrete) must be sampled and tested by an A2LA Certified Independent Testing Laboratory to show compliance with Subdivision Regulation specifications and in accordance with the construction documents approved by Commissioners Court. The Owner shall pay for all testing services and shall furnish the County Engineer with certified copies of all test results related to paving and drainage, including failures. The County Engineer must offer a "no objection" to the test results prior to constructing the next course of the roadway structure. Any material that does not meet the minimum required test specifications shall be removed, re-compacted or replaced, and retested unless alternative remedial action is approved in writing by the Commissioners Court.
- B5.5. All utilities installed in the public right-of-way shall comply with State and Federal regulations.
- B5.6. Construction oversight shall comply with the current, approved Construction Examination Guidelines.

B6 - Subgrade

- B6.1. The preparation of the subgrade shall follow standard engineering practices as directed by the County Engineer in conjunction with recommendations outlined in the geotechnical report. When the Plasticity Index (PI) is greater than 15, a sufficient amount of lime shall be added as described in Item 260 of the 2024 edition of the TxDOT Standard Specifications for Construction until the PI is less than 15. Carbide lime treatment is not permitted. If the addition of lime as described in Item 260 is not feasible, an alternate stabilizing design shall be proposed and submitted to the County Engineer for consideration. The subgrade shall be prepared and compacted to achieve a dry density per TxDOT Items 132 and 260.
- B6.2. Proof-rolling is required to be performed prior to chemical treatment per TxDOT Item 216.
- B6.3. The subgrade shall be inspected and approved by the developer's engineer and an A2LA Certified Independent Testing Laboratory, and a certified copy of all inspection reports shall be furnished to the County Engineer. All density test reports shall include a copy of the worksheet showing the percentage of the maximum dry (Proctor) density.
- B6.4. The testing laboratory's representative shall determine the Moisture-Density Relationship in accordance with ASTM D698, on material secured from the roadway or borrow source, for each type of material encountered or used.
- B6.5. The applicant's certifying engineer shall provide the County Engineer the recommended number and location of all subgrade tests and obtain a "no objection" from the County Engineer

B7 - Intentionally Left Blank

B8 - Intentionally Left Blank

B9 - Concrete Pavement

- B9.1. Portland cement concrete pavement is required for curb and gutter roadways and may be used on streets with roadside ditches. Concrete pavement shall be in conformance with 2024 TxDOT Specification Item 360 and all other applicable Items. The mix shall be from a TxDOT certified plant. The mix design shall be submitted to the County Engineer for approval prior to placement of the material.
- B9.2. The following are the allowed minimum requirements, minimum thickness and reinforcement requirements for concrete pavement. Refer to Appendix H for concrete pavement details. Pavement thickness and reinforcement shall be designed by the Professional Engineer responsible for the project and be based on a current soils analysis and recommendations by a qualified geotechnical engineer. Pavement design, based on soils analysis, use, loading, and life span, may require greater thickness and more reinforcement than the minimum required.
- a. For pavement widths less than, or equal to, 32 feet B/B of curb, minimum concrete slab thickness shall be 6 inches for $f_c' = 4,000$ psi and minimum reinforcement shall be Grade 60, $f_y = 60,000$ psi, #4 deformed reinforcing bars spaced at maximum 36 inches center to center transversely and maximum 18 inches center to center longitudinally, and minimum lap length of 22 inches. Expansion joints shall be placed at the end of each curb return, and at a maximum spacing of 60 feet. The minimum stabilized subgrade thickness shall be 6 inches.
 - b. For pavement widths greater than 32 feet B/B of curb, the minimum concrete slab thickness shall be 8 inches for $f_c' = 4,000$ psi, and minimum reinforcement shall be grade 60, $f_y = 60,000$ psi, #5 deformed reinforcing bars, maximum 36 inches center to center transversely and maximum 24 inches center to center longitudinally, and minimum lap length of 27 inches. Expansion joints shall be placed at the end of each curb return at a maximum spacing of 60 feet. The minimum stabilized subgrade thickness shall be 8 inches.
- B9.3. Concrete headers shall be placed at the end of all concrete pavements.
- B9.4. All concrete pavement to be removed/repared shall be removed to either the existing joint or a sawed joint.

B10 - Concrete – General

- B10.1. Unless otherwise specified, concrete shall be in accordance with Item 421 of the current edition of the TxDOT Standard Specifications for Construction and be placed in accordance with the applicable item.
- B10.2. All concrete shall be tested for compressive strength. One set of three concrete test cylinders shall be molded for every 50 cubic yards of concrete placed for each class of concrete per day, or at any other interval as determined by the County Engineer. A slump test shall be required with each set of test cylinders. One cylinder shall be tested for compressive strength at an age of seven days, and the remaining two cylinders shall be tested at 28 days of age.

B11 - Road Names, Signs, and Markers

- B11.1. All roads shall be named, with prior approval for said name from the Walker County 911 Addressing Coordinator. Roads must be named in a manner to avoid confusion in identification. Roads that are extensions of existing roads must carry the names of those in existence. The Owner shall provide the Coordinator with two digital files of the plat. One file shall be in an Adobe .pdf format, and the other file shall be in an AutoCAD .dwg format georeferenced to NAD 1983 State Plane Grid Coordinate System, Texas Central Zone (4203), with the drawing in US feet. The road names shall be displayed on standard intersection road marker signs erected by the Owner in compliance with the TxMUTCD "Street Name Signs" and at the locations, as indicated on the construction plans.
- B11.2. Traffic control signs (such as stop, yield, and speed limit signs) shall be installed by the Owner of said subdivision in compliance with the TxMUTCD and at the locations as indicated on the approved construction plans. Other traffic control signs, as shown on the construction plans, shall be installed to indicate any unusual traffic or road hazard or conditions that may exist. All traffic control devices shall be placed in compliance with the TxMUTCD and the construction cost shall be borne by the Owner.
- B11.3. A speed limit of 30 mph for local roads, 35 mph for collector roads, and 45 mph for arterial roads within all platted subdivisions are hereby adopted. This limit may be changed only by Commissioners Court upon the basis of an engineering and traffic investigation showing that the prima facie maximum reasonable and prudent speed for a particular road (or part of a road) should be different. The placement of a stop sign or a yield sign on the minor road at intersections shall be evaluated on a case-by-case basis in accordance with the TxMUTCD.
- B11.4. For any road that is proposed to be extended in the future, a minimum of five metal channel posts, equally spaced, shall be placed at the end of the road. Each post shall have an 18"x18" red diamond object marker sign (type OM-4 per TxMUTCD) placed four feet above the existing ground.
- B11.5. A future road extension sign shall be placed at the end of all roads and temporary cul-de-sacs that are proposed to be extended in the future. The sign shall state the following: Future Extension of <name of road>.
- B11.6. Signage that differs from the standard signage that is maintained by the County shall be maintained by the Owner. The signage shall be maintained in such a fashion to comply with the TxMUTCD requirements.
- B11.7. Public road name signs shall be green with white lettering. Private road name signs shall be brown with white lettering.

B12 - Drainage

- B12.1 Drainage infrastructure design and supporting calculations shall be completed by a Registered Professional Engineer, shall be in accordance with the most conservative methods described in the City of Huntsville Engineering Design Criteria Manual and TxDOT's Hydraulic Design Manual unless otherwise specified in this section, and shall conform to standard engineering practices and procedures. Roads shall not be used as drainage courses, except for extreme event sheet flow or where drainage is conveyed directly to inlets, without crossing streets or intersections. All data and supporting calculations must be presented to the County Engineer as part of the construction plans.
- B12.2 If the County accepts maintenance responsibility, the County's maintenance responsibility will be limited to only public drainage improvements that are located within the road right-of-way or parallel and adjacent to the right-of-way. Maintenance responsibility for all other stormwater management controls will remain with the Owner(s) or a designated Property Owner's Association. Drainage improvements associated with private drainage features, such as detention basin outfalls, are considered private and will also be the responsibility of the Owner(s) or a designated Property Owner's Association.
- B12.3 Easements shall be provided for all drainage courses in and across the property to be platted. The location and width shall be shown on the plat and marked Private Drainage Easement ("P.D.E.") or "Private Drainage and Utilities Easement". In general, a P.D.E. shall be designed to convey the 100-year flow and be a minimum of 20 feet in width when the easement is not parallel to a public right of way. Lot-to-lot drainage within Urban Subdivisions shall be located within a designed P.D.E., and it may be exempt from the minimum 20-foot width requirement. All drainage easements, private and public, shall be located in such a manner as to be locatable on the ground. Owner is responsible for the maintenance of private easements. See B12.12c for storm sewer easement requirements.
- B12.4 Provide a minimum 30-foot-by 30-foot drainage easement adjacent to the right-of-way, upstream and downstream of each culvert where it crosses a street.
- B12.5 Drainage infrastructure design shall be supported with a legible drainage area map that includes labeled contours, flow arrows, delineated onsite and offsite drainage areas, drainage area acreage, computed peak flow rates, and all existing and proposed drainage infrastructure clearly labeled.
- B12.6 Provide a culvert schedule noting the size, minimum slope, and quantity of all driveway culverts on a sheet with an overall layout of the development.
- B12.7 Both a plan and profile views shall be shown in the construction plans for all proposed drainage infrastructure. Each plan and profile shall show the design flow, velocity, invert elevations, and the hydraulic grade line for the design storm.
- B12.8 Detention Facilities
- a. Detention ponds shall be designed and constructed to mitigate the increased rate of runoff discharged from the platted area in order to meet or reduce the rate of discharge of the watershed, at the release point of the development, to its pre-developed state. Detention ponds shall be maintained by the Owner(s) or a designated Property Owner's Association. Mitigation without detention based on an engineering timing analysis cannot be used to meet this requirement. A variance may be allowed when the Owner can demonstrate that downstream properties will not be adversely affected.
 - b. The detention design for all onsite and offsite detention ponds shall be submitted with each engineering plan submittal and shall not be located within a right-of-way or utility easement.

- c. Offsite detention ponds shall be located in a dedicated easement, and the associated private drainage easement shall be shown on the recorded plat. Variances are required for offsite detention basins, when located on the parent tract, outside of the platted boundary.
- d. When a development is planned to be separated into several sections, a master drainage and detention plan will need to be provided that indicates that the pond is designed considering ultimate developed conditions.
- e. The detention pond and detention outlet structures are to be designed to mitigate increased runoff peak flow rates for the 5-year, 25-year, and 100-year storm events.
- f. For watersheds less than 50 acres, a detention storage estimating method such as the simplified method, or the NRCS unit hydrograph method along with the Modified Puls level pool routing method, may be used for detention design. Otherwise, the pond shall be designed per Section B12.8g.
- g. For watersheds greater than or equal to 50 acres, the NRCS unit hydrograph method along with the Modified Puls level pool routing method shall be used for detention design.
- h. For both curbed and uncurbed streets, runoff from the 100-year storm event shall be conveyed in a controlled manner in a dedicated right of way or dedicated easements, either overland or underground, to the detention facility or otherwise mitigated, as necessary.
- i. Detention ponds shall have a maximum side slope of 4 to 1, a minimum 10-foot maintenance access berm, a minimum of 1-foot of freeboard above the designed 100-year water surface elevation, and a minimum 0.75% bottom slope. Concrete pilot channels shall have a minimum depth of 2 inches and a minimum slope of 0.2%. Grass-lined pilot channels shall have a minimum depth of 1 foot and a minimum slope of 0.5%. The bottom slopes of the detention basin should be graded toward the pilot channel.
- j. Inlet pipes or channels shall be set a minimum of 6 inches above the bottom of the pond and shall include adequate erosion protection.
- k. Pond outlet orifices shall not be less than 6 inches in diameter, and the minimum outlet pipe shall be 18 inches.
- l. Outlet pipes shall be set a minimum of 6 inches above the flow line of the receiving watercourse and shall include adequate erosion protection. The outlet pipe shall enter the receiving watercourse at a 60-degree angle, plus or minus 10 degrees.
- m. Outlet exit velocities exceeding 5 feet per second shall have riprap erosion protection and exit velocities exceeding 10 feet per second shall have concrete energy-dissipating devices.
- n. Detention ponds shall have an emergency overflow weir at the pond outlet to mitigate the 100-year storm and provide a discharge location for greater storm events. This weir shall be designed to convey the 100-year storm event, assuming the main outlet is clogged. The emergency weir shall be constructed with concrete slope paving that has a 5-inch minimum thickness and includes sufficient reinforcement, and the weir shall not have a negative impact on the roadway.

B12.9 Roadway Bridges and Culverts

- a. Drainage crossings under all roads shall be designed to convey runoff from the 100-year storm event with the maximum water surface level not exceeding the lowest edge of pavement elevation of the road and without causing an increase in the pre-developed water surface for areas located outside of the platted area.

- b. The rational method shall be used to calculate peak flow rates for watersheds less than 200 acres. The NRCS unit hydrograph method or regression curves shall be used for watersheds greater than or equal to 200 acres.
- c. For culverts, hydraulic calculations shall consider entrance, exit, and friction losses as well as downstream hydraulic conditions (i.e., tailwater).
- d. For culverts, exit velocities exceeding 3 feet per second shall have erosion protection (i.e., riprap, concrete block mats, etc.). Exit velocities exceeding 5 feet per second shall have a concrete lining, and exit velocities exceeding 10 feet per second shall have concrete energy-dissipating devices.
- e. All riprap shall be clean and free of trash, metal, and debris. In addition, riprap shall not impede flow or create ponding.
- f. For span bridges, the bottom chord shall be set to 1.5 feet above the 1% annual chance base flood elevation and shall completely span the FEMA-designated floodway (Note: a floodplain permit will be required for any development within a FEMA special flood hazard area).
- g. Bridges, culverts, and all other drainage structures shall be designed and constructed per 2024 TxDOT Specification Section Items 400 - 499.
- h. Provide safety end treatments and headwalls in accordance with TxDOT Bridge Standards details. Slopes tying to natural ground (i.e., wing walls, safety end treatments, etc.) shall not exceed a 6 horizontal to 1 vertical.
- i. Design culvert crossings in accordance with the TxDOT Roadway Design Manual. If the ditch is greater than 4 feet deep, headwalls must be a minimum of 10 feet from the edge of the pavement or 6 feet from the back of the curb, unless a guardrail is provided. Guardrails are only permitted by variance.
- j. Bridges over 20 feet in span require a National Bridge Inventory ("NBI") number assigned by TxDOT. The applicant shall request the NBI from Walker County Planning and Development and shall provide all required TxDOT documentation and design, including scour analysis. The applicant shall request a TxDOT inspection through Walker County prior to the bridge being opened to traffic. Failure to meet this requirement could impact annual inspections and acceptance.

B12.10 Roadside Ditches

- a. Roadside ditches shall convey runoff from the 10-year storm event with 6 inches of freeboard. During a 100-year storm event, the water elevation shall not exceed the elevation at the adjacent right-of-way line or the elevation at the right-of-way adjacent drainage easement. The Engineer shall demonstrate proper cascading of flow through the streets or adequate conveyance capacity to ensure that runoff from the 100-year event is contained within the street right of way and drainage easement(s) as it is conveyed to the outlet point. Supporting calculations shall be provided demonstrating property conveyance of runoff from the 1% annual chance storm.
- b. The rational method shall be used to determine peak flows for all roadside ditch designs.
- c. Roadside ditches shall have a minimum depth of 18 inches, and roadside ditches are not required at grade breaks and high points. When a ditch is required, the minimum depth is to be measured from the edge of the road or the elevation at the right-of-way/edge of the drainage easement, whichever is lower. Exception: A roadside ditch may be a minimum of 12 inches deep for distances not to exceed 100 feet where there is no driveway access permitted on the roadway. There is no

minimum ditch depth requirement where the proposed infrastructure ties to existing infrastructure, but the transition to 18 inches deep shall occur as soon as feasible, as related to existing grades.

- d. Velocities in grass-lined roadside ditches shall not exceed 5 feet per second for the design storm. Ditch velocities between 3 and 5 feet per second required block sod or rigid lining (i.e., rip rap, geosynthetic or concrete matting, flexible growth medium, etc.). Concrete slope paving with minimum 18" deep toe walls, having a 5-inch minimum thickness with sufficiently designed reinforcement, shall be installed where velocities exceed 5 feet per second for the design storm.
- e. Grass-lined roadside ditch front slopes shall have a maximum grade of 6 horizontal to 1 vertical and the back slopes shall have a maximum grade of 4 horizontal to 1 vertical.
- f. Ditch longitudinal slopes shall not be less than 0.5%.
- g. Refer to Appendix F for a typical roadside ditch cross-section.
- h. No utilities shall be placed within the roadside ditches that obstruct the designed/constructed drainage flows.
- i. Manning Coefficient: The "n" coefficient for the ditch calculations shall be a minimum of 0.040. Natural channels shall have a minimum "n" coefficient of 0.060. All coefficient values must be justified.
- j. Provide safety end treatments and headwalls in accordance with TxDOT Bridge Standard details and 2024 TxDOT Standard Specification Item 467. The plans shall include the applicable details.

B12.11 Driveway Culverts

- a. Driveway culverts shall comply with the Regulations for Walker County Driveway Permits, Design, and Materials.
- b. Driveway culverts shall convey runoff from the 10-year storm event, assuming full-flow hydraulic conditions.
- c. The rational method shall be used to determine peak flows for driveway culvert design.
- d. A driveway culvert schedule shall be provided in the construction drawings and plat. The table shall include section number, block number, lot number, and culvert size.
- e. Exit velocities exceeding 5 feet per second shall have erosion protection (i.e., riprap, concrete block mat, concrete lining, etc.) and exit velocities exceeding 10 feet per second shall have concrete energy dissipating devices.
- f. Sheet flow from driveways shall be shed to the roadside ditch prior to the sheet flow reaching the driveway culvert crossing.
- g. Provide safety end treatments and headwalls in accordance with TxDOT Bridge Standards details and 2024 TxDOT Standard Specification Item 467. The plans shall include the applicable details.

B12.12 Storm Sewer

- a. All closed conduit storm sewers shall have a minimum Manning's Coefficient of 0.013 and shall be one of the following:
 - i. Reinforced concrete pipe (RCP) in accordance with 2024 TxDOT Specification Item 464,
 - ii. Reinforced concrete box culvert (RCBC) in accordance with 2024 TxDOT Specification Item 462 (minimum Manning's Coefficient of 0.015),
 - iii. Dual wall, corrugated, smooth interior, water-tight high-density polyethylene ("HDPE") in accordance with ASTM F2306, AASHTO M294, 2024 TxDOT Specification Item 468, and TxDOT Specification DMS-4710 (pipes over 48 inches are not permitted, a 30-day mandrel test is required), HDPE IS NOT PERMITTED UNDER A PUBLIC OR PRIVATE STREET, or
 - iv. Dual wall, corrugated, smooth interior, water-tight polypropylene ("PP") pipe in accordance with ASTM F2881, AASHTO M330, 2024 TxDOT Specification Item 468, and TxDOT Specification DMS-4710 (pipes over 48 inches are not permitted, 30-day mandrel test is required).
- b. Refer to Appendix I for pipe bedding and backfill details. The details in the appendix provide the minimum County requirements, and the construction plans shall include a site-specific design prepared by a professional engineer that is equal to or greater than the minimum requirements. The final details and design shall be signed and sealed by a professional engineer.
- c. When storm sewers are permitted outside of the public right of way, the minimum easement width shall be the following:

Pipe Depth D:			4'	5'	6'	7'	8'	9'	10'	11'	12'	13'	14'
Pipe Dia.	d ₀	X Value	15' Esm't	20' Esm't		25' Esm't (Trench Box Required)							
8"	1	0.5	12.0	16.0	20.0	24.0	28.0	32.0	36.0	40.0	44.0	48.0	52.0
12"	1.3		11.1	15.1	19.1	23.1	27.1	31.1	35.1	39.1	43.1	47.1	51.1
15"	1.7		9.9	13.9	17.9	21.9	25.9	29.9	33.9	37.9	41.9	45.9	49.9
18"	2		9.0	13.0	17.0	21.0	25.0	29.0	33.0	37.0	41.0	45.0	49.0
24"	2.5	0.75	8.0	12.0	16.0	20.0	24.0	28.0	32.0	36.0	40.0	44.0	48.0
30"	3			10.5	14.5	18.5	22.5	26.5	30.5	34.5	38.5	42.5	46.5
36"	3.5			9.0	13.0	17.0	21.0	25.0	29.0	33.0	37.0	41.0	45.0
42"	4	1			12.0	16.0	20.0	24.0	28.0	32.0	36.0	40.0	44.0
48"	4.5				10.5	14.5	18.5	22.5	26.5	30.5	34.5	38.5	42.5
54"	5.1	1.25			9.2	13.2	17.2	21.2	25.2	29.2	33.2	37.2	41.2
60"	5.6						15.7	19.8	23.7	27.7	31.7	35.7	39.7
66"	6.2	1.5	Depth is not Applicable					18.4	22.4	26.4	30.4	34.4	38.4
72"	6.7							16.9	20.9	24.9	28.9	32.9	36.9

Trench Width Formula for Predominately Type C Soils: $W = d_0 + 2X + 4 [D - (d_0 + 0.5)]$

- d. The design storm for storm sewer design shall be in accordance with Table B4.1. Adequately sized storm sewers are required on curb and gutter streets, and concentrated flow shall not discharge over the back of curb. The design storm HGL shall not exceed 12 inches below the gutter flow line.
- e. For the 100-year storm event, the starting HGL shall be equal to the top of pipe or the 25-year storm event water surface elevation of the receiving watercourse, whichever is greater.
- f. Storm sewer conduits shall have a minimum velocity of 3 feet per second and a maximum velocity of 10 feet per second when flowing full.
- g. Storm manholes shall have a maximum spacing of 600 feet measured along the conduit run. Manholes for storm sewer conduits shall be placed at size changes, cross-section changes, grade changes, inlet lead and conduit intersections, and direction changes.
- h. At the change in pipe size, match the soffits of the two pipes.
- i. A straight line should be used for the design of precast inlet leads and storm sewers 30 inches in diameter or less. Precast storm sewers 36 inches in diameter and larger may be deflected at joints not to exceed the manufacturer's recommendation.
- j. Soil borings with logs shall be made along the alignment of all storm sewers having a cross-section equal to or greater than 42 inches in diameter or equivalent cross-section area. Borings should be taken at intervals not exceeding 500 linear feet and to a depth not less than 3 feet below the flow line of the sewer.
- k. Any storm sewer 42 inches or smaller located underneath or within 1 foot of a paving section shall be bedded and backfilled 2 sack cement stabilized sand.
- l. Curb inlets shall be designed to prevent water from ponding in the street during the 5-year storm event.
- m. The gutter run to an inlet shall not exceed 700 feet.
- n. In profile view, provide both top-of-curb ground elevations at the left and right ROW. Curbs should be below both right-of-way profiles to facilitate drainage. The right-of-way must drain to the street for curbed roads at a minimum slope of $\frac{1}{4}$ inch per foot, and a maximum slope of 1 foot per 7 feet. Show and label proposed profiles where cut or fill is necessary.
- o. House finished floor elevations shall be set a minimum of 1 foot above natural ground or per the current floodplain regulations in relation to the base flood elevation, whichever is greater. This minimum requirement shall be noted on the plat.
- p. During a 100-year storm event, the water elevation shall not exceed the elevation at the adjacent right-of-way line or the elevation at the right-of-way adjacent drainage/utility easement. The Engineer shall demonstrate proper cascading of flow through the streets or adequate conveyance capacity in the storm sewer pipes and inlets to ensure that runoff from the 100-year event is contained within the street right of way as it is conveyed to the outlet point. Supporting calculations shall be provided demonstrating property conveyance of runoff from the 1% annual chance storm.
- q. Within 14 days of ceasing construction, seed all disturbed areas within a uniform (i.e., evenly distributed, without bare areas) perennial vegetative cover. The density shall be at least 70% and consist of suitable background vegetative cover for the area. Equivalent permanent stabilization measures are also acceptable. The method of stabilization to be utilized shall be specified in the plans.

B13 - Testing and Reporting

The following list is the minimum requirements that will be provided at the pre-construction conference and the material testing shall be to the satisfaction of the County. The Commissioners Court reserves the right to require any additional inspection, testing, or reporting, at the expense of the Owner, as deemed necessary to ensure compliance with these regulations and/or standard construction/engineering practices.

- B13.1 Prior to construction, the applicant shall request and attend a pre-construction meeting with the County. The developer, the applicant's engineer, and the contractor are also required to attend. The applicant's engineer shall periodically inspect the construction. It is the responsibility of the applicant's engineer to ensure and certify that the project is constructed in accordance with the plans and specifications.
- B13.2 The owner/developer or contractor needs to secure an A2LA Certified Independent Testing Laboratory for material testing.
- B13.3 The County will require soil test reports, lab recommendations of stabilization, proof roll reports, density test reports, and PH Test Reports (when applicable).
- B13.4 Prior to the pre-pave inspection, the County will require compaction/density tests.
- B13.5 Notify the County prior to placing drainage structures and bridges. County may inspect drainage structures prior to and during installation. This includes steel placement, dimensions, precast structures, etc.
- B13.6 Prior to paving, provide concrete pavement submittals for County Review, and the County must inspect the rebar at a scheduled inspection, requested by the certifying engineer. Obtain a "no objection" from the County prior to paving.
- B13.7 After paving, provide core/cylinder test results and tickets for County for review. Where cores are made, the developer is required to repair the hole with like material.
- B13.8 If visual concerns are noted at any time, additional testing may be required at the County's discretion.
- B13.9 After construction is deemed complete, the applicant's engineer shall submit a signed and sealed Engineer's Certification of Completion, a signed Developer's Certification of Completion, a completed Development Permit with the final Development Certifications Form (for approval), a complete package of lab reports, and request construction certification. In addition, the applicant's engineer shall submit certified record drawings, with all revisions clouded. The Engineer's Certification of Completion is included in Appendix E. If the construction included a bridge, additional items may be required. After receipt of a complete certification package, a certification walkthrough will be scheduled and a punch list shall be generated. Prior to certification of completion, all punch list items shall be completed, and an acceptable Maintenance Bond shall be provided.

C1 - Owner's Dedication

www

COUNTY OF WALKER

<Owner's signature>

<Typed Address>

**** There must be a separate signature block, each with a notary signature block, for each Owner on the deed.**

In approving this plat by the Commissioners Court of Walker County, Texas, it is understood that the building of all roads, and other public thoroughfares, and any bridges or culverts necessary to be constructed or placed is the responsibility of the Owner(s) of the tract of land covered by this plat in accordance with the plans and specifications prescribed by the Commissioners Court of Walker County, Texas. Said Commissioners Court assumes no obligation to build or maintain any of the roads, or other public thoroughfares shown on this plat, or of constructing or maintaining any of the bridges or drainage improvements in connection therewith. The County will assume no responsibility for drainage ways, stormwater management controls, or easements in the subdivision, other than those within the dedicated right of way or public easements at such time, if any, the roads are accepted for public maintenance. Until such time, if any, said infrastructure is adopted into public maintenance, <Assigned Party> shall be responsible for the ongoing maintenance of the roads, rights-of-way, signage, drainage, and other improvements within the subdivision.

C3 - Owner's Responsibilities

It is the responsibility of the Owner, not the County, to assure compliance with the provisions of all applicable state, federal, and local laws and regulations relating to the platting and development of this property.

The County assumes no responsibility for the accuracy of representations by other parties in this plat. Floodplain data, in particular, may change. It is further understood that the Owner(s) of the tract of land covered by this plat, its successors and/or assigns, or a designated property owner's association must install and maintain at their own expense all roads, stormwater management controls, traffic control devices, and signage that may be required until such time, if any, said infrastructure in the subdivision have been accepted for public maintenance.

C4 - Commissioners Court Approval

STATE OF TEXAS	§	
	§	KNOW ALL MEN BY THESE PRESENTS;
COUNTY OF WALKER	§	

The Commissioners Court of Walker County, Texas, does hereby certify that this map or plat, as described herein, for a subdivision having been fully presented to the Commissioners Court of Walker County, Texas, and by the said Court duly considered, was on this day approved and that this plat is authorized to be registered and recorded in the proper records of the County Clerk of Walker County, Texas. This certification is based upon the representations of the developer/developer's agent, engineer, sanitarian, and/or surveyor whose seal(s) and/or signatures are affixed hereto. This certification is made solely upon such representations and should not be relied upon for verifications of the facts alleged. Walker County disclaims any responsibility to any member of the public for independent verification of the representations, factual or otherwise, contained in this plat and the documents associated with it.

<Insert Current Commissioners Court Signature Block>

C5 - County Clerk Certification

Note for Major Plats or Plats Larger than 8.5"x14" Format

STATE OF TEXAS

§
§
§

KNOW ALL MEN BY THESE PRESENTS

COUNTY OF WALKER

I, *<insert name of current clerk>*, County Clerk of Walker County, do hereby certify that this plat with its certificate of authentication was filed for record in my office the ____ day of ____, 20____, in Volume _____, Page _____ of the Plat Records of Walker County, Texas.

For tax purposes, this plat complies with Section 12.002 of the Property Code.

County Clerk
Walker County, Texas

By: _____
Deputy Clerk

Note for Minor Plats Submitted in 8.5"x14" or 8.5"x 11" Format

STATE OF TEXAS

§
§
§

KNOW ALL MEN BY THESE PRESENTS

COUNTY OF WALKER

I, *<insert name of current clerk>*, County Clerk of Walker County, do hereby certify that this plat with its certificate of authentication was filed for record in my office the ____ day of ____, 20____, under instrument number _____ in the Official Public Records of Walker County, Texas.

For tax purposes, this plat complies with Section 12.002 of the Property Code.

County Clerk
Walker County, Texas

By: _____
Deputy Clerk

C6 - On-Site Sewage Facility Review

Based upon a review of the plat and plans as represented by the said engineer or surveyor, I, the below signed design/review professional, being qualified to make said determination under Texas law, find that this plat complies with the requirements of the Walker County On-Site Sewage Facility Regulations, and Title 30 of the Texas Administrative Code, Chapter 285, including but not limited to the suitability of the proposed lots to accommodate on-site sewage facilities within the proposed development considering all of the requirements of Title 30, 285 TAC and any applicable local orders. I also agree that Walker County, its agents, and assigns bear no responsibility to any member of the public for independent verification of the representations, factual or otherwise, contained in this plat and the documents associated with it.

<Print Name of P.E. or R.S.>

Date

C7 - Mailboxes

Cluster and individual mailboxes, if allowed, shall be set three feet from the edge of the pavement or behind curbs, when used. All mailboxes within County arterial right-of-way shall meet the current TxDOT standards. Any mailbox that interferes with or negatively affects the maintenance or use of the roads or drainage system may be removed by Walker County.

C8 - Floodplain Regulations Certification

(To be Provided on ETJ Plats and Major Plats)

Based upon a review of the plat and associated plans, I, the below signed Professional Engineer, find that this plat complies with the requirements of the current Walker County Floodplain Regulations. I further understand and agree that this finding is made by and through my independent review, and Walker County has no responsibility to any member of the public for independent verification of the representations, factual or otherwise, contained in this plat and the documents associated with it.

<Seal and Signature of P.E.>

<Print Name of P.E.>

Date

C9 - Development Notes

No structure or land within this plat shall hereafter be developed without first obtaining a Development Permit from the Walker County Floodplain Administrator unless the proposed development is exempt or excepted from the Walker County Floodplain Development Regulations.

The minimum, lowest finished floor elevation shall be in compliance with the local floodplain regulations and the finished floor elevation noted on the plat, whichever elevation is higher.

C10 - Plat Notes Addressing Area Drainage

Note for Minor Subdivision Plat

All owners of lots within the subdivision shall have the responsibility of complying with the Walker County Subdivision Regulations' policies on drainage runoff due to the development of impervious areas created through the development of the lot for residential, commercial, or recreational use. It is the responsibility of lot owners to comply with any regulations or limitations noted, and permits issued by Walker County for development do not act as a waiver or variance of the lot owner's responsibility to provide for excess runoff and drainage created by the permitted development. If detention of water is necessary in order to comply with the local, state, or federal regulations including but not limited to the Walker County Subdivision Regulations then the owner may be able to accomplish compliance with said policies through creating detention on a single lot, multiple lots, or the entire subdivision depending on the circumstances involved and depending on the owner's ability to obtain the cooperation of other owners in the subdivision. A copy of an agreement between owners to create detention shall be submitted to Walker County and filed in the public records becoming a restriction on future owners, heirs, and assigns.

Engineer's Note for Subdivision Plats (certified by engineer)

The design of this project will not negatively impact this property or adjacent properties. Based on calculations made from available data, if the impervious cover (structures, driveways, sidewalks, etc.) on each lot does not exceed _____ square feet, then the existing detention on the property will be sufficient. However, if the impervious cover of the property exceeds or surpasses _____ square feet then further study will be necessary and possible drainage/detention improvements may be required in accordance with current Local, State, and Federal regulations including the Walker County Subdivision Regulations. Local approval or allowance must be given by Walker County in writing prior to the alteration of the drainage infrastructure. It is the responsibility of lot owners to comply with any regulations or limitations noted, and permits issued by Walker County for development do not act as a waiver or variance of the lot owner's responsibility to provide for excess runoff and drainage created by the permitted development.

<Seal and Signature of P.E.> _____

<Print Name of P.E.> _____

_____ Date

The first section of this note can be altered to reflect the weighted development of larger lots considering the effect of increase in runoff on a per lot basis by allowing larger amounts of impervious cover on larger acreage lots or could reflect a unified sizing of impervious cover for all lots in the subdivision considering the effects of increased runoff from the subdivision as a whole.

Example: ... if impervious cover on Lots 1,2,&3 does not exceed 6,000 sq. ft. and impervious cover on lots 4 & 5 does not exceed 8,000 sq. ft. then...

Drainage Acceptance Note on all Plats (certified by owner/developer)

All lots within the subdivision and the owners thereof must continue to accept all existing drainage flows and drainage structures in place at the time of development that are a part of or necessary to the existing or designed roads infrastructure or the existing or designed system of drainage, in addition to all natural flows of water entering onto or crossing the property. All drainage easements shown hereon shall be kept clear of fences, buildings, plantings, and other obstructions to the operation and maintenance of the drainage facilities.

C11 - Plat Notes Addressing Utilities

Utilities shall be installed within a dedicated utility easement. Utilities are not permitted within drainage easements, unless specifically excepted by the subdivision regulations.

C12 - Water Supply Note:

Individual Water Well Note:

Each lot will be served by a private, on-site water well.

-OR-

Water Supply Note:

<Insert Name of Water Supplier>, an approved public water supply system, has an adequate quantity to supply the subdivision, and provisions have been made to provide service to each lot within this subdivision.

C13 - Certification of Surveyor

I, _____, the below signed Texas Registered Professional Land Surveyor, certify that this plat represents a survey made on the ground under my supervision and that all corners and monuments are shown hereon. This plat was prepared with the benefit of a current title report, and all existing easements and encumbrances related to said report are shown. Further, I certify this plat has been prepared in accordance with the Subdivision Regulations of Walker County.

<Seal and Signature of RPLS>

<Print Name of RPLS >

Date

Appendix D - Plat Application Checklists

WALKER COUNTY SUBDIVISION APPLICATION CHECKLISTS	
The applicant is responsible for the submittal of all documents on the checklist with each separate application submittal. The submittal of a document or file under a previous application does not supplant the requirement for submittal with a future application. Application submittals shall be submitted in whole on the date of application; applications will not be allowed to be submitted at separate times or on separate dates. All submittals shall be submitted with 3 properly sized paper copies and a digital .pdf file unless otherwise required below or by the Walker County Subdivision Regulations. Any digital media delivered with or containing part of an application, including but not limited to flash drives, DVDs, hard drives, etc., are considered to be part of the application and will not normally be returned to applicant.	
SUBMITTAL REQUIREMENTS BY APPLICATION TYPE	
Variance Request Application Submittal Checklist	
1	Completed Variance Request Application Form
2	Copy of the Deed for the Parent Tract and an acceptable Title Commitment or Title Policy/Report
3	Authorized Signatory Documentation
4	7 paper copies and 1 digital copy (.pdf) of all plans, drawings, exhibits, engineering studies, or other back-up submitted in support of the variance request.
Plat Application Submittal Checklist	
1*	Approved 911 Addressing Road and Feature Name Review. (If applicable)
2*	Completed Application Form
3*	Required Fee(s)
4*	Authorized Signatory Documentation
5*	Copy of the Deed for the Parent Tract and an acceptable Title Commitment or Title Policy/Report
6*	Copies of any approved variance requests that relate to the application (if applicable)
7*	Copy of an approved <i>OSSF Subdivision Planning Materials Submittal for Subdivision</i> (If applicable)
8*	Approved Development Permit under the Regulations for Floodplain Management for all proposed infrastructure. (If applicable)
9	Copies of required Plans, Reports, Calculations, and Studies sealed by a Professional Engineer. (3 properly sized paper copies and 2 digital files (.pdf, .dwg) (if applicable)
10*	Copies of the proposed Final Plat including all seals and signatures. (3 paper copies, 2 mylar copies, and three digital files (.pdf, .dwg, and shapefile formats)
11	Sealed Engineer's itemized list of improvements with quantities (excluding costs) necessary to complete the road and drainage improvements and is sufficient for Commissioners Court to set the surety amount
12	Improvement Maintenance Plan (if applicable)
13	An original copy of the completed financial surety documents/or documentation of acceptance of completed construction and post-construction bonding.
14	Letters of Serviceability from the Wastewater, Water, and Electric provider
15	Groundwater Certification (if applicable)
16*	Tax Certificate Showing Taxes Paid to Date
17*	Necessary Approvals from Other Governmental Entities (If applicable)(TXDOT, TCEQ, etc.)
<i>*Plat Applications and Amending or Re-plat Applications classified as Minor Subdivisions with no improvements related to development required need only submit the items marked with an asterisk.</i> <i>(If applicable) - Some application submittals may not be applicable to all subdivision applications, especially in cases where no infrastructure is required or proposed. Check regulations for applicability.</i>	
Amending or Re-plat Applications additional items	
1	A copy of the current deed restrictions for the subdivision, if any.

Exception Application Submittal Checklist		
1		Completed Variance Request Application Form
2		Required Fee(s) per the current schedule of fees
3		Copy of the Current Deed for the Parent
4		Copy of an approved On-Site Sewage Facility Subdivision/Development Plan
5		Written copies of any applicable Federal, State, and Local approvals required. (TXDOT, TCEQ, etc)
6		Copy of plat and metes and bounds description for proposed
7		Acceptable Authorized Signatory Documentation for any plat for any agent not listed on the deed, or for any agent of a corporation or other entity having ownership of the land.
8		Copy of the tax certificate showing taxes paid to date. (County Clerk's Requirement for filing)

Appendix E - Construction Documents

[ENGINEERING FIRM'S LETTERHEAD WITH FIRM NUMBER]

ENGINEER'S CERTIFICATION OF COMPLETION

[SUBDIVISION NAME AND SECTION NUMBER, IF APPLICABLE]

In accordance with the Walker County Subdivision Regulations, I _____, P.E., a registered Engineer duly licensed to practice in the State of Texas, on behalf of _____, the Applicant, do hereby certify that the subject subdivision has been constructed as designed, according to the approved plans and specifications, in accordance with standard engineering practice for public infrastructure, and to the standards of the Walker County Subdivision Regulations. I am providing this certification based on a visual inspection of the construction and the review of applicable and sufficient laboratory testing. I further certify that the required improvements are complete and functioning.

I have provided the following required items and respectfully request Initial Certification of the subject subdivision.

1. Digital copy of the engineer's certified record drawings
2. Hard copy of the engineer's certified record drawings
3. Applicant's Certification of Completion
4. Test Reports
5. Maintenance Bond
6. Completed County "Development Certifications Form"
7. (add any additional items)

[Engineer's seal with signature and date]

APPLICANT'S CERTIFICATION OF COMPLETION

[SUBDIVISION NAME AND SECTION NUMBER, IF APPLICABLE]

In accordance with the Walker County Subdivision Regulations, I, _____,
of _____, the Applicant, do hereby certify that the subject subdivision
has been constructed as designed, according to the approved plans and specifications to the
standards of the Walker County Subdivision Regulations. Further, I certify that any federal, state, or
local permits required for the construction were obtained.


[Applicant's signature and date]

Appendix F - Roadway Cross-Sections & Details

These details provide the minimum County requirements, and the construction plans shall include a site-specific design prepared by a professional engineer that is equal to or greater than the minimum requirements, including the minimum design life and traffic loading during and after construction. The final details and design shall be signed and sealed by a professional engineer.

NOTES:


1. THIS DETAIL PROVIDES THE MINIMUM REQUIREMENTS, AND GEOTECHNICAL INVESTIGATION IS REQUIRED TO DETERMINE IF THE MINIMUM STANDARDS ARE SUFFICIENT.
2. PROVIDE SAFETY END TREATMENTS AND HEADWALLS PER TXDOT BRIDGE STANDARDS DETAILS AND 2024 TXDOT STANDARD SPECIFICATION ITEM 467.
3. EXCEPT WHERE TYING TO EXISTING INFRASTRUCTURE, ROAD CROSS SLOPES SHALL NOT EXCEED 3% OR BE LESS THAN 1%.



DITCH EROSION CONTROL:

- DITCH VELOCITY OF <3 FPS REQUIRE SEEDING / HYDRO MULCH
 DITCH VELOCITY OF 3-5 FPS REQUIRE VEGETATION BLOCK SOD OR RIGID LINING
 DITCH VELOCITY OF >5 FPS REQUIRE RIGID LINING (PAVERS, STONE RIPRAP, CONC. OR EQUAL)

RURAL
 VOLUME PER DAY 12,000+



URBAN
 VOLUME PER DAY 12,000+



**ARTERIAL
 ROAD SECTIONS**



WALKER COUNTY, TX

SCALE: NTS 06/16/2025

THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.

NOTES:


1. THIS DETAIL PROVIDES THE MINIMUM REQUIREMENTS, AND GEOTECHNICAL INVESTIGATION IS REQUIRED TO DETERMINE IF THE MINIMUM STANDARDS ARE SUFFICIENT.
2. PROVIDE SAFETY END TREATMENTS AND HEADWALLS PER TXDOT BRIDGE STANDARDS DETAILS AND 2024 TXDOT STANDARD SPECIFICATION ITEM 467.
3. EXCEPT WHERE TYING TO EXISTING INFRASTRUCTURE, ROAD CROSS SLOPES SHALL NOT EXCEED 3% OR BE LESS THAN 1%.



THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.

NOTES:


1. THIS DETAIL PROVIDES THE MINIMUM REQUIREMENTS, AND GEOTECHNICAL INVESTIGATION IS REQUIRED TO DETERMINE IF THE MINIMUM STANDARDS ARE SUFFICIENT.
2. PROVIDE SAFETY END TREATMENTS AND HEADWALLS PER TXDOT BRIDGE STANDARDS DETAILS AND 2024 TXDOT STANDARD SPECIFICATION ITEM 467.
3. EXCEPT WHERE TYING TO EXISTING INFRASTRUCTURE, ROAD CROSS SLOPES SHALL NOT EXCEED 3% OR BE LESS THAN 1%.
4. DITCH EROSION CONTROL:
 DITCH VELOCITY OF <3 FPS REQUIRE SEEDING / HYDRO MULCH
 DITCH VELOCITY OF 3-5 FPS REQUIRE VEGETATION BLOCK SOD OR RIGID LINING
 DITCH VELOCITY OF >5 FPS REQUIRE RIGID LINING (PAVERS, STONE RIPRAP, CONC. OR EQUAL)



NOTE: FOR 6,000-11,999 TRIPS PER DAY, ADD DIMENSIONS PER COMMISSIONERS COURT APPROVED ROAD SECTION. TO OBTAIN ROAD SECTION APPROVAL, DEVELOPER SHALL PROVIDE AN ENGINEERS ROAD SECTION RECOMMENDATION, LAND PLAN, TIA, & TYPICAL ROADWAY CROSS-SECTION BASED ON TRAFFIC VOLUMES.

MAJOR COLLECTOR
VOLUME PER DAY
 6,000-11,999

MINIMUM DESIGN SPEED
 SPEED LIMIT
 40



COLLECTOR
RURAL ROAD SECTIONS
 WALKER COUNTY, TX
 SCALE: NTS 06/16/2025


MINOR COLLECTOR
VOLUME PER DAY
 2,000-5,999

MINIMUM DESIGN SPEED
 SPEED LIMIT
 40

THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.

NOTES:

1. THIS DETAIL PROVIDES THE MINIMUM REQUIREMENTS, AND GEOTECHNICAL INVESTIGATION IS REQUIRED TO DETERMINE IF THE MINIMUM STANDARDS ARE SUFFICIENT.
2. PROVIDE SAFETY END TREATMENTS AND HEADWALLS PER TXDOT BRIDGE STANDARDS DETAILS AND 2024 TXDOT STANDARD SPECIFICATION ITEM 467.
3. EXCEPT WHERE TYING TO EXISTING INFRASTRUCTURE, ROAD CROSS SLOPES SHALL NOT EXCEED 3% OR BE LESS THAN 1%.




DITCH EROSION CONTROL

DITCH VELOCITY OF <3 FPS REQUIRE SEEDING / HYDRO MULCH
 DITCH VELOCITY OF 3-5 FPS REQUIRE VEGETATION BLOCK SOD OR RIGID LINING
 DITCH VELOCITY OF >5 FPS REQUIRE RIGID LINING (PAVERS, STONE RIPRAP, CONC. OR EQUAL)
 PROVIDE SAFETY END TREATMENTS AND HEADWALLS IN ACCORDANCE WITH TXDOT BRIDGE STANDARDS DETAILS AND 2024 TXDOT STANDARD SPECIFICATION ITEM 467.

RURAL
 VOLUME PER DAY
 LESS THAN 2,000

MINIMUM DESIGN SPEED
 SPEED LIMIT
 35



URBAN
 VOLUME PER DAY
 LESS THAN 2,000


MINIMUM DESIGN SPEED
 SPEED LIMIT
 35

**LOCAL
 ROAD SECTIONS**

WALKER COUNTY

SCALE: NTS 06/16/2025


THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.




THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.

Appendix G - Curb Details

These details provide the minimum County requirements, and the construction plans shall include a site-specific design prepared by a professional engineer that is equal to or greater than the minimum requirements. The final details and design shall be signed and sealed by a professional engineer.



**6" CURB
(ALL STREETS)**



**4"x12" ROLLOVER CURB
(RESIDENTIAL LOTS ONLY)**

NOTES:

1. CONCRETE SHALL BE CLASS A (4000 PSI).
2. ALL REINFORCING BARS SHALL BE #4 GRADE 60 STEEL (100% TIED), UNLESS OTHERWISE SPECIFIED.
3. ROUND ALL EXPOSED SHARP EDGES WITH A ROUNDING TOOL TO A MINIMUM RADIUS OF 1/4 INCH.
4. PROVIDE EPOXIED DOWELS WHERE CONCRETE CURBS ARE PLACED ON EXISTING CONCRETE PAVEMENT.
5. EXPANSION AND CONTRACTION JOINTS SHALL BE CONSTRUCTED TO MATCH, INCLUDING PAVEMENT JOINTS IN THE CURB AND GUTTER LINES ADJACENT TO JOINTED CONCRETE PAVEMENT. WHERE PLACEMENT OF CURB OR CURB AND GUTTER IS NOT ADJACENT TO CONCRETE PAVEMENT, EXPANSION JOINTS SHALL BE PROVIDED AT STRUCTURES, CURB RETURNS, AND AT THE LOCATIONS DIRECTED BY THE ENGINEER.
6. ONE-HALF INCH EXPANSION JOINT MATERIAL SHALL BE PROVIDED WHERE CURB OR CURB AND GUTTER IS ADJACENT TO SIDEWALK OR RIPRAP.
7. ALL JOINTS SHALL BE EPOXY SEALED, (GRAY COLOR TO MATCH).
8. ALL CURB SHALL BE SPRAYED WITH WHITE PIGMENTED CURING COMPOUND.
9. PLACE BACKFILL BEHIND THE CURB WITHIN 7-DAYS OF NEW CURB INSTALLATION.

**CONCRETE CURB
DETAILS**


WALKER COUNTY

SCALE: NTS 06/16/2025

THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.

Appendix H - Concrete Pavement Details


These details provide the minimum County requirements, and the construction plans shall include a site-specific design prepared by a professional engineer that is equal to or greater than the minimum requirements. The final details and design shall be signed and sealed by a professional engineer.



THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.

Appendix I - Storm Bedding and Backfill Details

These details provide the minimum County requirements, and the construction plans shall include a site-specific design prepared by a professional engineer that is equal to or greater than the minimum requirements. The final details and design shall be signed and sealed by a professional engineer.



NOTES:

1. THIS DETAIL MAY BE USED ONLY FOR DRY STABLE TRENCH CONDITIONS.
2. MINIMUM TRENCH WIDTH SHALL BE PIPE OD PLUS AN ALLOWANCE "A" FOR THE NOMINAL PIPE SIZE:

NOMINAL PIPE SIZE	"A"
18" TO 30"	24"
OVER 30"	36"

3. MAXIMUM TRENCH WIDTH SHALL BE NOT GREATER THAN MINIMUM TRENCH WIDTH PLUS 24 INCHES, UNLESS OTHERWISE NOTED.
4. CEMENT STABILIZED SAND TO BE BACKFILLED UP TO BOTTOM OF SUBGRADE WHERE PIPES CROSS ANY ROAD.
5. ANY STORM SEWER 48 INCHES OR SMALLER LOCATED UNDERNEATH OR WITHIN 1 FOOT OF A PAVING SECTION SHALL BE BEDDED AND BACKFILLED WITH 2 SACK CEMENT STABILIZED SAND.

**RCP STORM BEDDING
AND BACKFILL DETAIL**

WALKER COUNTY

SCALE: NTS 06/16/2025

THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.




TABLE 1
RECOMMENDED MINIMUM TRENCH WIDTHS

PIPE DIAM.	MIN. TRENCH WIDTH
18" (450mm)	45" (1143mm)
24" (600mm)	52" (1321mm)
30" (750mm)	60" (1524mm)
36" (900mm)	78" (1981mm)
42" (1050mm)	83" (2108mm)
48" (1200mm)	90" (2286mm)

NOTES:

1. ALL PIPE SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS", LATEST ADDITION. NATIVE SOILS SHALL BE OF ADEQUATE STIFFNESS TO WITHSTAND A VERTICAL CUT WITHOUT MATERIAL SLOUGHING. DUE TO THE FINAL SET STRENGTH, CEMENT STABILIZED SAND (CSS) SHALL BE COMPACTED TO 95% SPD OR GREATER. SEE NOTES 7 AND 9 REGARDING SET STRENGTH.
2. RECOMMENDED TRENCH WIDTHS ARE LISTED IN TABLE 1 PER ASTM D2321. THESE VALUES ARE BASED ON PROVIDING SUFFICIENT SPACE BETWEEN THE PIPE O.D. AND THE TRENCH WALL, SUCH THAT WORKING ROOM FOR COMPACTION EQUIPMENT IS PROVIDED WITHOUT DAMAGING THE PIPE OR TRENCH WALL INTEGRITY. NARROWER TRENCHES MAY BE POSSIBLE BASED ON THE COMPACTION EQUIPMENT.
3. CSS SHALL HAVE A MIX DESIGN OF ADEQUATE FINAL STRENGTH TO CARRY ALL LIVE AND DEAD LOADING BUT ALLOW FOR ANY FUTURE EXCAVATION. TYPICAL 7 DAY COMPRESSIVE STRENGTHS RANGE BETWEEN 50 AND 100 PSI. MIX DESIGNS CAN VARY BASED ON THE CEMENT, ASH, SOIL, ADMIXTURES, AND WATER RATIO AND SHALL BE DESIGNED AND DEFINED BY THE ENGINEER OF RECORD. THE AMERICAN CONCRETE INSTITUTE (ACI) REPORT ACI 230.1R-09 IS ONE RESOURCE THAT PROVIDES MIX DESIGNS BASED ON DIFFERENT CLASSIFICATIONS OF SOIL.
4. CSS SHOULD NOT BE PLACED WHEN TEMPERATURES ARE BELOW 40°F, AGAINST FROZEN TRENCH MATERIAL OR WHEN APPRECIABLE PRECIPITATION IS FORECASTED DURING PLACEMENT.
5. **FOUNDATION:** WHERE THE TRENCH BOTTOM IS UNSTABLE, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER. AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL.
6. **BEDDING:** SUITABLE MATERIAL SHALL BE CSS, OR CLASS I OR II PER ASTM D2321. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. UNLESS OTHERWISE NOTED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4" (100mm) FOR 18"-24" DIAMETER PIPE (300mm-600mm); 6" (150mm) FOR 30"-48" (750mm-1200mm) DIAMETER PIPE. THE MIDDLE 1/3 BENEATH THE PIPE INVERT SHALL BE LOOSELY PLACED.
7. **FINAL BACKFILL:** THE CSS BACKFILL SHALL BE ALLOWED TO CURE AT LEAST 4 HOURS TO REACH AN INITIAL SET STRENGTH PRIOR TO PLACING SOIL ABOVE THE PIPE EMBEDMENT. ADDITIONAL CURE TIME MAY BE REQUIRED BASED ON THE OVERALL FINAL FILL HEIGHT (SEE NOTE 9).
8. **MINIMUM COVER:** MINIMUM COVER, H, IS 12" (300mm) THROUGH 48" (1200mm) DIAMETER PIPE, MEASURED FROM TOP OF PIPE TO BOTTOM OF FLEXIBLE PAVEMENT OR TO TOP OF RIGID PAVEMENT.
9. **MAXIMUM COVER:** MAXIMUM COVER, H, IS BASED ON A MINIMUM 4HR SET TIME OF THE CSS BACKFILL PRIOR TO ANY SOIL PLACEMENT ABOVE THE BACKFILL ENVELOPE. FILL HEIGHTS UP TO 15FT ARE SUITABLE FOR ALL DIAMETERS. LONGER SET TIME MAY ALLOW FOR GREATER FILL HEIGHTS, CONTACT AN ADS REPRESENTATIVE FOR GUIDANCE; SET TIME LESS THAN 4HR MAY RESULT IN HIGHER THAN EXPECTED DEFLECTION AND IMPACT LONG-TERM PERFORMANCE.
10. ANY STORM SEWER 48 INCHES OR SMALLER LOCATED UNDERNEATH OR WITHIN 1 FOOT OF A PAVING SECTION SHALL BE BEDDED AND BACKFILLED WITH 2 SACK CEMENT STABILIZED SAND.

**HDPE STORM BEDDING
AND BACKFILL DETAIL**

WALKER COUNTY

SCALE: NTS 05/16/2025

HDPE IS NOT PERMITTED UNDER
A PUBLIC OR PRIVATE STREET

THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.




TABLE 1
MINIMUM TRENCH WIDTHS AND MAXIMUM FILL HEIGHTS

PIPE DIAM.	MIN. TRENCH WIDTH	MAX. FILL HEIGHT
18" (450mm)	45" (1143mm)	21.0' (6.4m)
24" (600mm)	52" (1321mm)	18.5' (5.6m)
30" (750mm)	60" (1524mm)	18.5' (5.6m)
36" (900mm)	78" (1981mm)	15.5' (4.7m)
42" (1050mm)	83" (2108mm)	15.0' (4.6m)
48" (1200mm)	90" (2286mm)	14.0' (4.3m)

NOTES:


1. ALL PIPE SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS". LATEST ADDITION. NATIVE SOILS SHALL BE OF ADEQUATE STIFFNESS TO WITHSTAND A VERTICAL CUT WITHOUT MATERIAL SLOUGHING. CEMENT-STABILIZED SAND (CSS) EMBEDMENT REQUIRES PLACEMENT IN MAXIMUM 6" (150mm) LIFTS COMPACTED TO A MINIMUM OF 95% OF MAXIMUM DRY DENSITY IN ACCORDANCE WITH ASTM D558, WITH MOISTURE CONTENT ON THE DRY SIDE OF OPTIMUM BUT SUFFICIENT FOR EFFECTIVE HYDRATION.
2. CSS SHALL HAVE A MIX DESIGN OF ADEQUATE FINAL STRENGTH TO CARRY ALL LIVE AND DEAD LOADING BUT ALLOW FOR ANY FUTURE EXCAVATION. THE MIXTURE SHALL CONSIST OF NO LESS THAN 1.1 SACKS OF TYPE 1 PORTLAND CEMENT (CONFORMING TO ASTM C 150) PER ONE TON OF SAND (CONFORMING TO ASTM C 33), RESULTING IN A MINIMUM UNCONFINED COMPRESSIVE STRENGTH OF 100 PSI WITHIN 48 HRS OF SET TIME.
3. CSS SHOULD NOT BE PLACED WHEN TEMPERATURES ARE BELOW 40°F, AGAINST FROZEN TRENCH MATERIAL OR WHEN APPRECIABLE PRECIPITATION IS FORECASTED DURING PLACEMENT.
4. **FOUNDATION:** WHERE THE TRENCH BOTTOM IS UNSTABLE, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER, AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL.
5. **BEDDING:** SUITABLE MATERIAL SHALL BE CSS, OR CLASS I OR II PER ASTM D2321. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. UNLESS OTHERWISE NOTED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4" (100mm) FOR 18"-24" DIAMETER PIPE (450mm-600mm); 6" (150mm) FOR 30"-48" (750mm-1200mm) DIAMETER PIPE. THE MIDDLE 1/3 BENEATH THE PIPE INVERT SHALL BE LOOSELY PLACED.
6. **FINAL BACKFILL:** THE CSS BACKFILL SHALL BE ALLOWED TO CURE AT LEAST 4 HOURS TO REACH AN INITIAL SET STRENGTH PRIOR TO PLACING SOIL ABOVE THE PIPE EMBEDMENT. ADDITIONAL CURE TIME MAY BE REQUIRED BASED ON THE OVERALL FINAL FILL HEIGHT.
7. **MINIMUM COVER:** IN UNPAVED AREAS, MINIMUM COVER, H, IS 12" (450mm) FOR PIPES UP TO 48" (1200mm) IN DIAMETER. IN PAVED AREAS, MINIMUM COVER IS 12" (300mm) FOR PIPES UP TO 48" (1200mm) IN DIAMETER. H IS MEASURED FROM THE TOP OF PIPE TO BOTTOM OF FLEXIBLE PAVEMENT OR TO TOP OF RIGID PAVEMENT, ASSUMING HL-93 LOADING.
8. **MAXIMUM COVER:** MAXIMUM COVER(S), H, ARE LISTED ABOVE IN TABLE 1. THESE VALUES ARE BASED ON A MINIMUM 4 HR SET TIME OF THE CSS BACKFILL PRIOR TO ANY SOIL PLACEMENT ABOVE THE BACKFILL ENVELOPE. SET TIMES LESS THAN 4 HR MAY RESULT IN HIGHER THAN EXPECTED DEFLECTION AND IMPACT LONG-TERM PERFORMANCE. NATIVE SOILS ARE ASSUMED TO BE SOFT COHESIVE CLAYS, AND GROUND WATER LEVELS ARE ASSUMED TO BE AT THE SPRINGLINE OF THE PIPE. STRONGER NATIVE SOILS OR HIGHER GROUNDWATER LEVELS WILL AFFECT THE VALUES LISTED IN THE TABLE.
9. ANY STORM SEWER 48 INCHES OR SMALLER LOCATED UNDERNEATH OR WITHIN 1 FOOT OF A PAVING SECTION SHALL BE BEDDED AND BACKFILLED WITH 2 SACK CEMENT STABILIZED SAND.

**POLYPROPYLENE
STORM BEDDING AND
BACKFILL DETAIL**

WALKER COUNTY

SCALE: NTS 06/16/2025

THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.



MINIMUM RECOMMENDED COVER BASED ON VEHICLE LOADING CONDITIONS

PIPE DIAM.	SURFACE LIVE LOADING CONDITION	
	H-25	HEAVY CONSTRUCTION (75T AXLE LOAD) *
18" - 48" (450mm - 1200mm)	12" (305mm)	48" (1219mm)

* VEHICLES IN EXCESS OF 75T MAY REQUIRE ADDITIONAL COVER

PIPE DIAM.	MIN. "X"	MIN. "S"
18" (450mm)	14" (356mm)	12" (305mm)
24" (600mm)	14" (356mm)	12" (305mm)
30" (750mm)	18" (457mm)	15" (381mm)
36" (900mm)	21" (533mm)	18" (457mm)
42" (1050mm)	21" (533mm)	21" (533mm)
48" (1200mm)	21" (533mm)	24" (610mm)

MINIMUM SPACING ("S") MEASURED FROM OUTSIDE DIAMETER TO OUTSIDE DIAMETER

NOTES:

1. ALL PIPE SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS", LATEST EDITION.
2. MEASURES SHOULD BE TAKEN TO PREVENT MIGRATION OF NATIVE FINES INTO BACKFILL MATERIAL, WHEN REQUIRED.
3. **FOUNDATION:** WHERE THE TRENCH BOTTOM IS UNSTABLE, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER. AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL.
4. **BEDDING:** SUITABLE MATERIAL SHALL BE CLASS I, II OR III. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. UNLESS OTHERWISE NOTED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4" (100mm) FOR 4"-24" (100mm-600mm); 6" (150mm) FOR 30"-48" (750mm-1200mm).
5. **INITIAL BACKFILL:** SUITABLE MATERIAL SHALL BE CLASS I, II OR III IN THE PIPE ZONE EXTENDING TO THE CROWN OF PIPE. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. MATERIAL SHALL BE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION.
6. **MINIMUM COVER:** MINIMUM COVER, H, IN NON-TRAFFIC APPLICATIONS (GRASS OR LANDSCAPE AREAS) IS 12" FROM THE TOP OF PIPE TO GROUND SURFACE. ADDITIONAL COVER MAY BE REQUIRED TO PREVENT FLOTATION. FOR TRAFFIC APPLICATIONS, MINIMUM COVER, H, IS 12" UP TO 48" DIAMETER PIPE, MEASURED FROM TOP OF PIPE TO BOTTOM OF FLEXIBLE PAVEMENT OR TO TOP OF RIGID PAVEMENT.
7. ANY STORM SEWER 48 INCHES OR SMALLER LOCATED UNDERNEATH OR WITHIN 1 FOOT OF A PAVING SECTION SHALL BE BEDDED AND BACKFILLED WITH 2 SACK CEMENT STABILIZED SAND.

**PARALLEL HDPE/PP
PIPE STORM BEDDING
AND BACKFILL DETAIL**

WALKER COUNTY

SCALE: NTS 06/16/2025

**HDPE IS NOT PERMITTED UNDER
A PUBLIC OR PRIVATE STREET**

THIS DETAIL IS A MINIMUM STANDARD. THE FINAL DETAIL SHALL BE DESIGNED, SIGNED, & SEALED BY A PROFESSIONAL ENGINEER.