

NOTES:

1. THE BEARINGS SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, SOUTH CENTRAL ZONE, NAD 83.
2. SURVEYOR DID NOT ABSTRACT PROPERTY. SURVEY BASED ON LEGAL DESCRIPTIONS SUPPLIED BY TITLE COMPANY. EASEMENTS, RECORD LINES, ETC. SHOWN ARE AS EXISTING AT GF NO. CH-189-GTH(CS)-Global OF CHICAGO TITLE.
3. LOCATING OF THIS SURVEY IS INTENDED TO EXPRESS AN OPINION REGARDING OWNERSHIP OR TITLE.
4. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS BEST KNOWLEDGE, INFORMATION AND BELIEF.
5. SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.
6. THE FINDINGS AND OPINIONS OF WELLS LAND SURVEY, LLC REFLECTED HEREON ARE PROPRIETARY, CONFIDENTIAL AND INTENDED FOR THE USE OF THE INDIVIDUAL OR ENTITY FOR WHOM THIS WORK WAS PREPARED. IT IS UNDERSTOOD THAT THE USE OF, RELIANCE ON, OR REPRODUCTION OF SAME, IN WHOLE OR IN PART, BY OTHERS WITHOUT THE EXPRESS WRITTEN CONSENT OF WELLS LAND SURVEY, LLC IS PROHIBITED AND, WITHOUT WARRANTY, EXPRESS OR IMPLIED, SUCH USE OR RELIANCE SHALL BE HELD HARMLESS AGAINST DAMAGES OR EXPENSES RESULTING THEREFROM. ©2014 UNAUTHORIZED USE, RELIANCE OF REPRODUCTION, COPYRIGHT 2022. ALL RIGHTS RESERVED.

SCHEDULE B ITEMS

7. TERMS, CONDITIONS AND STIPULATIONS OF THAT CERTAIN EASEMENT RETAINED IN DEED DATED JANUARY 3, 1946, RECORDED IN VOLUME 302, PAGE 339 OF THE DEED RECORDS OF CHAMBERS COUNTY, TEXAS, FROM A. DELACROIX LAWRENCE, JR., ET AL. TO ALVIN CHARLES BAIL.
   - PIPELINE RIGHT OF WAY FOR SALT WATER PIPELINE, FROM VARUNA A. LAWRENCE TO HUMBLE OIL & REFINING COMPANY, DATED 4/23/46, OF RECORD IN VOLUME 71, PAGE 554 OF SAID DEED RECORDS. (DOES NOT PERTAIN TO SUBJECT TRACT)
   - EASEMENT, RIGHT AND RIGHT TO DRILL WATER WELLS, FROM VARUNA A. LAWRENCE TO HUMBLE OIL & REFINING CO., ET AL, DATED 8-12-50, OF RECORDS IN VOLUME 93, PAGE 467 OF SAID DEED RECORDS. (BLANKET NOT PLOTTABLE)
   - PIPELINE RIGHT OF WAY FROM VARUNA A. LAWRENCE TO SUN PIPE LINE CO., DATED 6/6/55, OF RECORD IN VOLUME 85, PAGE 472 OF SAID DEED RECORDS. (BLANKET NOT PLOTTABLE)
   - R.O.S. FROM A. DELACROIX LAWRENCE TO SUN PIPE LINE CO., DATED 10/28/57, OF RECORD IN VOLUME 99M, PAGE 433 OF SAID DEED RECORDS. (BLANKET NOT PLOTTABLE)
   - R.O.S. FROM A. DELACROIX LAWRENCE TO SUN PIPE LINE CO., DATED 6/16/59, OF RECORD IN VOLUME 140, PAGE 176 OF SAID DEED RECORDS. (DOES NOT PERTAIN TO SUBJECT TRACT)
   - R.O.S. FROM A. DELACROIX LAWRENCE TO SUN PIPE LINE CO., DATED 6/16/59, OF RECORD IN VOLUME 139, PAGE 609 OF SAID DEED RECORDS. (BLANKET NOT PLOTTABLE)
   - R.O.S. FROM VARUNA A. LAWRENCE TO HUMBLE OIL & REFINING CO., DATED 11/13/57, OF RECORD IN VOLUME 99L PAGE 911 OF SAID DEED RECORDS. (BLANKET NOT PLOTTABLE)
   - R.O.S. FROM A. D. LAWRENCE ET UX, TO TEXAS EASTERN GAS TRANSMISSION CO., DATED 9-7-66, OF RECORD IN VOLUME 225, PAGE 449 OF SAID DEED RECORDS. (DOES NOT PERTAIN TO SUBJECT TRACT)
   - PIPELINE RIGHT OF WAY FROM A. D. LAWRENCE ET UX TO SUN PIPELINE CO., DATED 4/7/1971, OF RECORD IN VOLUME 57, PAGE 240 OF SAID DEED RECORDS. (BLANKET NOT PLOTTABLE)
8. TERMS, CONDITIONS AND STIPULATIONS OF THAT CERTAIN RIGHTS OF THIRD PARTIES AND SOUTHERN CANAL COMPANY AS AND TO THE USE OF THAT CERTAIN IRRIGATION CANAL ALONG THE WESTERLY LINE OF THAT CERTAIN 30.054 ACRE TRACT DESCRIBED IN DEED RECORDED IN VOLUME 331, PAGE 600 OF THE DEED RECORDS OF CHAMBERS COUNTY, TEXAS AND ALONG THE WEST LINE OF THAT CERTAIN 41.06 ACRE TRACT DESCRIBED IN DEED RECORDED IN VOLUME 205, PAGE 323 OF THE DEED RECORDS OF CHAMBERS COUNTY, TEXAS. (DOES NOT PERTAIN TO SUBJECT TRACT)

SURVEYOR'S CERTIFICATION

TO: ORIGINO TITLE AND JESUS G. GUTIERREZ, EXCLUSIVELY:

I, TIM WELLS WHITE, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, HEREBY CERTIFY THAT THIS PLAT REPRESENTS A SURVEY MADE ON THE GROUND UNDER MY DIRECT SUPERVISION ON SEPTEMBER 23, 2022, AT THE TIME OF THIS SURVEY THERE WERE NO APPARENT DISCREPANCIES, CONFLICTS IN AREA, BOUNDARY LINE CONFLICTS, ENCROACHMENTS, OVERLAPPING OF IMPROVEMENTS, EXCEPTIONS OR CONFLICTS OF RIGHTS OF WAY, THAT I AM AWARE OF EXCEPT AS SHOWN HEREON, AND THAT SAID PROPERTY HAS ACCESS TO AND FROM A DEDICATED ROADWAY, PROPERTY IS SUBJECT TO ALL CITY ORDINANCES AND SUBDIVISION COVENANTS, CONDITIONS AND RESTRICTIONS THAT MAY APPLY.

THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

Tim Wells White, Registered Professional Land Surveyor No. 5742

STATE OF TEXAS
TIM WELLS WHITE
5742
REGISTERED
LAND SURVEYOR

LEGAL DESCRIPTION 11.8000 ACRES
SOLOMON BARROW LEAGUE, ABSTRACT NO. 3
CHAMBERS COUNTY, TEXAS

BEING A TRACT OR PARCEL CONTAINING 11.8000 ACRES (514,088 SQUARE FEET) OF LAND SITUATED IN THE SOLOMON BARROW LEAGUE, ABSTRACT NO. 3, CHAMBERS COUNTY, TEXAS, BEING OUT OF AND A PART OF A CALLED 187.3491 ACRE TRACT OF LAND CONVEYED TO LLOYD GRUMBHOUSE FROM FUSRO-MCCLELLAND LEASING, INC. BY DEED DATED NOVEMBER 30, 1998 AND RECORDED IN VOLUME 391, PAGE 551 OF THE OFFICIAL PUBLIC RECORDS OF CHAMBERS COUNTY, SAID 11.8000 ACRES BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS, THE BEARINGS SHOWN HEREON ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, SOUTH CENTRAL ZONE, NAD 83;

COMMENCING AT A 1/2 INCH BENT IRON ROD FOUND IN THE WEST RIGHT OF WAY LINE OF FARM TO MARKET HIGHWAY NO. 3354 (120 FEET RIGHT OF WAY), AND BEING THE SOUTHEAST CORNER OF THE RYAN M. PAUL CALLED 9.2308 ACRE TRACT DESCRIBED IN CLERKS FILE NO. 2016-115662 OF THE OFFICIAL PUBLIC RECORDS OF CHAMBERS COUNTY;

THENCE SOUTH 86 DEGREES 40 MINUTES 27 SECONDS WEST, ALONG THE NORTH LINE OF SAID 187.3491 ACRE TRACT, WITH THE SOUTH LINE OF SAID RYAN M. PAUL CALLED 9.2308 ACRE TRACT, A DISTANCE OF 900.07 FEET TO A 5/8 INCH CAPPED IRON ROD SET FOR THE NORTHERLY NORTHEAST CORNER OF THE HEREIN DESCRIBED TRACT AND POINT OF BEGINNING;

THENCE SOUTH 03 DEGREES 15 MINUTES 33 SECONDS EAST, PASS AT 699.80 FEET A 1/2 INCH IRON ROD FOUND FOR THE NORTHWEST CORNER OF THE FREDDIE DALE CORBELLO AND ANITA KAY CORBELLO CALLED 1.00 ACRE TRACT, IN ALL A DISTANCE OF 359.99 FEET TO A 1/2 INCH CAPPED IRON ROD FOUND FOR THE SOUTHWEST CORNER OF SAID FREDDIE DALE CORBELLO AND ANITA KAY CORBELLO CALLED 1.00 ACRE TRACT, AND BEING AN INTERIOR CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE NORTH 86 DEGREES 52 MINUTES 07 SECONDS EAST, ALONG THE SOUTH LINE OF SAID FREDDIE DALE CORBELLO AND ANITA KAY CORBELLO CALLED 1.00 ACRE TRACT, AND WITH THE SOUTH LINE OF THE FREDDIE DALE CORBELLO AND ANITA KAY CORBELLO CALLED 3.00 ACRE TRACT DESCRIBED IN CLERKS FILE NO. 2011-65469 OF THE OFFICIAL PUBLIC RECORDS OF CHAMBERS COUNTY, PASS AT 133.27 FEET THE COMMON SOUTH CORNER OF SAID FREDDIE DALE CORBELLO AND ANITA KAY CORBELLO CALLED 1.00 ACRE TRACT AND SAID FREDDIE DALE CORBELLO AND ANITA KAY CORBELLO CALLED 3.00 ACRE TRACT, IN ALL A DISTANCE OF 200.40 FEET TO A 5/8 INCH BENT IRON ROD FOUND FOR THE NORTHWEST CORNER OF THE DAVID SHARNER AND ANGELA SHARNER CALLED 5.0019 ACRE TRACT DESCRIBED IN CLERKS FILE NO. 2021-170495 OF THE OFFICIAL PUBLIC RECORDS OF CHAMBERS COUNTY, AND BEING THE NORTHEAST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE SOUTH 03 DEGREES 19 MINUTES 09 SECONDS EAST, ALONG THE WEST LINE OF SAID DAVID SHARNER AND ANGELA SHARNER CALLED 5.0019 ACRE TRACT, A DISTANCE OF 307.35 FEET TO A 5/8 INCH CAPPED IRON ROD SET (SURVEY FOUND 5/8 INCH BENT IRON ROD DISTURBED), FOR THE SOUTHWEST CORNER OF SAID DAVID SHARNER AND ANGELA SHARNER CALLED 5.0019 ACRE TRACT, AND BEING AN INTERIOR CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE NORTH 86 DEGREES 39 MINUTES 52 SECONDS EAST, ALONG THE SOUTH LINE OF SAID DAVID SHARNER AND ANGELA SHARNER CALLED 5.0019 ACRE TRACT, A DISTANCE OF 730.33 FEET TO A 5/8 INCH IRON ROD FOUND IN THE WEST LINE OF SAID FARM TO MARKET HIGHWAY NO. 3354, AND IN THE EAST LINE OF SAID 187.3491 ACRE TRACT FOR THE SOUTHEAST CORNER OF SAID DAVID SHARNER AND ANGELA SHARNER CALLED 5.0019 ACRE TRACT, AND BEING THE EASTERLY NORTHEAST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE SOUTH 16 DEGREES 50 MINUTES 34 SECONDS EAST, ALONG THE WEST LINE OF SAID FARM TO MARKET HIGHWAY NO. 3354, AND WITH THE EAST LINE OF SAID 187.3491 ACRE TRACT, A DISTANCE OF 165.75 FEET TO A 1/2 INCH CAPPED IRON ROD FOUND FOR THE NORTHEAST CORNER OF THE ARNA CALLED 80.00 ACRE TRACT DESCRIBED IN CLERKS FILE NO. 2006-14883 OF THE OFFICIAL PUBLIC RECORDS OF CHAMBERS COUNTY, AND BEING THE SOUTHEAST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE SOUTH 87 DEGREES 10 MINUTES 45 SECONDS WEST, ALONG THE NORTH LINE OF SAID ARNA CALLED 80.00 ACRE TRACT, WITH THE SOUTH LINE OF A 4.10 ACRE INGRESS/EGRESS & DRAINAGE EASEMENT DESCRIBED IN VOLUME 1406, PAGE 33 OF THE OFFICIAL PUBLIC RECORDS OF CHAMBERS COUNTY, A DISTANCE OF 1435.40 FEET TO A 5/8 INCH CAPPED IRON ROD SET FOR THE SOUTHEAST CORNER OF A 13.6570 ACRE TRACT SURVEYED THIS DAY, AND BEING THE SOUTHWEST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE NORTH 02 DEGREES 36 MINUTES 02 SECONDS WEST, ACROSS SAID 187.3491 ACRE TRACT, AND WITH THE EAST LINE OF SAID 13.6570 ACRE TRACT SURVEYED THIS DAY, PASS AT 80.00 FEET A 5/8 INCH CAPPED IRON ROD SET FOR REFERENCE IN THE NORTH LINE OF SAID 4.10 ACRE INGRESS/EGRESS & DRAINAGE EASEMENT, IN ALL A DISTANCE OF 790.94 FEET TO A 5/8 INCH CAPPED IRON ROD SET IN THE SOUTH LINE OF THE RALPH AND JOANN OLER TRUST CALLED PROPERTY 1 DESCRIBED IN CLERKS FILE NO. 2022-177662 OF THE OFFICIAL PUBLIC RECORDS OF CHAMBERS COUNTY, AND IN THE NORTH LINE OF SAID 187.3491 ACRE TRACT FOR THE NORTHEAST CORNER OF SAID 13.6570 ACRE TRACT SURVEYED THIS DAY, AND BEING THE NORTHWEST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE NORTH 86 DEGREES 40 MINUTES 27 SECONDS EAST, ALONG THE SOUTH LINE OF SAID RALPH AND JOANN OLER TRUST CALLED PROPERTY 1, THE SOUTH LINE OF SAID RYAN M. PAUL CALLED 9.2308 ACRE TRACT, AND WITH THE NORTH LINE OF SAID 187.3491 ACRE TRACT, PASS AT 120.80 FEET AN AXLE FOUND FOR THE COMMON SOUTH CORNER OF SAID RALPH AND JOANN OLER TRUST CALLED PROPERTY 1, AND SAID RYAN M. PAUL CALLED 9.2308 ACRE TRACT, IN ALL A DISTANCE OF 410.68 FEET TO THE POINT OF BEGINNING AND CONTAINING 11.8000 ACRES OF LAND, MORE OR LESS.

LEGEND:

DRCC – DEED RECORDS CHAMBERS COUNTY
POB – POINT OF BEGINNING
POC – POINT OF COMMENCING
-x-x- BARBED WIRE FENCE
-E- OVERHEAD ELECTRIC LINES
-x-x- WOOD FENCE
COVERED CONCRETE
CONCRETE
UP – UTILITY POLE
WW – WATER WELL
SS – SEPTIC SPRAY HEAD
IRF – IRON ROD FOUND
CRF – CAPPED IRON ROD FOUND
BIRF – BENT IRON ROD FOUND
F.I.R.M. – FLOOD INSURANCE RATE MAP
AC – AIR CONDITIONER
OPRCC – OFFICIAL PUBLIC RECORDS OF CHAMBERS COUNTY

PROPERTY LIES WITHIN FLOOD ZONE "X", ACCORDING TO F.I.R.M. NO. 48071C0010E DATED MAY 04, 2015, BY GRAPHIC PLOTTING ONLY. WELLS LAND SURVEY DOES NOT ASSUME RESPONSIBILITY FOR ERROR DETERMINATION, DEPICTED, NOT DEVELOPMENT PLANNING, DESIGN, OR CONSTRUCTION IS STAKED. THE CONSULTANTS, CITY, AND COUNTY IS WHOM SUBJECT TRACT EXISTS SHOULD BE CONTACTED, MAP ENTITIES MAY IMPOSE GREATER FLOOD PLAIN AND FLOODWAY RESTRICTIONS THAN SHOWN BY F.I.R.M. THAT MAY AFFECT DEVELOPMENT.

SURVEY OF

BEING A TRACT OR PARCEL CONTAINING 11.8000 ACRES (514,088 SQUARE FEET) OF LAND SITUATED IN THE SOLOMON BARROW LEAGUE, ABSTRACT NO. 3, CHAMBERS COUNTY, TEXAS, BEING OUT OF AND A PART OF A CALLED 187.3491 ACRE TRACT OF LAND CONVEYED TO LLOYD GRUMBHOUSE FROM FUSRO-MCCLELLAND LEASING, INC. BY DEED DATED NOVEMBER 30, 1998 AND RECORDED IN VOLUME 391, PAGE 551 OF THE OFFICIAL PUBLIC RECORDS OF CHAMBERS COUNTY.

ADDRESS: 13809 FM-3854
BEACH CITY, TX 77589

BUYER:
JESUS G. GUTIERREZ

WELLS LAND SURVEY

TBPLS LICENSE # 10193909
712 F.M. 562
ANAHUAC, TX 77514
(409) 267-9002
www.wellslandsurvey.com

Copyright 2022

JOB NO: 795-22	DATE: 09-20-22
DRAWN BY: AL	SCALE: 1"= 120'