

ESTIMATE



Prepared For

Alexandria Villalobos
7002 26th Ave
Kenosha , Wi 53143
(262) 945-4018

Everlasting Construction Inc.

527-1st St
Racine, WI 53403
Phone: (262) 331-4052
Email: everlastingconstructioninc@gmail.com
Web: everlasting.construction

Estimate # 312
Date 09/22/2026

Description

Total

Interior drain tile and sump pump installation	\$7,000.00
--	------------

EVERLASTING CONSTRUCTION INC.

Interior Drain Tile & Sump Pump Installation

Scope of Work

Sawcut and remove approximately 100 linear feet of existing basement concrete along the interior foundation perimeter.

Excavate and install new 4-inch perforated corrugated drain tile surrounded by washed drainage stone.

Install dimple board drainage membrane along the lower foundation walls to direct water into the drain tile system.

Furnish and install one 18-inch sump crock with a new 1/3 HP submersible sump pump and check valve.

Connect the drain tile to the sump crock and install a new aboveground exterior discharge line.

Connect the sump pump to the existing electrical outlet and test for proper operation.

Replace removed concrete with a standard concrete patch.

Remove construction debris and perform basic jobsite cleanup.

Exclusions: Electrical upgrades, battery backup, finished wall or flooring repairs, exterior excavation, and unforeseen structural or plumbing repairs. Homeowner is responsible for any required permits.

Warranty: One-year workmanship warranty. Excludes pump failure, power outages, discharge line blockage, and water intrusion outside the installed drainage system.

Total Project Price: \$7000.00

Subtotal	\$7,000.00
-----------------	------------

Total	\$7,000.00
--------------	-------------------

By signing this document, the customer agrees to the services and conditions outlined in this document.