SECURELY COVERING YOUR HOME

WICZEK'S TOP NOTCH CONSTRUCTION
414-397-5054

ESTIMATE DATE April 3rd 2026

THIS PROPOSAL HAS BEEN PREPARED FOR WORK FOUND TO BE NECESSARY ON THE ABOVE DATE:

Brownwood

- [ ] **RE-ROOF**
- [x] **TEAR OFF**
- [ ] **NEW CONSTRUCTION**

BILLING INFORMATION

NAME David + Sue Ziebell

ADDRESS 6220 W. Van Norman Ave

HOME PHONE (414) 306-3978

CELL PHONE ( )

CITY, ZIP Greenfield WI 53220

JOB INFORMATION

ADDRESS - Hard Copy → CITY/ZIP ziebell33@gmail.com

Contractor will, on any job marked as "**TEAR OFF**", remove all existing asphalt shingles, felt and nails down to bare wood surface. Contractor will cover any bare wood surface with ~~15 lb. felt~~ synthetic or ice and water shield where specified. Re-cover with self-sealing asphalt shingles. All new vents, stack pipes/covers and w-style valley's will be installed. Contractor will be responsible for the removal of all trash and debris resulting from the work performed.

Workmanship is guaranteed against leaking and wind damage for ten (10) years. Materials (shingles) guaranteed a minimum of twenty-five (25) years, depending on quality of shingle selected by the home owner. Warranty certificate will be furnished upon receipt of payment in full.

*Any damaged roof boards and/or plywood must be replaced. As this is "hidden damage" (i.e. not visible until old roofing has been removed) there will be an extra charge for any and all such work performed.

DESCRIPTION OF SPECIFIC WORK: Owens Corning Roofing System
- starter shingles
- hip n ridge shingles
- synthetic underlayment
- 6 ft of ice n water
- Venting

- Brown Drip Edge
- 5 slants back
- 2 BATH VENTS
- 1 Lead pipe
- Chimney flashing

- Lifetime Warranty - 1 time transferable

Dumpster Provided

AGGREED DATE 4-3-26 PRICE QUOTE $8700.00

PAYMENT RECEIVED ON Ø OF $ Ø PAYMENT DUE UPON COMPLETION $ 8,700.00

[signature] Kockley
CONTRACTOR SIGNATURE

Maureen S. Ziebell
HOMEOWNER SIGNATURE