NARI

BBB ACCREDITED BUSINESS

ACCURATE INSULATION Solutions

ZERO DRAFT Professional Weatherization Material Authorized Applicator

ENERGY STAR PARTNER

Building Envelope Specialists

Mail to: **John Dreist**	**Work Site:** **1045/1043 Carriage Court** **Palmyra WI 53156**
Phone:	**Fax:**
Mobile: 262-951-5772	**e-mail: dreistfam@gmail.com**
Date: December 10, 2024	**Contact:**

Agreement between customer listed above and Accurate Insulation Solutions, LLC

Work to be performed and materials to be provided.

☐ **Insulation removal:** Remove and dispose of existing blown in insulation/ debris using industrial vacuum method, supply 40-yard dumpster.

$ 5,052.00

☐ **Upper attic area:** Install plywood dam around (2) access to hold back proper insulation amount, weather strip and insulate new 5/8" code required drywall attic access panel, install and seal (8) new LED retro fit kits in kitchen recessed lights, spray Class 1 fire retardant expandable foam on all misc. ceiling penetrations, and partition wall top plates to reduce unwanted air migration from conditioned space, remove and dispose of existing chutes, install 24" O/C proper vents to roof decking to promote adequate attic ventilation, stuff exterior wall top plate area's with batt insulation to prevent insulation fall out and wind washing into soffit areas, install cellulose insulation to achieve an R 38 value.

$ 9,536.00

☐ **Main bathroom ventilation:** Remove and dispose of (4) inefficient existing units, install (4) Panasonic low sone model FV-05-11VF1, exhausted out dedicated existing roof termination in flexible insulated ducting to reduce unwanted condensation.

$ 3,241.00

☐ **Spot mold remediation:** Install MMR stain remover, Shockwave disinfectant and DuraBan antimicrobial spray per manufactures specifications to remove unwanted surface mold and staining from organic roof decking material where needed.

$ 2,846.00

1-9-25

#LOC

CK #102

10.337.50 (50% DP)

mailed w/ signed contract

Ck # 127
3-15-25

INVOICE

Accurate Insulation Solutions
Building Envelope Specialists

Date	Invoice #
3/12/2025	1932

Bill to:	Job Site Description:
John Dreist	1045/1043 Carriage Court Palmyra WI 53156

DATE	DESCRIPTION	AMOUNT
3-12-25	Insulation removal	$ 5,052.00
	Upper attic area	$ 9,286.00
	Main bathroom ventilation	$ 3,241.00
	Spot mold remediation	$ 2,846.00
	Install (2) junction boxes/ plate covers to open electrical boxes	$ 225.00
	Additional dumpster charge	$ 450.00

THANK YOU FOR YOUR BUSINESS!	TOTAL	$ 21,100.00

REMIT INVOICE PAYMENT TO:

Accurate Insulation Solutions
1705 Montclair Place
Fort Atkinson WI 53538
Phone: 262-347-1010
www.accurateinsulationsolutions.com

PAYMENT/CREDITS	$ 10,337.50
BALANCE DUE	$ 10,762.50

Hillander