July 24, 2026
File No. 25226010.01

Resident
W8467 State Road 11
Delavan, WI 53115

Subject: June 2026 Private Well Groundwater Analytical Results (PW-26)

Dear Resident:

On behalf of Mallard Ridge Landfill, Inc. (MRL), SCS Engineers is providing a copy of the results for the groundwater sample that was collected from your water supply well on June 25, 2026. Your well is sampled annually through a voluntary agreement between MRL and the Town of Darien. In accordance with the agreement, the sampling results are being provided to the well owner and the residents at the addresses served by the well (W8467 State Road 11 and W8463 State Road 11).

MONITORING PROGRAM

In accordance with the agreement, the water sample from your well was analyzed for the following parameters:

- Field measurements of pH, conductivity, and temperature
- Field observations of color, odor, and turbidity (clarity)
- Laboratory analysis of alkalinity, sulfate, manganese, iron, hardness, and chloride
- Laboratory analysis of volatile organic compounds (VOCs)

SCS Engineers collected the water sample and performed the field monitoring. Pace Analytical Services, Green Bay, Wisconsin and Ormond Beach, Florida, and Northern Lake Service, Inc., Crandon, Wisconsin performed the laboratory analysis.

MONITORING RESULTS

The results of the field monitoring and laboratory analysis are summarized in the attached table, and the laboratory report is attached. The field monitoring results are included in the laboratory report.

In accordance with the agreement, the results from your well water sample were compared with the drinking water Maximum Contaminant Levels (MCLs) from Wisconsin Administrative Code NR 809.11, the health-related groundwater Enforcement Standards from NR 140.10, and the water quality standards listed in the agreement.

The results were also compared with the public welfare-related groundwater Enforcement Standards in NR 140.12 for chloride, iron, manganese, and sulfate. For these parameters, the NR 140 Enforcement Standards are equal to the Drinking Water Secondary Standards established in NR 809.70. These standards are not based on a health risk, but are based on such criteria as taste, appearance, hardness, and odor.

The June 2026 iron concentration in the sample from your well exceeded the public welfare-related standard, and exceeded the Drinking Water Secondary Standard. The standard for iron in water is based on taste and appearance rather than on any detrimental health effect. There is no health-based standard for iron in drinking water. The level of iron in your well is likely attributable to the natural conditions in the groundwater and is within the range of concentrations found in aquifers in Walworth County.[1]

The June 2026 manganese concentration is higher than the public welfare-based standard. The public welfare-based standard for manganese in water, 50 µg/L, is based on staining and odor considerations rather than on health effects. The health-based standard for manganese is 300 µg/L, and the concentration reported for the sample from your well is well below this level. The level of manganese in your well is likely attributable to the natural conditions in the groundwater and is within the range of concentrations found in aquifers in Walworth County.[1]

Concentrations of the other inorganic parameters (alkalinity, hardness, chloride, sulfate, and field parameters) detected in the sample collected from your well in June 2026 were within normal ranges for groundwater. No VOCs were detected in the water sample collected from your well in June 2026.

CONCLUSIONS

For the tested parameters, the water in your well meets the NR 809 Drinking Water Standards, the State of Wisconsin NR 140 Groundwater Quality Enforcement Standards, and the standards established in the agreement, except for iron and manganese as discussed previously. The next sampling event is scheduled for June 2027.

If you would like to discuss the information in this letter with the Wisconsin Department of Natural Resources (DNR), please contact Greg Roanhouse of the Water Supply Division, at 262-822-7730, or Mark Peters, the site hydrogeologist with the Solid Waste Division, at 608-516-0820.

If you have any questions about the attached results, please contact us at 608-224-2830. Dan Buckley of GFL Environmental, at 262-742-3257, is also available to answer your questions.

Sincerely,

Sherren Clark, PG, PE
Project Director
SCS Engineers

William Ouimet
Staff Professional
SCS Engineers

WCO/REO/SCC

[1] Borman, R.G., 1976, Ground-Water Resources and Geology of Walworth County, Wisconsin. U.S. Geological Survey in Cooperation with Wisconsin Geological and Natural History Survey, Information Circular 34, p.31.

cc: Mr. Mark Peters – DNR, Milwaukee Service Center, Milwaukee
Mr. Greg Roanhouse – DNR, Waukesha Service Center
Ms. Marilyn Larson – Town of Darien
Mr. Daniel Buckley – Mallard Ridge Landfill (2 copies)
Ms. Kari Rabideau – GFL Environmental (e-copy only)

Encl. Table 1: Water Supply Well Sampling Results (PW-26)
Laboratory Report

I:\25226010.01\Deliverables - Working\2026 June PW Letters (LA)\Letters\2026-07-24_PW26_W8467 State Rd 11.docx

Table 1

Summary of Water Supply Well Sampling Results (Current Year plus Previous Four Years) - W8467 and W8463 State Road 11 (PW26)

Parameter (units)	June 2022	June 2023	June 2024	June 2025	June 2026	Drinking Water Primary MCL or Health-Related NR 140 Enforcement Standard (1)	Local Agreement Water Quality Standard (2)	Drinking Water Secondary Standard and Welfare-Based NR 140 Enforcement Standard (3)
Inorganic Laboratory Parameters								
Hardness, total (mg/L as $CaCO_3$)	382	400	396	400	389	--	1000	--
Alkalinity, total (mg/L as $CaCO_3$)	329	316	319	353	329	--	1000	--
Chloride (mg/L as Cl)	18.0	16.2	18.4	16.7	17.3	--	250	250
Sulfate (mg/L as SO_4)	54.5	54.1	57.6	52.6	55.8	--	400	250
Iron (µg/L)	2,490	2,530	2,460	4,570	3,650	--	--	300
Manganese (µg/L)	51.8	51.4	50.6	70.2	65.8	300	--	50
Detected Volatile Organic Compounds								
None detected	ND N2	ND N2	ND	ND	ND	--	--	--
Field Parameters								
Field Specific Conductance (µmhos/cm)	565	490	648	478	708	--	--	--
Field pH (Std. Units)	7.52	7.33	7.38	7.88	7.28	--	--	--
Field Temperature (degrees Centigrade)	15.1	16.9	15.0	16.1	14.5	--	--	--
Color	None	None	None	None	None	--	--	`
Odor	None	None	None	None	None	--	--	--
Turbidity	None	None	None	None	None	--	--	--

MCL = Maximum Contaminant Level
-- = Standard Not Established
ND = Not Detected

mg/L = milligrams per liter, or parts per million
µg/L = micrograms per liter, or parts per billion
µmhos/cm = micromhos per centimeter

1 mg/L = 1000 µg/L

Notes:
(1) NR 809.11 Primary Inorganic Chemical Maximum Contaminant Levels and NR 140.10 Groundwater Quality Enforcement Standards
(2) Water quality standards in Exhibit H, Paragraph 3, of the agreement between Mallard Ridge Landfill and the Town of Darien
(3) NR 809.70 Secondary Inorganic Chemical Standards and NR 140.12 Groundwater Quality Enforcement Standards

Table 1

Summary of Water Supply Well Sampling Results (Current Year plus Previous Four Years) - W8467 and W8463 State Road 11 (PW26)

Laboratory Notes:
N2 = The lab does not hold NELAC/TNI accreditation for this parameter but other accreditations/certifications may apply. A complete list of accreditations/certifications is available upon request.

Created by:	MOB	Date: 8/15/2014
Last revision by:	WCO	Date: 7/16/2026
Checked by:	MCK	Date: 7/17/2026

I:\25226010.01\Deliverables - Working\2026 June PW Letters (LA)\Table\[Table 1 - June 2026_Water Supply Well Sampling Results.xls]PW26

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

July 14, 2026

Dan Buckley
GFL Mallard Ridge Landfill
W8470 State Rd 11
Delavan, WI 53115

RE: Project: MRL #03244 PW-26
Pace Project No.: 40314716

Dear Dan Buckley:

Enclosed are the analytical results for sample(s) received by the laboratory on June 26, 2026. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

Some analyses were subcontracted outside of the Pace Network. The test report from the external subcontractor is attached to this report in its entirety.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay
- Pace Analytical Services - Ormond Beach

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Cindy K Varga

Cindy Varga
cindy.varga@pacelabs.com
(920)469-2436
Project Manager

Enclosures
cc:

REPORT OF LABORATORY ANALYSIS
This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

Kate Brunner, SCS ENGINEERS
Sherren Clark, SCS Engineers
Tracy Ipavec, SCS Engineers
Janice Newell, SCS Engineers
Regin Ostien, SCS Engineers
Kari Rabideau, GFL Environmental
Betty Socha, SCS ENGINEERS
Emma Syverson, SCS Engineers

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Table of Contents

Sections: 1 2 3 4 5 6 7 8 9

Section 1: Cert Page 4
Section 2: Sample Summary 5
Section 3: Sample Analyte 6
Section 4: Results 7
Section 5: Quality Control 8
Section 6: Qualifiers 13
Section 7: QC Cross Reference 14
Section 8: Chain of Custody 15
8.1: Chain of Custody 15
Section 9: Subcontract Report 18

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

CERTIFICATIONS

Project: MRL #03244 PW-26
Pace Project No.: 40314716

Pace Analytical Services Ormond Beach

8 East Tower Circle, Ormond Beach, FL 32174
Alabama Certification #: 41320
Colorado Certification: FL NELAC Reciprocity
Delaware Certification: FL NELAC Reciprocity
Florida Certification #: E83079
Guam Certification: FL NELAC Reciprocity
Illinois Certification #: 200068
Kansas Certification #: E-10383
Louisiana Certification #: FL NELAC Reciprocity
Maine Certification #: FL01264
Massachusetts Certification #: M-FL1264
Mississippi Certification: FL NELAC Reciprocity
Montana Certification #: Cert 0074
Nevada Certification: FL NELAC Reciprocity
New Jersey Certification #: FL022
North Carolina Environmental Certificate #: 667
North Dakota Certification #: R-216
Oklahoma Certification #: 2501
Puerto Rico Certification #: FL01264
South Dakota, FL NELAC Reciprocity
Texas Certification: FL NELAC Reciprocity
Utah FL NELAC Reciprocity
Virginia Environmental Certification #: 460165
West Virginia Certification #: 9962C
Wyoming (EPA Region 8): FL NELAC Reciprocity
Alaska DEC- CS/UST/LUST
California Certification# 3096
Connecticut Certification #: PH-0216
DoD-ANAB #:ADE-3199
Georgia Certification #: 955
Hawaii Certification: FL NELAC Reciprocity
Indiana Certification: FL NELAC Reciprocity
Kentucky Certification #: 90050
Louisiana Environmental Certificate #: 05007
Maryland Certification: #346
Michigan Certification #: 9911
Missouri Certification #: 236
Nebraska Certification: NE-OS-28-14
New Hampshire Certification #: 2958
New York Certification #: 11608
North Carolina Certification #: 12710
Ohio DEP 87780
Pennsylvania Certification #: 68-00547
South Carolina Certification: #96042001
Tennessee Certification #: TN02974
US Virgin Islands Certification: FL NELAC Reciprocity
Utah
Washington Certification #: C955
Wisconsin Certification #: 399079670

Pace Analytical Services Green Bay

1241 Bellevue Street, Green Bay, WI 54302
Illinois EPA Certification # 200050
Kentucky UST DEP Certification # 123059
Minnesota DOH Certification # 055-999-334
North Dakota DEQ Certification # R-150
South Carolina DES Certification # 83006001
USDA APHIS Foreign Soil Permit # 525-24-3-36355
Virginia VELAP Certification # 460263
Wisconsin DNR Certification # 405132750
Florida DOH Certification # E87948
ISO/IEC 17025 (A2LA) Certification # 6154.01
Louisiana DEQ Certification # 04168
New York DOH Certification # 12064
ISO/IEC 17025 (A2LA) Certification # 6154.01
Texas TCEQ Certification # T104704529
U.S. Fish & Wildlife Service Permit # 51774A
Wisconsin DATCP Certification # 444

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Date: 07/14/2026 05:40 PM

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

SAMPLE SUMMARY

Project: MRL #03244 PW-26
Pace Project No.: 40314716

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40314716001	**GREIDANUS (PW-26)**	Water	06/25/26 13:15	06/26/26 09:00

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

SAMPLE ANALYTE COUNT

Project: MRL #03244 PW-26
Pace Project No.: 40314716

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
40314716001	**GREIDANUS (PW-26)**	EPA 504.1	LJM	2	PASI-O
		EPA 6010D	SIS	3	PASI-G
			SLV	6	PASI-G
		EPA 310.2	MT	1	PASI-G
		EPA 375.2	AMR1	1	PASI-G
		SM 4500-Cl-E	AMR1	1	PASI-G

PASI-G = Pace Analytical Services - Green Bay
PASI-O = Pace Analytical Services - Ormond Beach

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Date: 07/14/2026 05:40 PM

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

ANALYTICAL RESULTS

Project: MRL #03244 PW-26
Pace Project No.: 40314716

Sample: GREIDANUS (PW-26) **Lab ID: 40314716001** Collected: 06/25/26 13:15 Received: 06/26/26 09:00 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
504.1 GCS EDB and DBCP	Analytical Method: EPA 504.1 Preparation Method: EPA 504.1 Pace Analytical Services - Ormond Beach								
1,2-Dibromo-3-chloropropane	**<0.0062**	ug/L	0.019	0.0062	1	07/02/26 14:24	07/03/26 02:13	96-12-8	
1,2-Dibromoethane (EDB)	**<0.0073**	ug/L	0.0097	0.0073	1	07/02/26 14:24	07/03/26 02:13	106-93-4	
6010D MET ICP	Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Green Bay								
Iron	**3650**	ug/L	100	56.7	1	07/02/26 10:15	07/08/26 15:05	7439-89-6	
Manganese	**65.8**	ug/L	5.0	1.5	1	07/02/26 10:15	07/08/26 15:05	7439-96-5	
Total Hardness SM2340B (2021)	**389000**	ug/L	5400	1000	1	07/02/26 10:15	07/08/26 15:05		
Field Data	Analytical Method: Pace Analytical Services - Green Bay								
Field pH	**7.28**	Std. Units			1		06/25/26 13:15		
Field Specific Conductance	**708**	umhos/cm			1		06/25/26 13:15		
Turbidity	**N**	NTU			1		06/25/26 13:15		
Apparent Color	**N**	no units			1		06/25/26 13:15		
Odor	**N**	no units			1		06/25/26 13:15		
Temperature, Water (C)	**14.5**	deg C			1		06/25/26 13:15		
310.2 Alkalinity	Analytical Method: EPA 310.2 Pace Analytical Services - Green Bay								
Alkalinity, Total as CaCO3	**329**	mg/L	25.0	7.4	1		06/29/26 13:52		
375.2 Sulfate, Total	Analytical Method: EPA 375.2 Pace Analytical Services - Green Bay								
Sulfate	**55.8**	mg/L	10.0	1.9	1		07/06/26 13:23	14808-79-8	
4500 Chloride	Analytical Method: SM 4500-Cl-E Pace Analytical Services - Green Bay								
Chloride	**17.3**	mg/L	5.0	1.6	1		07/02/26 11:25	16887-00-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Date: 07/14/2026 05:40 PM

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: MRL #03244 PW-26
Pace Project No.: 40314716

QC Batch: 541734
QC Batch Method: EPA 3010A
Analysis Method: EPA 6010D
Analysis Description: 6010D MET
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40314716001

5

METHOD BLANK: 3079433 Matrix: Water

Associated Lab Samples: 40314716001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Iron	ug/L	<56.7	100	07/08/26 14:33	
Manganese	ug/L	<1.5	5.0	07/08/26 14:33	
Total Hardness SM2340B (2021)	ug/L	<1000	5400	07/08/26 14:33	

LABORATORY CONTROL SAMPLE: 3079434

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	ug/L	10000	10600	106	80-120	
Manganese	ug/L	250	262	105	80-120	
Total Hardness SM2340B (2021)	ug/L		68900			

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 3079435 3079436

Parameter	Units	40314601001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Iron	ug/L	268	10000	10000	10600	10700	103	105	75-125	1	20	
Manganese	ug/L	103	250	250	365	371	105	107	75-125	2	20	
Total Hardness SM2340B (2021)	ug/L	118000			189000	194000				3	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Date: 07/14/2026 05:40 PM

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: MRL #03244 PW-26
Pace Project No.: 40314716

QC Batch: 1203370
QC Batch Method: EPA 504.1
Analysis Method: EPA 504.1
Analysis Description: 504 EDB DBCP
Laboratory: Pace Analytical Services - Ormond Beach

Associated Lab Samples: 40314716001

5

METHOD BLANK: 6581627 Matrix: Water

Associated Lab Samples: 40314716001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
1,2-Dibromo-3-chloropropane	ug/L	<0.0064	0.020	07/02/26 21:41	
1,2-Dibromoethane (EDB)	ug/L	<0.0075	0.010	07/02/26 21:41	

LABORATORY CONTROL SAMPLE & LCSD: 6581628 6581629

Parameter	Units	Spike Conc.	LCS Result	LCSD Result	LCS % Rec	LCSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
1,2-Dibromo-3-chloropropane	ug/L	0.25	0.25	0.26	100	102	70-130	3	40	
1,2-Dibromoethane (EDB)	ug/L	0.25	0.26	0.26	104	106	70-130	2	40	

MATRIX SPIKE SAMPLE: 6581630

Parameter	Units	35046574003 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
1,2-Dibromo-3-chloropropane	ug/L	0.0065U	0.25	0.26	102	65-135	
1,2-Dibromoethane (EDB)	ug/L	0.0076U	0.25	0.26	104	65-135	

SAMPLE DUPLICATE: 6581631

Parameter	Units	50435032001 Result	Dup Result	RPD	Max RPD	Qualifiers
1,2-Dibromo-3-chloropropane	ug/L	ND	<0.0065		40	
1,2-Dibromoethane (EDB)	ug/L	ND	<0.0076		40	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Date: 07/14/2026 05:40 PM

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: MRL #03244 PW-26
Pace Project No.: 40314716

QC Batch: 541326
QC Batch Method: EPA 310.2
Analysis Method: EPA 310.2
Analysis Description: 310.2 Alkalinity
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40314716001

5

METHOD BLANK: 3077768 Matrix: Water

Associated Lab Samples: 40314716001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Alkalinity, Total as CaCO3	mg/L	<7.4	25.0	06/29/26 13:36	

LABORATORY CONTROL SAMPLE: 3077769

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO3	mg/L	100	103	103	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 3077770 3077771

Parameter	Units	40314500016 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Alkalinity, Total as CaCO3	mg/L	232	100	100	330	333	98	102	90-110	1	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 3077772 3077773

Parameter	Units	40314758001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Alkalinity, Total as CaCO3	mg/L	339	100	100	432	434	93	96	90-110	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Date: 07/14/2026 05:40 PM

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: MRL #03244 PW-26
Pace Project No.: 40314716

QC Batch: 541857
QC Batch Method: EPA 375.2
Analysis Method: EPA 375.2
Analysis Description: 375.2 Sulfate, Total
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40314716001

5

METHOD BLANK: 3080359 Matrix: Water

Associated Lab Samples: 40314716001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Sulfate	mg/L	<1.9	10.0	07/06/26 13:10	

LABORATORY CONTROL SAMPLE: 3080360

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfate	mg/L	50	53.6	107	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 3080361 3080362

Parameter	Units	40314428001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Sulfate	mg/L	93.5	125	125	228	223	107	104	90-110	2	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 3080363 3080364

Parameter	Units	40314598001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Sulfate	mg/L	85.7	125	125	226	220	112	107	90-110	3	20	M0

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Date: 07/14/2026 05:40 PM

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: MRL #03244 PW-26
Pace Project No.: 40314716

QC Batch: 541695
QC Batch Method: SM 4500-Cl-E
Analysis Method: SM 4500-Cl-E
Analysis Description: 4500 Chloride
Laboratory: Pace Analytical Services - Green Bay

Associated Lab Samples: 40314716001

5

METHOD BLANK: 3079334 Matrix: Water

Associated Lab Samples: 40314716001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Chloride	mg/L	<1.6	5.0	07/02/26 11:08	

LABORATORY CONTROL SAMPLE: 3079335

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Chloride	mg/L	100	105	105	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 3079336 3079337

Parameter	Units	40314644001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Chloride	mg/L	3.9J	100	100	111	114	107	110	90-110	2	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 3079338 3079339

Parameter	Units	40314644002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Chloride	mg/L	<1.6	100	100	108	111	107	109	90-110	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Date: 07/14/2026 05:40 PM

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALIFIERS

Project: MRL #03244 PW-26
Pace Project No.: 40314716

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above LOD.
J - The reported result is an estimated value.
LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.
LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.
DL - Adjusted Method Detection Limit.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Analyte was not detected and is reported as less than the LOD or as defined by the customer.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

ANALYTE QUALIFIERS

M0	Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: MRL #03244 PW-26
Pace Project No.: 40314716

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40314716001	**GREIDANUS (PW-26)**	EPA 504.1	1203370	EPA 504.1	1203487
40314716001	**GREIDANUS (PW-26)**	EPA 3010A	541734	EPA 6010D	541782
40314716001	**GREIDANUS (PW-26)**				
40314716001	**GREIDANUS (PW-26)**	EPA 310.2	541326		
40314716001	**GREIDANUS (PW-26)**	EPA 375.2	541857		
40314716001	**GREIDANUS (PW-26)**	SM 4500-Cl-E	541695		

7

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace® Location Requested (City/State):
Pace Analytical Green Bay
1241 Bellevue Street, Suite 9
Green Bay, WI 54302

CHAIN-OF-CUSTODY Analytical Request Document

Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

LAB USE ONLY- Affix Workorder/Login Label Here

40314716

Scan QR Code for instructions

Company Name:	GFL Mallard Ridge Landfill	Contact/Report To:	Dan Buckley
Street Address:	W8470 State Rd 11, Delavan, WI 53115	Phone #:	
		E-Mail:	dbuckley@gflenv.com
		Cc E-Mail:	
Customer Project #:			
Project Name:	MRL #03244 PW	Invoice To:	Dan Buckley
		Invoice E-Mail:	dbuckley@gflenv.com
Site Collection Info/Facility ID (as applicable):		Purchase Order # (if applicable):	C05840000038 BU926
		Quote #:	
Time Zone Collected: [ ] AK [ ] PT [ ] MT [x] CT [ ] ET		County / State origin of sample(s):	Wisconsin

Data Deliverables: [x] Level II [ ] Level III [ ] Level IV [ ] EQUIS [ ] Other

Regulatory Program (DW, RCRA, etc.) as applicable: Reportable [ ] Yes [ ] No

Rush (Pre-approval required): [ ] Same Day [ ] 1 Day [ ] 2 Day [ ] 3 Day [ ] Other _____

DW PWSID # or WW Permit # as applicable:

Date Results Requested:

Field Filtered (if applicable): [ ] Yes [ ] No

Analysis:

* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Waste Water (WW), Product (P), Soil/Solid (SS), Oil (OL), Wipe (WP), Tissue (TS), Bioassay (B), Vapor (V), Surface Water (SW),Sediment (SED), Sludge (SL), Caulk (CK), Leachate (LL), Biosolid (BS), Other (OT)

Customer Sample ID	Matrix *	Comp / Grab	Composite Start Date	Composite Start Time	Collected or Composite End Date	Collected or Composite End Time	# Cont.	Res. Chlorine Results	Res. Chlorine Units	524 VOCs NR507	524 VOCs Trip Blank	6010 Fe,Mn,Hardness	Alk,Cl,SO4	504 EDB/DBCP	Sample Comment
										Specify Container Size **					
										6	6	3	3	6	
										Identify Container Preservative Type***					
										9/4	4	2	1	8	
										Analysis Requested					
GREIDANUS (PW-26)	GW	G	—	—	6/25/26	1315	8			X		X	X	X	001

**Container Size: (1) 1L, (2) 500mL, (3) 250mL, (4) 125mL, (5) 100mL, (6) 40mL vial, (7) EnCore, (8) TerraCore, (9) 90mL, (10) Other

*** Preservative Types: (1) None, (2) HNO3, (3) H2SO4, (4) HCl, (5) NaOH, (6) Zn Acetate, (7) NaHSO4, (8) Sod. Thiosulfate, (9) Ascorbic Acid, (10) MeOH, (11) Other

Lab Use Only

Proj. Mgr: Cindy Varga

AcctNum / Client ID:

Table #:

Profile / Template: 6689

Prelog / Bottle Ord. ID: EZ 3363508

Preservation non-conformance identified for sample.

Additional Instructions from Pace®:

Collected By: (Printed Name) Katrina Waltenberger

Signature:

Customer Remarks / Special Conditions / Possible Hazards:

# Coolers:	Thermometer ID:	Correction Factor (°C):	Obs. Temp. (°C)	Corrected Temp. (°C)	On Ice:

Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature)	Date/Time:	Tracking Number:
GFL LOGISTICS	6/25/26 1530			
GFL LOGISTICS	6/26/26 0900	Stefanie VerBoogen PACE	6/26/26 0900	Delivered by: [ ] In-Person [ ] Courier [ ] FedEX [ ] UPS [ ] Other
Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature)	Date/Time:	
Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature)	Date/Time:	Page: 1 of 1

Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace® Terms and Conditions found at https://www.pacelabs.com/resource-library/resource/pace-terms-and-conditions/

ENV-FRM-CORQ-0019_v02_110123 ©

8.1

8

Sample Preservation Receipt Form

Client Name: GFL Maillard Ridge LF Project # 40314716

All containers needing preservation have been checked and noted below: ☒Yes ☐No ☐N/A Initial when completed: LM Date/ Time:

Lab Lot# of pH paper: 10D46242 Lab Std #ID of preservation (if pH adjusted):

Pace Lab #	Glass							Plastic						Vials						Jars				General				VOA Vials (>6mm) *	H2SO4 pH ≤2	NaOH+Zn Act pH ≥9	NaOH pH ≥12	HNO3 pH ≤2	pH after adjusted	Volume (mL)
	AG1U	BG1U	AG1H	AG4S	AG5U	AG2S	BG3U	BP1U	BP3U	BP3B	BP3N	BP3S	BP2Z	VG9C	DG9T	VG9U	VG9H	VG9M	VG9D	JGFU	JG9U	WGFU	WPFU	SP5T	ZPLC	GN 1	GN 2							
001									1		1			3	3		3															X		2.5 / 5
002																6/2	6/26 SCJ																	2.5 / 5
003																																		2.5 / 5
004																																		2.5 / 5
005																																		2.5 / 5
006																																		2.5 / 5
007									CH1																									2.5 / 5
008																																		2.5 / 5
009																																		2.5 / 5
010																																		2.5 / 5
011																																		2.5 / 5
012																																		2.5 / 5
013																																		2.5 / 5
014																																		2.5 / 5
015																																		2.5 / 5
016																																		2.5 / 5
017																																		2.5 / 5
018																																		2.5 / 5
019																																		2.5 / 5
020																																		2.5 / 5

Exceptions to preservation check: VOA, Coliform, TOC, TOX, TOH, O&G, WI DRO, Phenolics, Other: _____ Headspace in VOA Vials (>6mm) : ☐Yes ☒No ☐N/A *If yes look in headspace column

5 6/26/26 SCJ

AG1U	1 liter amber glass	BP1U	1 liter plastic unpres	VG9C	40 mL clear ascorbic w/ HCl	JGFU	4 oz amber jar unpres
BG1U	1 liter clear glass	BP3U	250 mL plastic unpres	DG9T	40 mL amber Na Thio	JG9U	9 oz amber jar unpres
AG1H	1 liter amber glass HCL	BP3B	250 mL plastic NaOH	VG9U	40 mL clear vial unpres	WGFU	4 oz clear jar unpres
AG4S	125 mL amber glass H2SO4	BP3N	250 mL plastic HNO3	VG9H	40 mL clear vial HCL	WPFU	4 oz plastic jar unpres
AG5U	100 mL amber glass unpres	BP3S	250 mL plastic H2SO4	VG9M	40 mL clear vial MeOH	SP5T	120 mL plastic Na Thiosulfate
AG2S	500 mL amber glass H2SO4	BP2Z	500 mL plastic NaOH + Zn	VG9D	40 mL clear vial DI	ZPLC	ziploc bag
BG3U	250 mL clear glass unpres					GN 1	
						GN 2	

Sample Condition Upon Receipt Form (SCUR)

Project #:

WO#: 40314716

40314716

Client Name: GFL Mallard Ridge LF

Courier: ☒ CS Logistics ☐ Fed Ex ☐ Speedee ☐ UPS ☐ Purple Mountain ☐ Client ☐ Pace Other: _____

Tracking #: N/A

Custody Seal on Cooler/Box Present: ☐ yes ☒ no Seals intact: ☐ yes ☒ no

Custody Seal on Samples Present: ☐ yes ☒ no Seals intact: ☐ yes ☒ no

Packing Material: ☐ Bubble Wrap ☐ Bubble Bags ☐ None ☒ Other Ziploc

Thermometer Used SR - 149 **Type of Ice:** Wet Blue Dry None ☐ Meltwater Only

Cooler Temperature Uncorr: 0 /Corr: 0

Temp Blank Present: ☐ yes ☒ no **Biological Tissue is Frozen:** ☐ yes ☐ no

Temp should be above freezing to 6°C.
Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

Person examining contents:
Date: 6/26/24 Initials: LM

Labeled By Initials: BM

Chain of Custody Present:	☒Yes ☐No ☐N/A	1.
Chain of Custody Filled Out:	☒Yes ☐No ☐N/A	2.
Chain of Custody Relinquished:	☒Yes ☐No ☐N/A	3.
Sampler Name & Signature on COC:	☒Yes ☐No ☐N/A	4.
Samples Arrived within Hold Time:	☒Yes ☐No	5.
- DI VOA Samples frozen upon receipt	☐Yes ☐No	Date/Time:
Short Hold Time Analysis (<72hr):	☐Yes ☒No	6.
Rush Turn Around Time Requested:	☐Yes ☒No	7.
Sufficient Volume: For Analysis: ☒Yes ☐No MS/MSD: ☐Yes ☐No ☒N/A		8.
Correct Containers Used:	☒Yes ☐No	9.
Correct Type: Pace Green Bay, Pace IR, Non-Pace		
Containers Intact:	☒Yes ☐No	10.
Filtered volume received for Dissolved tests	☐Yes ☐No ☒N/A	11.
Sample Labels match COC: -Includes date/time/ID/Analysis Matrix: W	☒Yes ☐No ☐N/A	12.
Trip Blank Present:	☐Yes ☐No ☒N/A	13.
Trip Blank Custody Seals Present	☐Yes ☐No ☒N/A	
Pace Trip Blank Lot # (if purchased):		

Client Notification/ Resolution: If checked, see attached form for additional comments ☐

Person Contacted: _____ Date/Time: _____

Comments/ Resolution: _____

PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample logir

Page 2 of 2

Northern Lake Service, Inc • 400 N Lake Ave • Crandon, WI 54520
800-278-1254 • www.nlslab.com

July 06, 2026

Cindy Varga
Pace Analytical Services Inc (GB)
1241 Bellevue Street
Green Bay, WI 54302

Project: 2026 DW Testing - MRL #03244 PW (No EDD)
Project Number: 40314716 MRL #03244 PW-26
Work Order: CE06986
Received: 06/30/26

Enclosed are the results of analyses for samples received by our laboratory on 6/30/2026. If you have any questions concerning this report, please feel free to contact a client service representative at clientservices@nlslab.com.

Sincerely,

Ronald T. Krueger - CEO
Northern Lake Service, Inc.

Pace Analytical Services Inc (GB)	Project: 2026 DW Testing - MRL #03244 PW (No EDD)		
1241 Bellevue Street	Project Number: 40314716 MRL #03244 PW-26	**Reported:**	**Work Order:**
Green Bay, WI 54302	Project Manager: Cindy Varga	7/6/26 13:40	CE06986

Sample Summary

Descriptions of all qualifiers and comments listed throughout this report can be found on the Qualifiers Definitions Page.

Lab ID	Sample	Matrix	Date Sampled	Date Received
CE06986-01	40314716001 (Greidanus PW-26)	DW	6/25/26 13:15	6/30/26 11:45

Analysis Qualifiers:

LabNumber	Analysis	Qualifier
CE06986-01	524.2 VOCs by GC/MS	FBNAc

6

The contents of this report apply to the sample(s) analyzed in accordance with the chain of custody document.
No duplication of this report is allowed, except in its entirety.

Pace Analytical Services Inc (GB)	Project: 2026 DW Testing - MRL #03244 PW (No EDD)		
1241 Bellevue Street	Project Number: 40314716 MRL #03244 PW-26	**Reported:**	**Work Order:**
Green Bay, WI 54302	Project Manager: Cindy Varga	7/6/26 13:40	CE06986

Case Narrative

The trip blank for this work order can be referenced on work order CE06981.

The contents of this report apply to the sample(s) analyzed in accordance with the chain of custody document.
No duplication of this report is allowed, except in its entirety.

Pace Analytical Services Inc (GB)	Project: 2026 DW Testing - MRL #03244 PW (No EDD)		
1241 Bellevue Street	Project Number: 40314716 MRL #03244 PW-26	**Reported:**	**Work Order:**
Green Bay, WI 54302	Project Manager: Cindy Varga	7/6/26 13:40	CE06986

Sample Results

Sample: 40314716001 (Greidanus PW-26)

CE06986-01 (DW) Sampled: 06/25/26 13:15

Analyte	Result	Qualifier	LOD	LOQ	MCL	Units	Date Prepared	Date Analyzed	Analyst	Method	Laboratory FID
Volatiles Analytes: 43											
Benzene	ND		0.17	0.57	5	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Bromodichloromethane	ND		0.23	0.77	80	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Bromoform	ND		0.24	0.80	80	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Bromomethane	ND		0.30	1.0		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Carbon Tetrachloride	ND		0.30	1.0	5	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Chloroethane	ND		0.25	0.83		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Chloroform	ND		0.24	0.80	80	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Chloromethane	ND		0.27	0.90		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Dibromochloromethane	ND		0.24	0.80	80	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Dibromomethane	ND		0.22	0.73		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
1,3-Dichlorobenzene	ND		0.28	0.93		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
1,2-Dichlorobenzene	ND		0.32	1.1	600	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
1,4-Dichlorobenzene	ND		0.29	0.97	75	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Dichlorodifluoromethane	ND		0.22	0.73		ug/L	7/1/26 11:43	7/1/26	JLG	EPA 524.2, Rev 4.1	2
1,1-Dichloroethane	ND		0.21	0.70		ug/L	7/1/26 11:43	7/1/26	JLG	EPA 524.2, Rev 4.1	2
1,2-Dichloroethane	ND		0.22	0.73	5	ug/L	7/1/26 11:43	7/1/26	JLG	EPA 524.2, Rev 4.1	2
1,1-Dichloroethene	ND		0.31	1.0	7	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
cis-1,2-Dichloroethene	ND		0.23	0.77	70	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
trans-1,2-Dichloroethene	ND		0.20	0.67	100	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Dichloromethane	ND		0.18	0.60	5	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
1,2-Dichloropropane	ND		0.16	0.53	5	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Ethyl Benzene	ND		0.21	0.70	700	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
MTBE	ND		0.24	0.80		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Chlorobenzene	ND		0.20	0.67	100	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Naphthalene	ND		0.19	0.63		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Styrene	ND		0.19	0.63	100	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Tetrachloroethene	ND		0.25	0.83	5	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Toluene	ND		0.20	0.67	1000	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
1,2,4-Trichlorobenzene	ND		0.28	0.93	70	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
1,1,1-Trichloroethane	ND		0.23	0.77	200	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2

The contents of this report apply to the sample(s) analyzed in accordance with the chain of custody document.
No duplication of this report is allowed, except in its entirety.

Pace Analytical Services Inc (GB)	Project: 2026 DW Testing - MRL #03244 PW (No EDD)		
1241 Bellevue Street	Project Number: 40314716 MRL #03244 PW-26	**Reported:**	**Work Order:**
Green Bay, WI 54302	Project Manager: Cindy Varga	7/6/26 13:40	CE06986

Sample: 40314716001 (Greidanus PW-26) (Continued)

CE06986-01 (DW) Sampled: 06/25/26 13:15

Analyte	Result	Qualifier	LOD	LOQ	MCL	Units	Date Prepared	Date Analyzed	Analyst	Method	Laboratory FID
Volatiles (Continued) Analytes: 43											
1,1,2-Trichloroethane	ND		0.21	0.70	5	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Trichloroethene	ND		0.22	0.73	5	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Trichlorofluoromethane	ND		0.33	1.1		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Vinyl Chloride	ND		0.18	0.60	0.2	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Xylene (Total)	ND		0.24	0.80	10000	ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Acetone	ND		7.6	25		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Carbon disulfide	ND		1.3	4.3		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
cis-1,3-Dichloropropene	ND		0.26	0.87		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Methyl ethyl ketone	ND		2.1	7.0		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Tetrahydrofuran	ND		0.44	1.5		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
trans-1,3-Dichloropropene	ND		0.25	0.83		ug/L	7/1/26 11:43	7/1/26 15:58	JLG	EPA 524.2, Rev 4.1	2
Surrogate: (SURR) 4-Bromofluorobenzene	*105%*		*Limits: 36-122%*				*7/1/26 11:43*	*7/1/26 15:58*	*JLG*	*EPA 524.2, Rev 4.1*	
Surrogate: (SURR) 1,2-Dichlorobenzene-d4	*100%*		*Limits: 42-127%*				*7/1/26 11:43*	*7/1/26 15:58*	*JLG*	*EPA 524.2, Rev 4.1*	

6

The contents of this report apply to the sample(s) analyzed in accordance with the chain of custody document.
No duplication of this report is allowed, except in its entirety.

Pace Analytical Services Inc (GB)	Project: 2026 DW Testing - MRL #03244 PW (No EDD)		
1241 Bellevue Street	Project Number: 40314716 MRL #03244 PW-26	**Reported:**	**Work Order:**
Green Bay, WI 54302	Project Manager: Cindy Varga	7/6/26 13:40	CE06986

Laboratory Facility Identifications

Code	Description	Number	Expires
2	NLS (Crandon) WDNR Laboratory ID No.	721026460	8/31/26

9

The contents of this report apply to the sample(s) analyzed in accordance with the chain of custody document.
No duplication of this report is allowed, except in its entirety.

Pace Analytical Services Inc (GB)	Project: 2026 DW Testing - MRL #03244 PW (No EDD)		
1241 Bellevue Street	Project Number: 40314716 MRL #03244 PW-26	**Reported:**	**Work Order:**
Green Bay, WI 54302	Project Manager: Cindy Varga	7/6/26 13:40	CE06986

Qualifier Definitions

Item	Definition
FBNAc	The field sample had no detects, therefore the corresponding trip blank/field reagent blank was not analyzed.
J	Result is between LOD and LOQ and considered to be within a region of less-certain quantitation.
ND	Analyte NOT DETECTED at or above the LOD or MRL.
LOD	Limit of Detection.
LOQ	Limit of Quantitation.
NA	Not Applicable.
Dry	Dry Weight Basis.
Wet	Wet Weight Basis.
% Dry	Equal to: (mg/kg dry) / 10000.
1000 ug/L	Equal to: 1 mg/L.
MCL	Maximum Contaminant Levels for Drinking Water Samples. Shaded results indicate >MCL.
RPD	Relative Percent Difference.
%REC	Percent Recovery.
Source	Sample that was matrix spiked or duplicated.

All LOD/LOQs adjusted to reflect preparation volumes, dilutions, and/or solids content.

9

The contents of this report apply to the sample(s) analyzed in accordance with the chain of custody document.
No duplication of this report is allowed, except in its entirety.

Chain of Custody

PASI Green Bay Laboratory

Workorder: 40314716 **Workorder Name:** MRL #03244 PW-26 **Results Requested By:** 7/13/2026

Report / Invoice To	Subcontract To
Cindy Varga Pace Green Bay 1241 Bellevue Street Suite 9 Green Bay, WI 54302 Phone (920)469-2436 Email: cindy.varga@pacelabs.com	Northern Lake Services Inc 400 N. Lake Avenue Crandon, WI 54520

Send Invoice To: invoices@pacelabs.coupahost.com

State of Sample Origin: WI LOD/LOQ

CE06986

Item	Sample ID	Collect Date/Time	Lab ID	Matrix	Preserved Containers: ascorbic/hcl	Requested Analysis: 524 VOCs NR507 APP III	LAB USE ONLY
1	GREIDANUS (PW-26)	06/25/2026 13:15	40314716001	Water	3	X	
2							
3							
4							
5							

Transfers	Released By	Date/Time	Received By	Date/Time
1	[signature] Courtney Law		[signature]	6/30/26 1145 FE
2				
3				

Comments

see attached list
landfill compliance
Trip Blank on WO 40314710

Cooler Temperature on Receipt 0.0 °C (B) | Custody Seal Y or N | Received on Ice (Y) or N | Samples Intact (Y) or N

Preservation Confirmed for non NIS Bottles MV

Monday, June 29, 2026 8:12:48 AM
Dates and times are displayed using (-05:00) America/Chicago.

524 NR507 App III

Acetone
Benzene
Bromodichloromethane
Bromoform
Bromomethane
Carbon disulfide
Carbon tetrachloride
Chlorobenzene
Chloroethane
Chloroform
Chloromethane
Dibromochloromethane
Dibromomethane
1,2-Dichlorobenzene
1,3-Dichlorobenzene
1,4-Dichlorobenzene
Dichlorodifluoromethane
1,1-Dichloroethane
1,2-Dichloroethane
1,1-Dichloroethylene
cis-1,2-Dichloroethylene
trans-1,2-Dichloroethylene
1,2-Dichloropropane
cis-1,3-Dichloropropylene
trans1,3-Dichloropropylene
Ethylbenzene
Methylene chloride
Methyl ethyl ketone
Methyl tert butyl ether
Napthalene
Styrene
Tetrachloroethylene
Tetrahydrofuran
Toluene
1,2,4-Trichlorobenzene
1,1,1-Trichloroethane
1,1,2-Trichloroethane
Trichloroethylene
Trichlorofluoromethane
Vinyl chloride
Xylene(total)