Phone: 414.282.1800

2:42 LTE

GAIDISH FOUNDATION COMPANY Basement Waterproofing

WATERPROOFING & FOUNDATION SPECIALISTS

1572 E. Bolivar • St. Francis, WI 53235 • (414) 282-1800 • gaidishfoundation@gmail.com

OWNER Jim Risqw PHONE

ADDRESS W179S6711 Muskego Dr CITY Muskego DATE 7/23/26

CONSTRUCTION	JOIST SIZE	COURSES	DEPTH	DRAIN TILE	SUMP PUMP
Block	2x8	11	85"	?	Yes

ANALYSIS Owner has concerns with movement of one wall only. Wall bowed up to 3" out of plumb with susbtantial block seperation. Remainder of walls unknown. If portions of block have to be replaced/rebuilt addit'tional charge may be needed.

[redacted] A

OUTSIDE EXCAVATION METHOD

- ☑ EXCAVATE TO FOOTINGS AND HAUL AWAY CLAY
- ☑ STRAIGHTEN WALLS AS MOST REASONABLY POSSIBLE AND TUCKPOINT MAJOR CRACKS
- ☑ SEAL WALL WITH SEALMASTIC WATERPROOFING
- ☑ CLEAN OUT EXPOSED BLEEDERS AND INSTALL NEW 4" EXTERIOR DRAIN TILE
- ☑ BACKFILL 80% WITH LIGHTWEIGHT #1 CLEAR STONE (100% UNDER CONCRETE)
- ☑ COVER STONE WITH FILTERING FABRIC AND ADD BLENDED TOPSOIL FOR PROPER SLOPE AWAY
- ☑ TIE INTO RIOR DRAIN TILE - ANY FAILED TILE CAN BE REPLACED FOR $ 80.00 PER LINEAR FOOT
- ☑ STABILIZE WALL PER WALL STABILIZATION METHOD

100% GUARANTEED

WALL STABILIZATION METHOD

☐☐☐☐ B

- ☑ INSTALL 3 X 5 STEEL WALL MEMBERS PER WAFRP STANDARDS-EVERY 30 to 36 inches
- ☑ CHIP OUT AND TUCK POINT OPEN MORTAR JOINTS
- ☑ 100% GROUT FILL BEHIND BRACES WITH MORTAR

Note: All Gaidish's wall braces have galvanized bottom plates to prevent rust

INSIDE DRAIN TILE METHOD

////////// C

- ☐ REMOVE FLOOR SECTION APPROXIMATELY 12" TO 16" WIDE FROM WALL AND OLD DRAIN TILE
- ☐ CLEAN EXPOSED BLEEDERS TO EXTERIOR DRAIN TILE ☐ DRILL BLOCK CORES AND TEST FLOW
- ☐ INSTALL NEW DRAIN TILE & CONNECT TO EXISTING SYSTEM ☐ INSTALL PREMIUM WALL DRAIN BOARD
- ☐ COVER DRAIN TILE WITH PROPER FILTERING STONE ☐ REPLACE FLOOR AREA REMOVED

Retaining Wall



- Gaidish to excavate walls at [redacted] as described above.
- Gaidish to reinforce walls at ▭ as described above.
- Gaidish to remove retaining wall for excavation. No replace.
- Gaidish to remove concrete as needed for excavation. No replace.
- Owner to remove railings & garage-side of plant beds for equipment to get through.
- Owner to remove section of plant beds next to driveway if wanted. Otherwise Gaidish to cover & drive over with machinery.
- Gaidish to supply permit.
- All work done per WAFRP standards.

Starting Date ASAP Completion Date

GAIDISH GUARANTEES FOR A PERIOD OF 30 YEARS TO SERVICE ANY DEFECTIVE WORK, INCLUDING LABOR & MATERIALS.

WALL STABILIZATION DOES NOT WARRANT AGAINST SETPAGE.

DRAIN TILE REPAIR DOES NOT WARRANT AGAINST SETPAGE OR DAMPNESS ABOVE 1ST COURSE OF BLOCK ABOVE COVE.

FAILURE DUE TO IRON OCHRE CONTAMINATION NOT COVERED UNDER WARRANTY

TOTAL COST	$ 13,050.00
DEPOSIT	$ 500.00
3.5% CREDIT CARD FEE	
BALANCE	$ 12,550.00

FOR GAIDISH FOUNDATION Jason Huber

Note: This proposal may be withdrawn by us if not accepted within 30 days.

I HAVE READ THE REVERSE SIDE OF THIS PROPOSAL AND UNDERSTAND THIS AGREEMENT IS SUBJECT TO THOSE CONDITIONS. THE CONDITIONS, SPECIFICATIONS, PRICES AND TERMS ARE SATISFACTORY AND HEREBY ACCEPTED. OBSTRUCTION NOT MOVED PRIOR TO REPAIR THAT WERE OWNERS RESPONSIBILITY SHALL BE MOVED BY GAIDISH AT COST OF TIME WILL BE BILLED AT $65 PER MAN HOUR AND MATERIAL.

Signature Date Signature Date

WHITE - OFFICE COPY YELLOW - SHOP COPY PINK - CUSTOMER COPY

TERMS AND CONDITIONS

BUYER TESTIFIES THAT HE IS THE LEGAL OWNER OF THE PREMISES ON WHICH LABOR AND MATERIALS ARE